

EMD Shale Gas and Liquids Committee Annual Report, FY 2014

Neil S. Fishman, Chair

March 30, 2014

Vice Chairs:

- Brian Cardott, (Vice Chair, Government), Oklahoma Geological Survey, Norman, OK
- Harris Cander (Vice Chair, Industry), BP, Houston, TX
- Sven Egenhoff, (Vice Chair, University), Colorado State University, Fort Collins, CO

Advisory Committee (in alphabetical order):

- Kent Bowker, Bowker Petroleum, The Woodlands, TX
- Ken Chew, IHS (retired), Perthshire, Scotland
- Thomas Chidsey, Utah Geological Survey, Salt Lake City, UT
- Russell Dubiel, U.S. Geological Survey, Denver, CO
- Catherine Enomoto, U.S. Geological Survey, Reston, VA
- William Harrison, Western Michigan University, Kalamazoo, MI
- Ursula Hammes, Bureau of Economic Geology, Austin, TX
- Shu Jiang, University of Utah, Salt Lake City, UT
- Margaret Keller, U.S. Geological Survey, Menlo Park, CA
- Julie LeFever, North Dakota Geological Survey, Grand Forks, ND
- Peng Li, Arkansas Geological Survey, Little Rock, AR
- Jock McCracken, Egret Consulting, Calgary, AB
- Stephen Nordeng, North Dakota Geological Survey, Grand Forks, ND
- Rich Nyahay, New York Museum, Albany, NY
- Stephen Sonnenberg, Colorado School of Mines, Golden, CO
- Michael D. Vanden Berg, Utah Geological Survey, Salt Lake City, UT
- Rachel Walker, Countrymark Energy Resources, LLC, Indianapolis, IN

INTRODUCTION

It is a pleasure to present this Annual Report from the EMD Shale Gas and Liquids Committee. This report contains information about specific shales across the U.S., Canada, Europe, China, as well as SE Asia from which hydrocarbons are currently being produced or shales that are of interest for hydrocarbon exploitation. The inclusion in this report of shales from which any hydrocarbon is produced reflects the expanded mission of the EMD Shale Gas and Liquids Committee to serve as a single point of access to technical information on shales regardless of the hydrocarbons produced from them (e.g., gas, oil, condensate). Given the intense interest in shales as “unconventional” hydrocarbon reservoirs, this report contains information available at the time of its compilation, and the reader is advised to use links provided herein to remain as up-to-date as possible. The price of natural gas,

however, has affected gas production in many of the plays in the U.S., which is clear from information provided in several of the sections below.

This report is organized so that the reader can examine contributions from members of the EMD Shale Gas and Liquids Committee on various shales in the United States (presented in alphabetical order by shale name or region), Canada (by province), Europe (by country), China, and other parts of Asia. Additional sections of the report include Valuable Links, Additional Sources of Information, and a Gas Shales and Shale Oil Calendar.

The leaders of this committee are interested in your feedback. Please feel free to contact Neil Fishman (nfishman@hess.com) with your comments and suggestions.

Antrim Shale (Devonian), Michigan Basin, U.S.

By Dr. William B. Harrison, III (Western Michigan University)

The Michigan Basin Antrim Shale play is currently 27 years old, having begun the modern phase of development in 1987. The total number of producing wells drilled in the play through end of October, 2013 is approximately 11,550 with about 9,672 still online. Total cumulative gas production reached 3.216TCF by the end of October, 2013. Michigan Antrim production is reported by project rather than by individual well or lease. Projects may be only a few wells or more than 70 wells. There were 768 separate projects at the end of October, 2013. Cumulative production for first 10 months of 2013 was 84,525,378 MCF, which was a 1.45% decline from the same period in 2012.

There were 30 operators with production at the end of October, 2013. There were 9,672 wells online at the end October, 2013. There were 111 new wells drilled in 2009, only 58 in 2010, 13 drilled in 2012 and 5 new wells drilled in 2013. That is a 48% decrease in wells drilled from 2009 to 2010, a continuing drop of 33% in 2011, a 78% drop in 2012 and 61% in 2013. Overall drilling activity in Michigan was down 2% in 2012 compared to 2011. Most of the production comes from a few operators. The top 10 operators produced 82.5% of the total Antrim gas in 2013.

Although some wells can initially produce up to 500 MCF/day, generally wells settle at less than 100 MCF/day. Play wide average production at the end of October, 2013 was 28 MCF/day per well. Many Michigan Antrim wells begin with high water production and begin to increase gas production as the water is pumped off. Water production generally continues throughout the project life, although it usually declines through time. Play wide gas to water production ratio reached almost 3 MCF/BBL in 1998, in 2004 it was 2.21 MCF/BBL, the 2009 ratio is 1.56 MCF/BB, the 2011 the ratio was 1.57 MCF/BBL and the ratio was 1.60 MCF/BBL through October, 2013. Play wide water ratios have begun to decrease relative to gas production as old wells are dewatered and very few new wells are being drilled.

CO₂ is also an issue in the produced Antrim gas that is mostly of biogenic origin. Most wells begin with very low amounts of CO₂ in the produced gas; however, the percentage of CO₂ increases through time. Some projects that have a long production history may now exceed 30% CO₂ in the produced gas. The play wide average was just over 12.5% CO₂ in 2012.

Wells produce from depths as shallow as 350 feet to just over 3,000 feet, although the vast majority of wells are completed from 1,000 to 2,500 feet deep. Wells are typically drilled with water and an attempt is made to keep the well in balance or slightly under-balanced. Wells are fraced with water and sand. Some wells are fraced using nitrogen or foam.

Production and well data is available online at the Michigan Public Service Commission at <http://www.cis.state.mi.us/mpsc/gas/prodrpts.htm>

Various kinds of oil and gas information is also available at the Michigan Office of Geological Survey site at http://www.michigan.gov/deq/0,1607,7-135-3311_4111_4231---,00.html

Cores, samples and other kinds of data are available at the Michigan Geological Repository for Research and Education at Western Michigan University. That website is <http://wst023.west.wmich.edu/MGRRE%20Website/mgrre.html>

Top 10 Operators, Antrim Shale:
Linn Operating, Inc.
Chevron Michigan LLC
Terra Energy Ltd
Breitburn Operating Limited Partnership
Ward Lake Energy
Muskegon Development Co.
Trendwell Energy Corp
Jordan Development Co. LLC
Merit Energy Co.
Delta Oil Co. Inc.

Significant Trends – New drilling has almost ceased during 2011 through 2013 due to low gas prices. Production continues to decline as do the total number of active wells. Daily gas production per well declined by 1.45% in the first 10 months of 2013. However, daily water production per well decreased 5.67% in 2013 compared to the same period in 2012. The numbers of horizontal completions still represent less than 5% of total wells.

Bakken Formation (Upper Devonian-Lower Mississippian), Williston Basin, U.S.

By Julie LeFever and Stephan Nordeng (North Dakota Geological Survey)

In 2008, the United States Geological Survey (USGS) used a standardized assessment regime that concluded that the Bakken Petroleum System in the entire Williston Basin contains an undiscovered 3.65 BBbls of oil, 1.85 trillion cubic feet of natural gas, and 148 million barrels of natural gas liquids that are technically recoverable with current technologies (Pollastro and others, 2008). The North Dakota Department of Mineral Resources (Bohrer and others, 2008) estimates that, within the North Dakota portion of the Williston Basin, the Bakken Formation contains 2.3 BBbls of recoverable oil in place (OIP) and the underlying Three Forks Formation contains an additional 2.1 BBbls (Nordeng and Helms, 2010). A re-assessment of the Bakken Petroleum System is currently underway by the USGS with an expected publication date September 2013, although an update is expected to be provided at the AAPG Annual Meeting in Pittsburgh.

Development of Elm Coulee Field in 1996 resulted from the first significant oil production from the middle member of the Bakken Formation. Production from the middle member was established in the Kelly/Prospector #2-33 Albin FLB following an unsuccessful test of the deeper Birdbear (Nisku) Formation. Subsequent porosity mapping outlined a northwest-southeast trending stratigraphic interval containing an unusually thick dolomitized carbonate shoal complex within the middle member. Horizontal wells drilled through this shoal complex in 2000 resulted in the discovery of the giant Elm Coulee Field in eastern Montana. As with the previous Bakken producing fields, production at Elm Coulee depends on fracturing but in this case the productive fractures are found in the middle member of the formation. Since its discovery, more than 600 horizontal wells have been drilled in the 450-square-mile field from which more than 94 MMBbls of oil have been recovered. The productive portions of the reservoir contains between 3 and 9 percent porosity with an average permeability of 0.04 md. A pressure gradient in the Bakken of 0.53 psi/ft indicates that the reservoir is overpressured. Laterals are routinely stimulated by a variety of sand-, gel- and water-fracturing methods. Initial production from these wells is between 200 and 1900 BOPD (Sonnenberg and Pramudito, 2009).

The Bakken middle member play moved across the line into North Dakota when Michael Johnson noted that wireline logs of the Bakken Formation along the eastern limb of the Williston Basin in Mountrail County, North Dakota resembled those from Elm Coulee. Even though the kerogen within the Bakken shales appeared immature and thus might not be generating oil, free oil in DSTs and some minor Bakken production encouraged Johnson to pursue a Bakken play in Mountrail

County (Durham, 2009). In 2005, EOG Resources demonstrated with the #1-24H Nelson-Farms (SESE Sec. 24, T156N, R92W) that horizontal drilling coupled with large scale hydraulic fracture stimulation of the middle Bakken Formation could successfully tap significant oil reserves along the eastern flank of the Williston Basin. In the following year, EOG Resources drilled the #1-36 Parshall and #2-36 Parshall which resulted in wells with initial production rates in excess of 500 BOPD. Well stimulation of the early wells typically involved large single stage fracs using over 2 million pounds of proppant and over a million gallons of water. More recently single stage fracture stimulations have been replaced by multistage stimulations. These fracture the lateral with similar amounts of fluid and proppant but that is distributed over 10 to 40 or more separate stages. In a few instances, different laterals in the same well as well as laterals in adjacent wells are stimulated at the same time. Whiting Oil & Gas Corp. has installed a microseismic array in the Sanish Field in order to better visualize the real-time generation of induced fractures during stimulation process.

Subsequent horizontal drilling coupled with staged fracture stimulation has resulted in wells with IPs in excess of 2,000 BOPD. The Parshall field is currently averaging 779 MBbls of oil per month from 233 wells. Sanish Field, next to Parshall, is averaging 1.5 MMBbls of oil/month from 331 wells.

Over 354.5 million bbls of oil have been recovered from the 3,157 wells in the 240 middle Bakken producing fields put into service since 2004. The 882 horizontal wells drilled into the Three Forks Formation since 2006 have produced a total of 71.5 million bbls of oil. Currently there are 173 fields with Three Forks production. Sixty-eight wells have been completed in both the Bakken and Three Forks Formations. The majority of these wells were drilled in 2010.

The increase in information from recent drilling has resulted in the definition of a new member of the Bakken Formation called the Pronghorn. Additionally, to conform to adjoining states and provinces the original members have been formalized. New standard subsurface reference sections have also been designated. The formation now consists of four members, including: Upper; Middle; Lower; and Pronghorn.

As the play moves into the production phase, multiple wells are now drilled from single pads with a closed mud system to minimize the footprint. Also, there has been an increase in the number of acquisitions. The latest is the purchase of Denbury's Bakken holdings by Exxon-Mobil.

The North Dakota portion of the Williston Basin is extremely active with 186 rigs running. The top 10 producers in the play are:

1. EOG Resources (405 wells; up from 267)
2. Whiting Oil and Gas Corporation (360 wells; up from 161 wells)
3. Hess Corporation (473 wells; up from 172 wells)
4. Continental Resources, Inc. (480 wells; up from 210 wells)
5. Marathon Oil Company (280 wells; up from 177 wells)
6. Slawson Exploration Company, Inc. (139 wells; up from 73 wells)
7. Brigham Oil & Gas, L.P. (194 wells)
8. Burlington Resources Oil & Gas Company, LP. (165 wells; up from 92 wells)
9. XTO Energy Inc. (112 wells; up from 83 wells)
10. Petro-Hunt, LLC (188 wells)

Additional Information:

The Bakken Source System was the focus of this past year's Williston Basin Petroleum Conference. The materials presented are available at the following link:

<http://ndoil.org/?id=279&page=2012+WBPC+Presentations>

North Dakota Geological Survey Website:

<https://www.dmr.nd.gov/ndgs/bakken/bakkenthree.asp>

Recent Publications:

First 60 - 90 Day Average Bakken Horizontal Production by Well Available: North Dakota Geological Survey: Geological Investigations 149
LeFever, J.A., Nordeng, S.H., T. Nesheim, 2012, Core Workshop Booklet: North Dakota Geological Survey Geological Investigations 155
LeFever, J.A., and S.H. Nordeng, 2012, Preliminary Report on the Bakken Formation, North-Central ND: North Dakota Geological Survey Geological Investigations 156.
S.H. Nordeng and L.D. Helms, 2010, Bakken Source System: Three Forks Formation Assessment: <https://www.dmr.nd.gov/ndgs/bakken/bakcenthree.asp>


Barnett Shale (Mississippian), Fort Worth Basin, U.S.

By Kent Bowker (Bowker Petroleum, LLC)


Daily gas production from the primary Barnett field (Newark, East) continues to decline but at a rate less than might have been expected given the decrease in drilling and completion activity over the past five years. The current daily gas production is right at 5 BCF while oil/condensate production is at 9300 bbls.

The total producing-well count in Newark, East field is 17,494; roughly 10,000 of those wells were drilled in the past five years. There are approximately 19,200 total Barnett wells in the Fort Worth basin (in several fields) and 14,400 of those are horizontal producers. The number of permits issued for the field has dropped to a rate of 700/year, well below the 4065 permits that were issued in 2008.

Newark, East (Barnett Shale)
Total Natural Gas
1993 through 2013




http://www.rrc.state.tx.us/barnettshale/NewarkEastField_1993-2013.pdf



(used with permission of Gene Powell)

Newark, East (Barnett Shale) Well Count 1993 through December 13, 2013



http://www.rrc.state.tx.us/barnettshale/barnettshalewellcount_1993-2013.pdf

Barnett Shale Annual Daily Average to 1-1-2014			
Year	Total Gas Per Day MCFGPD	Total Condensate/Oil Per Day BOPD	Drilling Rig Count Average
2003	861,518	5,698	47
2004	1,080,271	6,123	61
2005	1,430,783	6,518	101
2006	2,039,992	7,148	142
2007	3,144,209	8,193	175
2008	4,617,514	9,565	183
2009	5,088,198	9,255	81
2010	5,271,068	11,555	86
2011	5,958,680	33,002	69
2012	5,702,415	25,492	48
2013	5,224,193	21,287	31

Used with permission of Gene Powell

The current rig count in the Barnett is 26 in 14 counties, which is a drop of 10 from the count six months ago. The more liquids-rich portions of the play (Montague, Denton and northern Wise counties have the bulk of the rigs in the Barnett, as noted in the Powell Shale Digest - www.shaledigest.com). Devon continues to be the most active operator in the play.

Over the past several months there has been a growing concern about the increase in earthquakes near the small town of Azle, northwest of Fort Worth. The earthquakes have all been less than magnitude 4, but several have been felt by residents in the area. There is a possibility that Class II (oil-field) waste-water injection wells could be the cause of these temblors. In response to these events, the Texas Railroad Commission has begun the process to hire a staff seismologist to help evaluate the possible seismic hazards of Class II injection wells (<http://www.rrc.state.tx.us/pressreleases/2014/010714.php>), which the Commission regulates. Southern Methodist University, in conjunction with the USGS (http://www.usgs.gov/blogs/features/usgs_top_story/man-made-earthquakes), has also recently announced a scientific investigation into the earthquakes around Azle (<http://smu.edu/smunews/earthquakestudy/>). A detailed map showing the epicenters of the earthquakes and the locations of Class II injection wells in the area can be found here http://www.shaledigest.com/documents/2014/earthquakes/AZLE_PP_MAPS_012114.pdf. As seen in the map, there is some uncertainty as to the actual epicenters and foci of the earthquakes; these uncertainties will be addressed as part of the SMU study. SMU researchers have cautioned that it could take years to determine the cause of the earthquakes. Interestingly, the USGS has reported only one earthquake in the area (M 2.5) since January 1.

Eagle Ford Group (Cretaceous), Gulf Coast Basin, U.S.

Russell Dubiel (U.S. Geological Survey)

The Cretaceous (Cenomanian-Turonian) Eagle Ford Shale of southwest Texas continues as an important play producing thermogenic gas, oil and condensate. The Eagle Ford play trends across Texas from the area of the Maverick Basin, northeast into the Karnes Trough, where it is variably a target for dry gas, wet gas/condensate, or oil. The wells that have been completed display a steady decline in production similar to those in other shale plays. As for shale oil wells, recently drilled wells have shown initial production rates of several hundreds to as much as 1000 BOPD. As of September, 2012, there were 2,093 oil wells, 817 gas wells, and 4,976 permitted wells in Eagle Ford (Railroad Commission of Texas). The trend occurs at an average depth of 11,000 feet, and it is over-pressured.

As with the Barnett and Haynesville Shales, the Eagle Ford is a viable target for hydrocarbon exploitation because of advances in the application of horizontal drilling and fracturing procedures. Mineralogy of the Eagle Ford is somewhat different than other gas shales, however, in that where it is being explored, the Eagle Ford contains significant marlstone beds that are brittle and enhance the opportunity for induced fractures. Most operators are drilling horizontal well laterals of 3,500 to 5,000 feet and are fracing the wells with slick water or acid in at least 10 different stages. For more information on Eagle Ford production, please refer to the Texas Railroad Commission web link at <http://www.rrc.state.tx.us/eagleford/>.

Continued activity and success in the Eagle Ford in Texas has generated renewed interest in the laterally equivalent Cenomanian-Turonian Tuscaloosa marine shale in eastern Louisiana and southern Mississippi. Initial exploration in the Tuscaloosa Marine Shale in the 1970's has been followed by minimal exploration and production in the 1980's, 1990's and early 2000's. In 2010 and 2011, several companies began significant leasing in eastern Louisiana and southern Mississippi. Over the last twenty-four months, those companies have begun exploratory and initial development drilling for the Tuscaloosa marine shale, based in part on the current higher price for oil, corresponding low price for natural gas, and the recent horizontal drilling success in the Eagle Ford in Texas, as well as a historical record of hydrocarbon generation and proven, but minimal, production from the unit. The trend averages about 12,000 to 15,000 ft and is overpressured. During 2011 and 2012, several companies have drilled successful horizontal wells; 15 oil wells have come on line in northeast Louisiana and southern Mississippi. Reported IPs are encouraging in the neighborhood of several hundred BOPD, but currently only minimal yearly production data is available to evaluate the play's future success. A summary of play history and a discussion of recent leasing and exploration trends can be found in the August 2011 issue of the AAPG Explorer:

<http://www.aapg.org/explorer/2011/08aug/tuscaloosa0811.cfm>.

In depth discussions of the nuances of the Tuscaloosa marine shale can be found on a blog maintained by Kirk Barrel of Amelia Resources: <http://www.tuscaloosatrend.blogspot.com/>.

Fayetteville Shale (Mississippian), Arkoma Basin, U.S.

By Peng Li (Arkansas Geological Survey)

The Upper Mississippian Fayetteville Shale play is the current focus of a regional shale-gas exploration and development program within the central and eastern Arkoma Basin of Arkansas. Approximately 2.5 million acres have been leased in the Fayetteville Shale gas play (Figure 1). Production of thermogenic gas from the Fayetteville began in 2004 and continues to the present.

U.S. Energy Information Administration (EIA) reports in 2011 that the Fayetteville contains 31.96 Tcf of technically recoverable gas resource, in which 27.32 Tcf is attributable to the core producing area (aka eastern area) and 4.64 Tcf for the uncore producing area (aka western area). EIA also reports that the proved gas reserves of the Fayetteville Shale in 2011 is 14.8 Tcf, 2.3 Tcf of increase from the 2010 estimates. Estimated ultimate recovery (EUR) for a typical horizontal Fayetteville gas well increases from 1.8 Bcf in 2008 to 3.2 Bcf in 2011 (OGJ, 2012).

Estimated cumulative production of gas from the Fayetteville Shale as of November 2013 has totaled 4,569,552,339 Mcf from 5,060 wells. For the period of January through November 2013, Fayetteville Shale zone has yielded 942,951,674 Mcf dry gas from 4,843 wells. Annual production of Fayetteville Shale for 2012 is 1,027,711,866 Mcf from 4,434 wells. The daily production has amounted to 2.6 Bcf in 2012. Initial production rates of horizontal wells have recently averaged about 3,136 Mcf/day. Notably, even in the face of the challenging gas price environment in 2011 and 2012, production from the Fayetteville continued to grow at a fast clip, increasing by over 21% since January 2011. For more Fayetteville Shale production information, please refer to the Arkansas Oil and Gas Commission (AOGC) web link at <http://www.aogc.state.ar.us/Fayprodinfo.htm>.

Like other dry gas plays, the Fayetteville has seen a dramatic decline in its rig count. According to Baker Hughes (BHI), the number of gas-directed rigs active in the play has dropped

from 33 rigs in February 2011 to just 9 rigs in February 2014. The continued production growth, in spite of the sharply lower rig count, is explained by the truly remarkable gains in rig productivity and operating efficiencies as the transition towards the full development mode in many areas is beginning to bear fruit. Since 2013, Southwestern Energy has drilled its average well in just 6.5 days, re-entry to re-entry, compared to 11 days in 2010. The comparison is even more impressive given that the average length of the lateral is expected to increase by over 10%.

Fayetteville Shale reports from the AOGC have noted well increases from 24 in 2004, 33 in 2005, 129 in 2006, 428 in 2007, 587 in 2008, 839 in 2009, and 874 in 2010. Since then the numbers of new completed wells declined in three consecutive years, with 829 in 2011, 675 in 2012, and 557 in 2013. As of February 2014, there are a total of 5,087 producing gas wells in the Fayetteville Shale play. Most Fayetteville Shale wells are drilled horizontally and have been fracture stimulated using slickwater or cross-linked gel fluids. Baker Hughes' FracPoint Multi-stage fracturing system has provided most of the hydraulic fracturing completions in the Fayetteville Shale. Completed lateral length has increased 82% over the last four years while holding total well costs flat at about \$ 2.8 million. Horizontal wells drilled from 2010 to 2012 averaged 5,600 feet in lateral length with some wells up to 8,000 feet. Fayetteville Shale gas production generally ranges over a depth between 1,500 to 6,500 feet. The thickness of Fayetteville Shale varies from 50 feet in the western portion of the Arkoma Basin of Arkansas (fairway area) to 550 feet in the central and eastern regions (primary producing area).

Since the play's inception, the Fayetteville Shale play has been dominated by a small number of large players. Three operators -- Southwestern, BHP Billiton, and XTO Energy (a subsidiary of Exxon Mobil) -- accounted for over 99% of gross operated production from the field. The three companies hold close to 2 million net acres under lease in the play. Southwestern, with 925,000 net acres and more than three thousand producing wells, is by far the largest operator among the three companies, and accounts for about two-thirds of the field's total production volume. Exxon and BHP are approximately equal in terms of their acreage and gross operated production. During 2012, Southwestern contributed 724.8 Bcf in Fayetteville gas sales, good for 70.3% of the play's total sales that year. BHP sold 155.7 Bcf (15.1%) and XTO Energy sold 147.9 Bcf (14.3%). The remaining 0.3% of sales, or 2.4 Bcf, was spread out among nine companies.




Figure 1. Primary area of the Fayetteville Shale exploration and development in Arkansas.

The top three operators of the Fayetteville gas shale play as of February 2014 based on numbers of producing wells are as follows (Figure 2):

- 1) SEECO Inc. (an exploration subsidiary of Southwestern Energy) (3,264 wells)
- 2) BHP Billiton Petroleum (965 wells)
- 3) XTO Energy, Inc. (a subsidiary of ExxonMobil) (817 wells)

Two different maps are available that illustrate the location and types of wells located in the Fayetteville Shale producing area. Web links for the Fayetteville Shale maps and the associated federal and state agencies are listed below:

(1) The home page of the Arkansas Geological Survey (AGS) website is: <http://www.geology.arkansas.gov/home/index.htm> and the AGS Fayetteville Shale well location maps can be viewed at http://www.geology.arkansas.gov/home/fayetteville_play.htm. AGS updates these maps and associated well database (in Excel® format) online every two weeks.

(2) The home page of the U.S. Energy Information Administration (EIA) website is: <http://www.eia.doe.gov/> and the EIA Fayetteville Shale map is available at http://www.eia.doe.gov/pub/oil_gas/natural_gas/analysis_publications/maps/maps.htm.

Disposal of production well wastewater through injection wells has gradually mounted a concern in the Fayetteville Shale play area given thousands of recent area earthquakes. Most of the seismic events have been too small to be felt, and a majority of the epicenters form a northeast-southwest trending linear feature near the towns of Guy and Greenbrier in Faulkner County. These earthquakes have become known as the Guy-Greenbrier Swarm. It was recently discovered that the Guy-Greenbrier Swarm earthquakes occurred along and illuminate a previously unknown sub-surface fault, the Guy-Greenbrier Fault, located near the disposal wells. The fault, nearly 7.5 miles long, could theoretically generate an earthquake of around 6.0 in magnitude. In January 2011, the AOGC imposed a six-month moratorium on new injection wells in a portion of the Fayetteville Shale production area to determine what relationship, if any, there is between the wastewater injection and the earthquakes. The quakes intensified during the last two weeks of February 2011, culminating with a 4.7-magnitude earthquake near Greenbrier on February 27, 2011, the most powerful reported seismic event in Arkansas in 35 years. AOGC held a special meeting on March 4, 2011 to issue an emergency order immediately shutting down all injection operations of two disposal wells through the last day of the regularly scheduled hearing in March 2011. At the March 2011 hearing, AOGC ordered the companies to continue the cessation of all injection operations of these two wells for a period of an additional sixty days. During the July 2011 hearing, the AOGC requested an immediate and permanent moratorium on any new or additional disposal wells or disposal well permits in the moratorium area (Figure 3). At the time of the hearing, there were four disposal wells within the moratorium area, including the two wells that were shut down since March 2011. The frequency of the quakes within the moratorium area saw a significant decrease, about 75%, since the cessation of the injection operation of the disposal wells. This, in turn, gave more evidence to confirm a potential relationship between the injection activities and the earthquakes. Geohazards geologists at the AGS that monitor the earthquakes in the state provide the relevant information to the public and the AOGC.

Concerns about the effect of Fayetteville gas exploration and production on public health, air, water and land are increasing with the spread of hydraulic fracturing technology that is utilized in well completions. Expanded production and potential environmental impacts have increased the need for additional regulations related to all aspects of exploration and production. Arkansas joins Wyoming as the only states that require the full disclosure of all chemical constituents in all frac fluids and additives on a well-by-well basis and the release of these reports to the public. The AOGC's Rule B-19 (available on the AOGC website), which also protects the trade secrets behind proprietary compounds, went into effect January 15, 2011. AOGC also issued a revised surface casing and production casing cementing requirements for all Fayetteville Shale wells. All operators of such wells since June 1, 2011 are required to set surface casing to a depth equal to 500 feet below the lowest

ground surface elevation occurring within 1 mile of the proposed well, with a minimum of 1000 feet of surface casing to be set and cemented to surface. In addition, cement shall be circulated to the surface on all production casings, so as to isolate from all strata encountered in the wellbore above the Fayetteville Shale horizon.




Figure 2. Location map of the Fayetteville Shale producing wells by top 3 operators as of February 2014.

AGS has completed two extensive geochemical research projects on the Fayetteville Shale and has provided this information to the oil and gas industry and the public to assist with exploration and development projects. These studies are available at the Arkansas Geological Survey as Information Circular 37 (Ratchford et. al., 2006) and Information Circular 40 (Li et al., 2010) and integrate surface and subsurface geologic information with organic geochemistry and thermal maturity data.

The AGS continues to partner with the petroleum industry to pursue additional Fayetteville Shale related research. Ongoing AGS research is focused on the chemistry and isotopic character of produced gases, mineralogy of the reservoir, and outcrop to basin modeling.

Permanent Disposal Well Moratorium Area




Figure 3. Permanent moratorium area for disposal wells in the Fayetteville Shale Play, Arkansas (from the AOGC website).

Haynesville/Bossier Shale (Jurassic), Texas and Louisiana, U.S.

by Ursula Hammes (Bureau of Economic Geology, Austin, TX)

The Kimmeridgian Haynesville Shale spans more than 16 counties/parishes along the boundary of eastern Texas and western Louisiana. Basement structures and salt movement influenced carbonate and siliciclastic sedimentation associated with the opening of the Gulf of Mexico forming the Haynesville basin. The Haynesville shale is an organic- and carbonate-rich mudrock that was deposited in a deep, partly euxinic and anoxic basin during Kimmeridgian to early Tithonian time, related to a second-order transgression that deposited organic-rich black shales worldwide. The Haynesville basin was surrounded by carbonate shelves of the Smackover and Haynesville lime

Louark sequence in the north and west. Several rivers supplied sand and mud from the northwest, north, and northeast into the basin. Haynesville mudrocks contain a spectrum of facies ranging from more calcareous in the southern part of the productive area to more siliceous and argillaceous rich in the northern and eastern part of the productive area (Fig. 1; Hammes et al., 2011). Haynesville reservoirs are characterized by overpressuring, porosity averaging 8–12%, Sw of 20–30%, nano-darcy permeabilities, reservoir thickness of 200–300 ft (70–100m), and initial production ranging from 3 to 30 MMCFE/day (Wang and Hammes, 2010). Reservoir depth ranges from 9,000 to 14,000 ft (3000–4700 m), and lateral drilling distances are 3000– 5000 ft (1000–1700 m). Optimal frac stages are 12–16 with an optimum number of 15 with multiple perforation clusters (Wang et al., 2013).

Haynesville drilling permits and rig count showed an increase in Texas over Louisiana (Figs. 2–4). The Haynesville Shale in Texas and Louisiana experienced a slight revival during the last quarter because of higher prices for natural gas and more electricity and export demand in Louisiana. However, production fell to half from what was produced at its peak in 2011 (Fig. 5). Cumulative production reached 8.6 Tcf at the end of 2013 (Fig. 6). Liquids production is still increasing due to additional exploitation in Arkansas and parts of northern Louisiana (Fig.7). Additional information on the Haynesville can be found at the Louisiana Oil and Gas association <http://www.loga.la/haynesville-shale-news/>, accessed March 21, 2014.




Figure 1: Location of Haynesville Basin and productive zone of Haynesville Shale (red stippled pattern; from Hammes et al., 2011).

March 14, 2014			
All Haynesville/MBS Wells			
Operator	LA	TX	Total
Chesapeake	8	0	8
Anadarko	2	3	5
Exco Resources	3	2	5
Petrohawk	3	0	3
XTO Energy	0	3	3
J-W Operating	2	0	2
SWEPI LP	1	0	1
Total	19	8	27

Parish/County	14-Mar	7-Mar	28-Feb
DeSoto, LA	10	11	12
Panola, TX	4	4	5
Bossier, LA	3	3	2
Caddo, LA	3	1	1
Sabine, LA	2	2	1
San Augustine, TX	2	2	2
Shelby, TX	2	2	2
Red River, LA	1	1	1
Total	27	26	26

Figure 2: Rig counts for March 2014 (www.haynesvilleplay.com; accessed march 20, 2014)




Figure 3: Texas Haynesville well activity through March 2014.




Figure 4: Louisiana Haynesville well activity including unitized wells through March 2014.




Figure 5: Monthly production chart (MCF) through December 2013 for Haynesville Shale (data from IHS Enerdeq).





Figure 6: Cumulative production for Haynesville Shale through December 2013 Shale (data from IHS Enerdeq).



02/28/2014

Source: Railroad Commission of Texas Production Data Query System (PDQ)

Figure 7: Texas Haynesville Shale condensate production through December 2013 shows steady increase in liquids production.

References:

- Hammes, U., H.S. Hamlin, and T.E. Ewing, 2011, Geologic analysis of the Upper Jurassic Haynesville Shale in east Texas and west Louisiana: AAPG Bull., v. 95, p. 1643-1666.
- Hammes, U., and G. Frébourg, 2012, Haynesville and Bossier mudrocks: A facies and sequence stratigraphic investigation, East Texas and Louisiana, USA: Marine and Petroleum Geology (2011), doi: 10.1016/j.marpetgeo.2011.10.001.
- Wang, F.P., and U. Hammes, 2010, Effects of petrophysical factors on Haynesville fluid flow and production: World Oil, D79-D82.
- Wang, F.P., U. Hammes, and Q. Li, 2013, An overview of Haynesville Shale production, in, Hammes, U., and J. Gale, (2013): Geology of the Haynesville Gas Shale in East Texas and West Louisiana, USA: AAPG Memoir 105, p. 155-178.

Maquoketa and New Albany Shales, Illinois Basin

By Rachel Walker (Countrymark Energy Resources, LLC)

The 2013/2014 shale activity in the Illinois Basin continues to be limited due to poor gas prices, with some New Albany permitting and drilling taking place, largely within existing fields. No known Maquoketa related activity has occurred beyond the apparent initial leasing interest in 2011/2012.

Maquoketa Shale

Indiana: No Maquoketa wells have been permitted in Indiana since the last report in November 2013. There is no known production from the Maquoketa in Indiana.

Illinois: No Maquoketa wells have been permitted in Illinois since the last report in November 2013. While there has been speculation in the basin that several deep permitted wells may have been looking at the Maquoketa, there is little publicly available data to support this. There is no known production from the Maquoketa in Illinois.

Kentucky: No Maquoketa wells have been permitted in Kentucky since the last report in November 2013. There is no known production from the Maquoketa in Kentucky.

New Albany Shale

Indiana: In July 2013, Riverside Operating Co. permitted a New Albany well in the Plainville Field in Daviess County (not yet drilled). Riverside continues to operate 26 New Albany Shale gas wells in Daviess County, producing 3500 mcf/day. Although there are several existing NAS fields in Indiana, the Indiana Geological Survey does not have good records of New Albany gas production, so it is difficult to report on volume produced to date. A number of NAS fields were shut in when gas prices dropped and it is unclear when they will be operational again.

Illinois: Other than the Core Minerals New Albany well in the Salem Field of Marion County (drilled July 2013 and temporarily abandoned), there have been no further New Albany specific wells permitted in Illinois.

Kentucky: In May and June 2013, Endeavor Energy Resources permitted three New Albany wells in the Rockvale Consolidated Field in Breckinridge County (not yet drilled). In September 2013, Irvin Anderson Jr. permitted two New Albany wells - one in the Glen Dean Field and one in the McQuady Field, both in Breckinridge County (not yet drilled). In February 2014, GTC Land & Energy also permitted a New Albany well in the McQuady Field (not yet drilled). In March 2014, Trico-Tiger permitted a New Albany well in the Flaherty Field of Meade County (not yet drilled). Trico-Tiger have drilled and completed several New Albany wells in this area, testing between 163 and 360 MCFGPD at a very shallow 500-800' depth.

References

Indiana Department of Natural Resources, Division of Oil and Gas, Indianapolis, IN

Illinois Department of Natural Resources, Division of Oil and Gas, Springfield, IL

Commonwealth of Kentucky Department of Mines and Minerals, Division of Oil and Gas, Frankfort, KY

The Scout Check Report, LLC, Evansville, IN

Marcellus Shale (Devonian)—Appalachian Basin, U.S.

by Catherine Enomoto (U.S. Geological Survey, Reston, VA)

The Middle Devonian Marcellus Shale of the Appalachian Basin is the most extensive shale play in the U.S., covering about 66,600,000 acres (USGS Marcellus Shale Assessment Team, 2011). Extending from Tennessee to New York, the gross thickness of the Marcellus Shale increases to the northeast, with the thickest area located in northeastern Pennsylvania (Milici and Swezey, 2006; Wrightstone, 2009). The organic-rich zone of the Marcellus Shale has a net thickness of 50 to over 250 feet, and exists at drilling depths of 2,000 to 9,000 feet ((Milici and Swezey, 2006; Wrightstone, 2009). The organic-rich Marcellus Shale has high radioactivity responses, and thus high gamma ray values on well logs, because the organic matter tends to concentrate uranium ions (Harper, 2008). According to studies during and after the Eastern Gas Shales Project (EGSP), there is a strong relationship between higher-than-normal gamma ray response and total gas content in the black, organic-rich Marcellus Shale. In the majority of the currently productive area, the Marcellus Shale has a vitrinite reflectance between 1.0 and 2.5 %R_o (Milici and Swezey, 2006; Repetski and others, 2008; Ryder and others, 2013) and produces mostly natural gas. However, areas in southwest Pennsylvania, eastern Ohio, and northern West Virginia have reported condensate and oil production from wells in the Marcellus Shale. Published data indicates the total organic carbon content (TOC) of the Marcellus Shale is as high as 11% (Repetski and others, 2008).

As in other shale plays, horizontal drilling and hydraulic fracturing increase permeability which allows for commercial production of hydrocarbons from this formation. The orientation of the horizontal sections of the wells and the design of the staged hydraulic fracturing operations enhance the natural fracture trends in the Marcellus Shale. “Slick-water fracs” have provided the best method for recovering large volumes of natural gas efficiently. These use sand as a proppant and large volumes of freshwater that have been treated with a friction reducer such as a gel. The slick-water frac maximizes the length of the induced fractures horizontally while minimizing the vertical fracture height (Harper, 2008). Issues of water supply for large volume fracturing, and disposal of produced formation water and used hydraulic fracturing fluid, called “flow-back” fluid, are being studied, and have been addressed with a variety of approaches including recycling and reuse.

According to a report published by the U.S. Energy Information Administration (EIA) in February, 2014 (U.S. Energy Information Administration, 2014), which contained analyses of drilling data through January, 2014, and projected production through March, 2014, the number of rigs that completed wells in the Marcellus Shale decreased from over 140 per month on January 1, 2012, to about 100 per month, as of January 31, 2014. However, the daily gas production rate of new Marcellus Shale wells increased from less than 3 million cubic feet per day to over 6 million cubic feet per day for the same period. Including production declines in legacy wells, the total production from the Marcellus Shale is about 14 billion cubic feet (bcf) of gas per day and almost 50,000 barrels (bbls) of oil per day, as of January 31, 2014, according to the EIA report (U.S. Energy Information Administration, 2014).

In August, 2011, the U.S. Geological Survey (USGS) published Fact Sheet 2011-3092, “Assessment of undiscovered oil and gas resources of the Devonian Marcellus Shale of the Appalachian Basin Province” (Coleman and others, 2011). According to this publication, the USGS estimated a mean undiscovered, technically recoverable natural gas resource of about 84 trillion cubic feet (tcf) and a mean undiscovered, technically recoverable natural gas liquids resource of 3.4 billion barrels in continuous-type accumulations in the Marcellus Shale. The estimate of natural gas resources ranged from 43 to 144 tcf (95 percent to 5 percent probability, respectively), and the estimate of natural gas liquids resources ranged from 1.6 to 6.2 billion bbls (95 percent to 5 percent probability, respectively). This re-assessment of the undiscovered continuous resources in the Marcellus Shale updated the previous assessment of undiscovered oil and gas resources in the Appalachian Basin performed by the USGS in 2002 (Milici and others, 2003), which estimated a mean of about 2 tcf of natural gas and 11.5 million bbls of natural gas liquids in the Marcellus Shale .

The new estimates are for resources that are recoverable using currently available technology and industry practices, regardless of economic considerations or accessibility conditions, such as areas limited by policy and regulations. The Marcellus Shale assessment covered areas in Kentucky, Maryland, New York, Ohio, Pennsylvania, Tennessee, Virginia and West Virginia. In Figure 1, the extent of three assessment units (AU) defined in this latest assessment are shown. Ninety-six percent of the estimated resources reside in the Interior Marcellus AU.

The increase in undiscovered, technically recoverable resources is due to new geologic information and engineering data. In late 2004, the Marcellus Shale was recognized as a potential reservoir rock, instead of only a regional hydrocarbon source rock. Technological improvements resulted in commercially viable gas production and rapid development of this new play in the Appalachian Basin, the oldest producing petroleum province in the United States. According to the Pennsylvania Department of Conservation and Natural Resources, the first production from the Marcellus Shale was in 2005 by Range Resources in Washington County, PA, and the first horizontal wells in the Marcellus Shale were drilled in 2006. Natural gas production was reported from wells that were completed in the Marcellus Shale in West Virginia as early as 2007.

Maryland: There were no wells drilled in Maryland for the Marcellus Shale between 2004 and 2013. In 2009, four companies submitted applications for permits to drill Marcellus Shale wells. None of these applications were approved, and all of the applications were withdrawn by the companies. There is no reported production from the Marcellus Shale in Maryland. Due to the

estimated thermal maturity of the Marcellus Shale in Maryland (Repetski and others (2008)), it may be suggested that dry gas will be found if wells are drilled to the Marcellus Shale. The permit process to drill and produce natural gas from the Marcellus Shale in Maryland is under review. On June 6, 2011, the Governor of Maryland signed an Executive Order establishing the Marcellus Shale Safe Drilling Initiative. The Order required the Maryland Department of the Environment (MDE) and Department of Natural Resources (DNR) to undertake a study of drilling for and extracting natural gas from shale formations. In December, 2011, the MDE and DNR developed four recommendations regarding revenue and three recommendations regarding standards of liability. A report titled “Marcellus Shale Safe Drilling Initiative Study Part II, Best Practices (Draft for Public Comment)” is available on the MDE website. Comments were solicited and accepted through September 10, 2013. On September 25, 2013, the results of a survey completed by members of the Marcellus Shale Safe Drilling Initiative Advisory Commission indicating their agreement or disagreement with the recommended best practices was published on the MDE website. The results of this preliminary survey can be accessed at

http://www.mde.state.md.us/programs/Land/mining/marcellus/Documents/Survey_Commissioners_Final.pdf. A final report with findings including environmental impacts and recommendations will be issued no later than August 1, 2014.

New York: The Marcellus Shale extends into the northernmost part of the Appalachian basin in central New York. The organic-rich thickness of the Marcellus Shale increases from 20 feet in the west to 250 feet in the eastern part of the basin in New York (Smith and Leone (2010)). The depths of the Marcellus Shale range from zero to as much as 7,000 feet in the eastern part of basin in south-central New York (Smith and Leone (2010)). According to the New York Department of Environmental Conservation (DEC), there were 31 wells with Marcellus Shale listed as the productive formation, but only 15 reported production in 2012. Natural gas production from the Marcellus Shale in 2012 was 23.3 million cubic feet (Mcf), down from reported production of 25.6 Mcf in 2011, and down from the high of 64 Mcf reported for 2008. There was no reported oil production. According to the New York DEC, there were over 250 Mcf of gas produced from the Marcellus Shale between 2000 and 2012. The DEC also reported that between 1967 and 1999, there may have been as much as 543 Mcf of gas produced from the Marcellus Shale. A search of the NY DEC wells database returned 184 well permit applications where the objective formation was “Marcellus”. 37 of these wells have been drilled (correction from the last report), and all are vertical wells (correction from the last report). The NY DEC published a Preliminary Revised Draft Supplemental Generic Environmental Impact Statement (SGEIS) in July, 2011. Additional information was added and a Revised Draft SGEIS was released September 7, 2011. The public comment period ended January 11, 2012. DEC was required to refile the draft regulations covering high volume hydraulic fracturing. DEC held public hearings during the comment period for the SGEIS and for the regulations in November, 2012. The public comment period closed on January 11, 2013. While the process of reviewing the SGEIS is ongoing, any company that applies for a drilling permit for horizontal drilling in the Marcellus Shale will be required to undertake an individual, site-specific environmental review.

Ohio: The Ohio Department of Natural Resources (ODNR) reported that about 1.23 bcf of gas and over 17,700 bbls of oil were produced from the Marcellus Shale from 2007 through 2012. There were less than 30 wells that reported production from the Marcellus Shale in 2012. The productive wells were in Athens, Belmont, Jefferson, Meigs, Monroe, Noble, and Washington counties. According to the Ohio DNR, there were about 188 Mcf of gas and about 770 bbls of oil produced in 2012. This was a decrease from 2011, for which reported production was about 340 Mcf of gas and about 8,000 bbls of oil. As of March 1, 2014, 36 Marcellus Shale horizontal well permits were issued, 23 horizontal wells have been drilled into the Marcellus Shale, and 8 horizontal wells were producing from the Marcellus Shale. The horizontal Marcellus Shale wells reported as productive are in Belmont, Carroll, Jefferson and Monroe counties.




Figure 1. 2011 Marcellus Shale Assessment Units (modified from Coleman and others, 2011).

The maximum thickness of the Marcellus Shale in Ohio is 70 feet, and the average thickness is about 40 feet in the prospective area in easternmost Ohio. The Ohio Geological Survey published a map of the area of potential within the Marcellus Shale (<http://geosurvey.ohiodnr.gov/energy-resources/marcellus-utica-shales>), which includes the counties of Ashtabula, Trumbull, Mahoning, Columbiana, Carroll, Jefferson, Harrison, Belmont, Guernsey, Monroe, and Washington. The ODNR Division of Oil and Gas Resources Management Division has draft rules pertaining to horizontal well site construction available for review and comment at <http://oilandgas.ohiodnr.gov/oil-gas-home/post/draft-rules-review>.

Pennsylvania: The Marcellus Shale is deepest in east-central Pennsylvania, and the deepest wells to test the Marcellus Shale have been drilled to 8,500 feet in Clinton County. The areas of greatest activity in the Marcellus Shale are in southwestern and northeastern Pennsylvania. The production of oil and condensate from fields in southwest Pennsylvania made this area attractive to operators. Pennsylvania has continued to be the state with the most drilling into, and production from, Marcellus Shale. According to the Pennsylvania Department of Conservation and Natural Resources (DCNR) and Department of Environmental Protection (DEP), as of March 2014, the counties with the most drilling and production activity in the Marcellus Shale were Greene, Washington, Fayette, Lycoming, Tioga, Bradford, Wyoming and Susquehanna. According to the Pennsylvania DEP, 2,976 permits for unconventional wells were issued in 2013. Susquehanna County was the location of most of the permits for unconventional wells, and Bradford County had the second highest number of

permits. In 2013, 1,207 unconventional wells were drilled, while 960 conventional wells were drilled in Pennsylvania. The majority of the unconventional wells were drilled in Washington County, followed closely by Susquehanna County. According to PA*IRIS/WIS, the Pennsylvania database of oil and gas records, and DEP, by the end of 2013, over 3,100 wells reported production from the Marcellus Shale. About 85% of these productive wells were horizontal wells. According to PA*IRIS/WIS and DEP, about 1800 bcf of gas, about 1 million bbls of condensate, and about 43,400 bbls of oil were produced from the Marcellus Shale in 2013. During the last 6 months of 2013, Chesapeake Appalachia LLC was the largest producer of natural gas from the Marcellus Shale, having reported over 245 bcf in the 6-month reporting period. Chesapeake was followed by Cabot Oil & Gas Corporation, Range Resources Appalachia LLC, Anadarko E&P Onshore LLC, and Talisman Energy USA Inc., each with production of over 60 bcf of natural gas in the last 6 months of 2013.

Virginia: According to the Virginia Division of Gas & Oil (DGO), there were no wells drilled exclusively for the Marcellus Shale in Virginia between 2004 and 2013. There may have been gas production from the Marcellus Shale commingled with other zones in vertical wells in Virginia, but the quantity is unknown. The George Washington National Forest (GWNF) Plan was last revised in 1993. In an effort to update its land management plan, The U.S. National Forest Service (NFS) issued the Draft Environmental Impact Statement (DEIS) and Draft Revised Land and Resource Management Plan for the GWNF in April, 2011. Several options were proposed by the NFS, but the NFS' preferred alternative forest plan included the restriction that, on lands administratively available for gas and oil leasing within the GWNF, no horizontal drilling will be allowed. The public comment period for the Draft Forest Plan and Draft Environmental Impact Statement ended on October 17, 2011. Staff of the NFS continue to review and analyze the comments, and as of December 12, 2013, had not released the final Forest Plan and Environmental Impact Statement.

West Virginia: Total production from wells completed in the Marcellus Shale from 1979 through 2012 was over 660 bcf of gas and almost 1.8 million bbls of oil, according to information from the West Virginia Geological and Economic Survey (WVGES). The first production reported from a horizontal well completed in the Marcellus Shale was in 2007. Between 2007 and 2012, about 547 bcf of gas was produced from horizontal wells completed in the Marcellus Shale, as well as about 1.5 million bbls of oil. The oil volumes reported by operators include natural gas liquids. West Virginia is second to Pennsylvania in cumulative production of hydrocarbons from the Marcellus Shale. According to WVGES, over 1400 vertical wells reported production from the Marcellus Shale that was commingled with production from other formations in 2012. There were 612 horizontal wells from which there was reported production from the Marcellus Shale in 2012. In 2012, production of over 324 bcf of gas and almost 925,000 bbls of oil were reported from both vertical and horizontal wells completed in the Marcellus Shale. In 2012, the counties from which most of the liquids were produced were Wetzel, Ohio, Brooke, Doddridge, Marshall and Tyler. Most of the completed Marcellus Shale wells that are reported as "deviated", meaning horizontal, were located in Marion, Marshall, Wetzel, Ohio, Taylor, Harrison, Doddridge, and Upshur counties. In most of these counties, the thickness of the Marcellus Shale with high gamma-ray readings is 40 to 100 feet, according to WVGES. Based on volume of gas production from the Marcellus Shale through 2012, the major producers included Chesapeake Appalachia, LLC, Antero Resources Appalachian Corp., EQT Production Company, XTO Energy, Inc., and Stone Energy. The companies with the most oil production in 2012 from the Marcellus Shale were Chesapeake Appalachia LLC, EQT Production Company, and Stone Energy.

Visit the following web sites for more information on the Marcellus Shale:

http://www.eia.gov/oil_gas/rpd/shale_gas.pdf

http://www.eia.gov/energy_in_brief/about_shale_gas.cfm

<http://geology.com/articles/marcellus-shale.shtml>

<http://www.wvgs.wvnet.edu/www/datastat/devshales.htm>

<http://www.dep.wv.gov/oil-and-gas/databaseinfo/Pages/default.aspx>

http://www.mgs.md.gov/geology/minerals_energy_resources/marcellus.html
<http://www.mde.state.md.us/programs/Land/mining/marcellus/Pages/index.aspx>
<http://www.dec.ny.gov/energy/46288.html>
<http://www.dec.ny.gov/energy/36159.html>
<http://www.dec.ny.gov/energy/205.html>
<http://www.dec.ny.gov/energy/1603.html>
<http://geosurvey.ohiodnr.gov/energy-resources/marcellus-utica-shales>
<http://oilandgas.ohiodnr.gov/>
<http://oilandgas.ohiodnr.gov/shale>
<http://www.ohiodnr.com/portals/11/publications/pdf/oilgas11.pdf>
http://www.dcnr.state.pa.us/cs/groups/public/documents/document/dcnr_006811.pdf
<http://www.dcnr.state.pa.us/topogeo/econresource/oilandgas/marcellus/index.htm>
http://www.portal.state.pa.us/portal/server.pt/community/office_of_oil_and_gas_management/20291
<https://www.paoilandgasreporting.state.pa.us/publicreports/Modules/DataExports/DataExports.aspx>
<http://www.dmme.virginia.gov/DGO/HydraulicFracturing.shtml>
<http://www.dmme.virginia.gov/DGO/pdf/NaturalGasFAQs.pdf>
<http://www.fs.fed.us/r8/gwj/>
http://www.fs.usda.gov/detail/gwj/landmanagement/?cid=fsbdev3_000397
<http://pubs.usgs.gov/of/2012/1194/>
<http://pubs.usgs.gov/fs/2011/3092/>
<http://pubs.usgs.gov/of/2011/1298/>

References cited:

- Coleman, J. L., Milici, R. C., Cook, T. A., Charpentier, R. R., Kirschbaum, M., Klett, T. R., Pollastro, R. M., and Schenk, C. J., 2011, Assessment of undiscovered oil and gas resources of the Devonian Marcellus Shale of the Appalachian Basin Province, 2011: U.S. Geological Survey Fact Sheet FS2011-3092, 2 p., (accessed at <http://pubs.usgs.gov/fs/2011/3092/> on October 25, 2011).
- Harper, J. A., 2008, The Marcellus Shale – An old “new” gas reservoir in Pennsylvania: *Pennsylvania Geology*, v. 38, no. 1, p. 2-13.
- Milici, R.C., Ryder, R.T., Swezey, C.S., Charpentier, R.R., Cook, T.A., Crovelli, R. A., Klett, T.R., Pollastro, R.M., and Schenk, C.J., 2003, Assessment of undiscovered oil and gas resources of the Appalachian basin province, 2002: U.S. Geological Survey Fact Sheet FS-009-03, 2 p.
- Milici, R. C., and Swezey, C. S., 2006, Assessment of Appalachian Basin Oil and Gas Resources: Devonian Shale – Middle and Upper Paleozoic Total Petroleum System: U. S. Geological Survey Open-File Report 2006-1237, 70 p., with additional figures and tables, <http://pubs.usgs.gov/of/2006/1237/>, (accessed March 27, 2012).
- Repetski, J. E., R. T. Ryder, D. J. Weary, A. G. Harris, and M. H. Trippi, 2008, Thermal maturity patterns (CAI and %Ro) in Upper Ordovician and Devonian rocks of the Appalachian Basin: a major revision of USGS Map I-917-E using new subsurface collections: U. S. Geological Survey Scientific Investigations Map 3006, one CD-ROM.
- Ryder, R.T., Hackley, P.C., Alimi, Hossein, and Trippi, M.H., 2013, Evaluation of thermal maturity in the low maturity Devonian shales of the northern Appalachian basin: *American Association of Petroleum Geologists Search and Discovery Article #10477* (2013), available at http://www.searchanddiscovery.com/documents/2013/10477ryder/ndx_ryder.pdf.
- Smith, L.B., and Leone, James, 2010, Integrated characterization of Utica and Marcellus black shale gas plays, New York State: *American Association of Petroleum Geologists, Search and Discovery Article #50289*, 36 p.

- U.S. Energy Information Administration, 2014, Drilling Productivity Report for key tight oil and shale gas regions, February 2014: U.S. Energy Information Administration, available at <http://www.eia.gov/petroleum/drilling/pdf/dpr-full.pdf> .
- USGS Marcellus Shale Assessment Team, 2011, Information relevant to the U.S. Geological Survey assessment of the Middle Devonian Shale of the Appalachian Basin Province, 2011: U.S. Geological Survey Open-File Report 2011-1298, 22 p.
- Wrightstone, G., 2009, Marcellus Shale – Geologic controls on production: American Association of Petroleum Geologists Search and Discovery Article #10206 ©AAPG Annual Conven

Monterey Formation (Miocene), various California basins, U.S.

by Margaret A. Keller (U.S. Geological Survey, retired, originally submitted in 2013)

The Monterey Formation of central and southern California, USA, is widely known as a world-class petroleum source rock (one of the geologically youngest) and for sourcing much of the petroleum in California over the 100 plus years of development (e.g., see Behl, 1999; Isaacs, 2001; Isaacs and Rullkötter, 2001). Most of this production occurs in California's share of the EIA's top 100 oil and gas fields of the USA (http://www.eia.doe.gov/oil_gas/rpd/topfields.pdf), and is predominantly heavy oil in the coastal regions (e.g., Santa Maria and Santa Barbara-Ventura), and lighter oil in the interior basins (e.g., San Joaquin; see USGS Professional Paper 1713 at <http://pubs.usgs.gov/pp/pp1713/>). Conventional gas production occurs in both the onshore (http://www.eia.doe.gov/oil_gas/rpd/conventional_gas.pdf) and offshore regions (http://www.eia.doe.gov/oil_gas/rpd/offshore_gas.pdf) of California. However, California and the Monterey Formation are not highlighted on the most recent EIA map of shale gas plays for the lower 48 states (http://www.eia.doe.gov/oil_gas/rpd/shale_gas.pdf), and so far, no shale gas production has been reported. The Monterey Formation is primarily an oil play because much of the formation is either currently within the oil window or has not matured beyond that. Only a few places have the high maturity required to match the Barnett model [for shale gas] -- southern San Joaquin, western Ventura, and Los Angeles (P. Lillis, Pers. Comm. 8/12/10). Nevertheless, some characteristics of the gas production from siliceous shales of the Monterey Formation at Elk Hills (<http://www.onepetro.org/mslib/servlet/onepetropreview?id=00035742&soc=SPE>) fit some of the criteria for a shale gas play.

The Monterey Formation is notable for and primarily recognized by its fine-grained lithofacies that contain abundant biogenic silica from diatoms. These lithofacies - diatomite and diatomaceous shales or mudstones - and their diagenetic equivalents - chert, porcelanite, and siliceous shales or mudstones - and characteristic interbedding at millimeter scale, distinguish the Monterey Formation from other Tertiary rock systems in California which, for the most part, comprise predominantly terrigenous derived siliciclastic rocks - clay-rich and clay-dominated mudstones, sandstones, and coarser-grained lithofacies. In addition to being the source for most of the petroleum in reservoirs of interbedded coeval sandstones and adjacent Tertiary strata, within the past 3 decades the Monterey Formation has become better known for self sourcing its less conventional, fine-grained reservoir lithofacies (oil and associated gas in fractured chert, diatomite, and siliceous shale reservoirs within the formation). Two different oil types (low and high sulfur Monterey sourced systems) originate from different type II kerogens - generally those forming within the more proximal parts of the Monterey depositional system being low in sulfur and those in more distal areas of the system being relatively higher in sulfur (Orr, 1986).

Resurgence in exploration for shale oil in the Monterey Formation is occurring again in California (Durham, 2010; Huggins, 2010). Durham's (2010) article quotes Marc Kammerling's estimate of ultimate recovery from fields identified as Monterey producers only as 2.5 billion barrels. Durham (2010) also reports that the Monterey is "estimated to contain more than 500 billion barrels of oil in place." As noted by Huggins (2010), "thousands of acres have been leased and top leased, millions of dollars have been invested in shooting seismic and drilling wells. New rigs are arriving on

a regular basis, and land consultants are being brought in from out of state to deal with all the transactions and lease checks.” In addition to providing a short history of the evolution of Monterey development/exploration concepts, Huggins (2010) also makes the important point that “the other big change is the realization that significant thicknesses of high total organic carbon-rich rocks, in the right structural configuration, with the right combination of porosity and permeability, can in themselves be productive.”

REFERENCES CITED:

- Behl, R. J., 1999, Since Bramlette (1946): The Miocene Monterey Formation of California revisited, *in* E.M. Moores, D. Sloan, and D.L. Stout, eds., *Classic Cordilleran concepts: A view from California: Boulder, Colorado, Geological Society of America Special Paper 338.*
- Durham, L.S., 2010, Monterey Shale gets new look; *AAPG Explorer*, Vol. 31, No. 11, p.10-12.
- Huggins, C., 2010, What is old is new again – a new way to look at recycling; *Pacific Petroleum Geologist Newsletter*, November & December, 2010, p. 4-5.
- Isaacs, C. M., 2001, Depositional framework of the Monterey Formation, California, *in* C.M. Isaacs, and J. Rullkötter, eds., *The Monterey Formation: From rocks to molecules: New York, Columbia University Press*, p. 1-30.
- Isaacs, C. M., and J. Rullkötter, eds., 2001, *The Monterey Formation: From rocks to molecules: New York, Columbia University Press*, 553 p.
- Orr, W.L., 1986, Kerogen/asphaltene/sulfur relationships in sulfur-rich Monterey oils; *Organic Geochemistry*, v. 10, p. 499-516.

Niobrara Formation (Cretaceous), Rocky Mountain Region, U.S.

by Stephen Sonnenberg (Colorado School of Mines, previously submitted)

The Niobrara is a significant, self-sourced, resource play throughout the Rocky Mountain region. New technology of horizontal drilling and multi-stage, hydraulic-fracture stimulation is unlocking reserves that previously were not obtainable.

Known production comes from both fracture and matrix porosity systems (dual porosity). High matrix porosity is present in the shallow biogenic gas accumulations of eastern Colorado and Western Kansas. The shallow biogenic play is important for natural gas production at burial depths of less than 3500 feet. The deeper Niobrara thermogenic accumulations generally occur at burial depths greater than 7000 feet. Burial diagenesis (chemical and mechanical compaction and cementation) reduces porosities to values less than 10 percent in the deeper parts of the various basins where the Niobrara is prospective. Mature Niobrara source rocks are located in these areas of low porosity. Natural fractures are important contributors to production in the deeper areas.

The Niobrara Petroleum System contains all aspects of a large resource play (e.g., widespread mature source and reservoir rocks, self-sourced). The Niobrara was deposited in the Western Interior Cretaceous (WIC) Basin and is a widespread unit in the Rocky Mountain Region (Fig. 1). The WIC Basin was broken into numerous smaller basins during the Laramide orogeny. The Niobrara contains reservoir rocks, rich source beds and abundant seals. The various productive lithologies all have low porosity and permeability. TOC values in shales locally range from 2% to 8% in the eastern WIC area and are reduced to 1-3% because of siliciclastic dilution in the western WIC area. Laramide structural events exert the primary control on fracturing within the Niobrara as well as thermal maturity. Neogene extension fracturing is also thought to be an important component for locating production “sweet spots.” Understanding the thermal maturity of the source rocks will assist in predicting the distribution of hydrocarbon accumulations. Hydrocarbon generation may enhance the tectonic fractures and may also create new ones as a result of overpressuring associated with this process.

A summary of factors thought to be important for Niobrara production in the Rocky Mountain region are as follows: presence of favorable reservoir facies (brittle chalk) and a diagenetic history

that enables open fracture systems to exist; presence of mature source rocks to enable a continuous oil column to exist in the trap; source rocks interbedded with respect to the reservoir limestone (chalk); a favorable tectonic history for fracture formation. Most fracture systems fall into two major categories: structure-related fractures and regional orthogonal fractures.

Resistivity mapping can be used to determine both the presence of a hydrocarbon accumulation and the maturity of source rocks for the Niobrara. The presence of oil in open fracture systems is thought to be the cause of the high resistivity anomalies in chalk beds. A relationship between increasing resistivity of source shales with increasing thermal maturity has also been demonstrated.

Knowledge of the distribution and occurrence of hydrocarbon source and reservoir rocks in the Niobrara interval will greatly aid future exploration.

REGIONAL SETTING

The Upper Cretaceous Niobrara (Coniacian-Campanian; ~ 82 to 89.5 million years ago) was deposited in a foreland basin setting in the Western Interior Cretaceous Seaway of North America during a time of a major marine transgression (Fig. 1). This major transgression probably represents the maximum sea-level highstand during the Cretaceous and may contain the best source rocks in the Cretaceous. The present-day basins in the Rocky Mountain region formed during the Late Cretaceous to Early Tertiary Laramide orogeny.

The Western Interior Cretaceous (WIC) Basin was an asymmetric foreland basin with the thickest strata being deposited along the western margin of the basin (Figs. 1, 2). The WIC Basin is a complex foreland basin that developed between mid to late Jurassic to Late Cretaceous time. The basin was bordered by mountainous areas to the west (zone of plutonism, volcanism, and thrusting that formed the Cordilleran thrust belt) and a broad stable cratonic zone to the east. The foreland basin subsided in response to thrust and synorogenic sediment loading and pulses of rapid subduction and shallow mantle flow.

During sea-level highstands, coccolith-rich and planktonic foraminifera-rich carbonate sediments (chalks) accumulated on the eastern half of the seaway. Chalky beds extend into Montana and southern Canada (where they are called the White Spec zones) and into the Gulf Coast region (Austin Chalk). Chalk-rich carbonate facies change westward into siliciclastic-rich beds.

STRATIGRAPHY AND DEPOSITIONAL SETTING

The Niobrara represents one of the two most widespread marine invasions and the last great carbonate producing episode of the Western Interior Cretaceous basin (the first widespread event is represented by the Greenhorn chalks). The dominant lithologies of the Niobrara Formation are limestones (chalks) and interbedded with marls and calcareous shales (Figs. 2, 3). The chalk-shale cycles are interpreted to represent changes from normal to brackish water salinities possibly related to regional paleo-climatic factors or sea level fluctuations. The chalk lithologies are thought to represent deposition in normal to near normal marine salinities having a well-mixed water column and well oxygenated bottom waters. The chalks reflect influx of warm Gulfian currents into the WIC seaway during relatively high sea levels. The interbedded shale/marl cycles are interpreted to be caused by an increase in fresh water runoff caused by increased rainfall which may be related to climatic warming. The fresh water runoff creates a brackish water cap and salinity stratification. Vertical mixing of the water column is inhibited causing anoxic conditions in the bottom waters. This enhances preservation of organic material and results in organic-rich source rocks. The decrease in water salinities is also suggested by oxygen isotopic values. The shalier intervals may reflect lower sea levels and greater influx of clastic material from the west. The chalks have previously been interpreted to represent higher sea levels during Niobrara time.

Three major facies are present in the Niobrara and equivalents across the Rocky Mountain region (Figs. 1 and 2). On the western side of the area, a sandstone facies is present which changes laterally to the east into a calcareous shale facies, and which, in turn, changes eastward into a limestone and chalk facies. These various lithologies interfinger and the facies changes are very

gradational. The Niobrara name is used for chalk and shale units located on the eastern side of the Western Interior Seaway; whereas, the term Mancos is generally used for the equivalent shale, and siltstone units in the western part of the area. The equivalent shoreline and non-marine sandstone units further to the west are known by a variety of names. The limestone facies is composed of coccolith-rich fecal pellets probably derived from pelagic copepods, inoceramid and oyster shell fragments, planktonic foraminifer tests, micrite, clay, and quartz silt. The thick siltstone facies was derived from highlands to the west. The shales found in the Mancos/Niobrara are dark-gray to black and generally organic rich (>1% TOC). The shales are fair to excellent source rocks and also provide seals for the chalky and sandy reservoir facies. TOC content in the interval increases to the east (Fig. 1).

The chalks of the Niobrara are rich in organic matter and organic related material (e.g., pyrite). On the east side of the WIC basin, the Niobrara consists of four chalk beds and three shale intervals (Fig. 3). The basal chalk bed is known as the Fort Hays limestone member and the unit contains some of the purest chalk in the Western Interior. The Fort Hays is regionally extensive and ranges in thickness from 50 feet in southeast Colorado to 120 feet in New Mexico to less than 10 feet in southeast Wyoming. Carbonate content persists from the Denver Basin to southwest Colorado into the Laramie, North Park, South Park, and Sand Wash basins. The Fort Hays interval is difficult to distinguish from the remainder of the Niobrara north of the Laramie Basin.

The Fort Hays is overlain by the Smoky Hill member. The Smoky Hill consists of organic rich shales to chalky shale (marls) to massive chalk beds. The interval has been subdivided by various authors into several units. Figure 3 illustrates a six member subdivision.




Figure 1. The Western Interior Cretaceous Basin during Niobrara time (modified from Longman et al., 1990). Source area for clastics is dominantly to the west, total organic carbon content in the Niobrara increases to the east, carbonate content generally increases on the eastern side of the Western Interior Cretaceous (WIC) seaway and to the southeast.




Figure 2. Generalized cross section across the Western Interior Cretaceous Basin. The Niobrara is Upper Cretaceous in age. Limestone and chalk beds are present over the eastern two thirds of the basin (modified from Kauffman, 1977).

The Niobrara ranges in thickness from 100 to 300 feet along the eastern side of the WIC basin to over 1500 feet on the west side of the WIC basin. Figure 4 illustrates an isopach map of the Niobrara across the northern Rockies region. Thinning occurs in a northeast trend across the map area. This thin trend was related to paleotectonic movement on the Transcontinental arch. Superimposed on the Transcontinental arch are northeast axes of thinning (Fig. 4). Thinning in the Niobrara is believed to result from differing rates of sedimentation (i.e., convergence or divergence of section) and unconformities at the base, within, and at the top of the formation.

Niobrara deposition in the Western Interior Basin was strongly influenced by the interplay of warm north-flowing currents from the paleo-Gulf of Mexico and cooler southward-flowing currents from the Arctic region along with sea level fluctuations. Warm waters from the Gulf brought in rich carbonate flora of coccoliths and promoted carbonate production and deposition. Siliciclastic input from the west and cooler Arctic currents inhibited carbonate production and deposition.

Chalks and marls are abundant in the Denver Basin. The section changes to marl and is shalier west of the Front Range and north of the Hartville Uplift. Chalk intervals extend into the Laramie, Hanna, North Park, Sand Wash, and Piceance basins. The section in the Piceance consists of interbedded sandstone, siltstone, and shale. In the San Juan Basin, the Niobrara consists of a mixture of siliciclastic and marl lithologies.

The Niobrara is overlain by the Pierre Shale in the eastern part of the Western Interior Basin and its age equivalent Mancos shale in the western part. The Niobrara overlies the Carlile Formation across much of the Western Interior basin (and its members: Codell Sandstone, Sage Breaks Shale, etc.). The Sharon Springs member of the Pierre shale overlies the Niobrara in most of eastern Colorado. The Sharon Springs is an excellent source rock with TOC's ranging from 2 to 8 weight percent.

The type locality for the Niobrara Chalk is Knox County in northeastern Nebraska.

SOURCE ROCKS

Several workers have discussed the organic-rich nature of the Niobrara Formation and the increased thermal maturity and resistivity with increased burial depth. Vitrinite reflectance and resistivity of the organic-rich shale both increase with increasing thermal maturity. These values can be mapped to show areas of source rock maturity.

The Niobrara Formation has been analyzed using the Rock-Eval instrument by several workers (Fig. 5). Organic-rich beds in the formation have total organic carbon values which average 3.2%. A plot of hydrogen index versus oxygen index (modified van Krevelen diagram) illustrates the type and

level of maturity of the source rocks for different depths across the Denver basin. The plot also illustrates that the kerogen present in the Niobrara is Type-II or oil-prone (sapropelic).




Figure 3. Generalized stratigraphic column for the Niobrara from the Denver Basin setting. The Niobrara ranges in age from Coniacian to lower Campanian. Several transgressive and regressive cycles are noted for the Niobrara interval. Four chalk-rich intervals were deposited during transgressive events, calcareous shales during regressive events (modified from Longman et al., 1998; Barlow and Kauffman, 1985).

RESERVOIR ROCKS

The lithology of the Niobrara changes from east to west across the Western Interior Basin (Fig. 2). In the Denver Basin, the lithology consists of interbedded calcareous shale, shaley limestones, marls, and limestones (Fig. 3). Westward, the lithology becomes shalier and sandier (Fig. 1). The carbonates are still present in the western area but clastics begin to dominate.

Most Niobrara reservoir rocks have undergone mechanical and chemical compaction and are low porosity and permeability rocks. Burial depth is the single most important factor affecting porosity. Chalks have high original porosities (50% or greater). Initial dewatering and mechanical compaction is the first diagenetic phase. Grain and fossil breakage and re-orientation reduce porosity. Initial coccolith grain sizes are 0.2 to one micron. Chemical compaction is characterized by calcite dissolution along wispy dissolution seams, microstylolites, and stylolites. Grain-to-grain dissolution along microstylolites is common and the dissolved calcite is reprecipitated locally.

HYDROCARBON PRODUCTION

Niobrara production represents some of the oldest established production in the Rocky Mountain region. The oldest field in the region is the Florence-Cañon City field which was discovered in 1881 (Fig. 6). The field produces from the Pierre shale immediately above the Niobrara and is believed to be sourced from the Niobrara and Sharon Springs. The Boulder oil field (western Denver basin) was discovered in 1901 and is also productive from fractured Pierre shale but also sourced from the Niobrara. Fractured Mancos shale production was found in Rangely (northwest Colorado) in 1902. Niobrara production was established in Tow Creek (Sand Wash basin) in 1924. The Berthoud field of the western Denver basin is productive from several horizons including the Niobrara and discovered in 1927. Gas in the Niobrara was discovered in Beecher Island (eastern Colorado) in 1919 (commerciality was not established until 1972, however). The Niobrara interval is

productive in the Bowdoin field of Montana which was discovered in 1913. The reason for these early discoveries is that many of them are associated with surface structures which were the primary targets of early explorers.




Figure 4. Isopach of the Niobrara across the northern Rockies (modified from Longman et al., 1998). The Niobrara ranges in thickness from less than 100 feet to over 1800 feet. Thinning occurs in a northeast trend across the area known as the Transcontinental Arch (Weimer, 1978).

Hydrocarbon production comes from all three major Niobrara lithofacies: 1) microporous and fractured coccolith- and planktonic foraminifer-rich limestone (eastern part of WIC basin); 2) fractured marls and shales (mainly in the central part of the seaway); 3) fractured sandstone and siltstone rich facies, mainly in the western and southwestern parts of the seaway. Production occurs in the Laramide-aged Powder River, Denver, North Park, Greater Green River (including Sand Wash), Raton, San Juan, and Piceance basins and in north-central Montana. The widespread distribution of the production along with many wells with hydrocarbon shows across these basins suggests a large resource play may exist. The majority of recent drilling activity in the Niobrara has been in the Denver Basin, north of Wattenberg field and in southeast Wyoming around the Silo field. Hydrocarbon production from chalk reservoirs occurs along the shallow eastern margin of the Denver basin. Many of the gas accumulations in this area occur in structural traps and reservoirs require hydraulic-fracture stimulation. The gas is biogenic or microbial in origin. Production in the shallow play comes from the upper chalk bench or Beecher Island member of the Niobrara and is mainly from microporosity within the chinks, but is enhanced by natural fracturing. Production from the shallow Niobrara from eastern Colorado is 600 BCFG. Beecher Island Field is one of the largest and first fields discovered in the shallow Niobrara. Commercial production dates back to 1972 (initial discovery in 1919!) and the cumulative for the field is 100 BCFG. Three-dimensional seismic data have been used effectively to improve development and exploration success ratios in fields.

Shallow gas production from the Niobrara also occurs in north central Montana. Bowdoin Dome has produced 62 BCFG and 19 MBO from the Niobrara. Additional Niobrara fields are located to the west the Alberta Basin extends into Montana. The largest field to date is the St. Joe Road field which was discovered in 2001 and has produced 18.2 BCFG.

Deeper in the Denver Basin, the Niobrara is oil productive in a number of fields. The porosity of the chinks in the deeper part of the basin has been dramatically reduced by compaction and burial diagenesis. Production is attributed to the presence of fractures in the chalky intervals. Some attempts have been made to establish production from some of the rich, shaley intervals within the Niobrara. The shale gas and fractured chalk potential of the deep Denver basin area is significant as

shown by fields like Wattenberg and Silo. Silo Field was discovered in 1981 and has produced approximately 10.4 MMBO and 8.9 BCFG.

The Niobrara is productive on the Casper Arch of Wyoming at Salt Creek and Teapot fields. Total production has been 1.5 MMBO and 0.2 BCFG. In the deeper Powder River Basin production has been established in a number of accumulations including Fetter, Hilight, Brooks Draw and Flat Top. Hilight has produced 411 MBO and 0.8 BCFG to date.

The western portion of the region is productive in a variety of traps and lithologies (mainly siliciclastic) and there is significant potential for hydrocarbon production in many of the western basins. The basal part of the Niobrara equivalent in the west yields oil and gas in the San Juan basin from a sandstone and shale interval (Tocito and Gallup sandstones). Examples of producing fields from the Gallup are Bisti and Verde fields. Bisti Field has produced 41.8 MMBO and 79.2 BCFG. Verde Field has produced 8.1 MMBO and 2.5 BCFG. Examples of fields producing from the Tocito Sandstone are the Blanco South and Chipeta fields. These fields have produced 4.2 MMBO and 18.8 BCFG. Production is from interparticle porosity but is enhanced by fractures. The upper Niobrara equivalent (Smoky Hill member) is productive in the Sand Wash basin from fractured reservoirs (Fig. 6) and perforated intervals are commonly long. Field examples are Buck Peak and Tow Creek. Buck Peak has produced 4.8 MMBO and 8.5 BCFG. Tow Creek has produced 3 MMBO and 0.3 BCFG. Farther to the west where the Niobrara equivalents are dominantly shale, production is found in the Rangely and Douglas Creek Arch fields. Production from fractured Mancos shale at Rangely represents some of the oldest production in Colorado (1902). The Mancos at Rangely has produced around 11.9 MMBO and 0.2 BCFG. Neogene age extensional faulting is a key to production at Buck Peak and Rangely. The extensional fracture trend is N60W. The Douglas Creek arch production comes mainly from Cathedral Field. The field has produced 56.5 BCFG and 40.6 MBO from the Mancos (mainly the Mancos B zone).

Other production equivalent to the upper Niobrara zone comes from the Mancos interval in the San Juan basin. Examples of Mancos producing fields are: East and West Puerto Chiquito, Rio Puerco; Gavilan, Basin, and Boulder. These fields are interpreted to be fractured reservoirs and producing intervals are hundreds of feet thick. The Puerto Chiquito fields have produced 19.3 MMBO and 55.5 BCFG. Gavilan Field has produced 7.8 MMBO and 111 BCFG. Boulder Field has produced 1.8 MMBO and 1.6 BCFG. Basin Field has produced 120 MBO and 4.1 BCFG. Rio Puerco Field has produced 1.3 MMBO and 1.4 TCFG.

The Mancos is gas productive in the deeper parts of the Uinta basin in several fields including Natural Buttes. Mancos is also productive in some silty and very fine-grained sandstone zones in the Cathedral field of the Douglas Creek Arch. New Mancos/Niobrara production has been established in several areas of the deeper Piceance Basin (e.g., Mamm Creek field).

EXPLORATION METHODS

Methods of exploration for fractured Niobrara reservoirs should incorporate many if not all of the following: seismic acquisition; aeromagnetics study; surface lineament analysis; subsurface mapping; isoresistivity mapping; logging technology; and technology to produce the reservoir. 2-D and 3-D seismic is extremely important to map structural anomalies. Three-dimensional three-component (compressional and shear wave data) methods have also proved to be effective in analyzing the fractured reservoir. Aeromagnetism is a tool that may identify basement shear zones areas of potential fractures having gradient changes such as narrow zones of steep gradients. Aeromagnetic data examined in the Silo field area illustrates possible northwest-trending shear zones. If basement fracture systems propagate all the way to the surface then a surface lineament analysis may also be effective. Northwest-trending surface lineament in the Silo area have been mapped by use of remote sensing techniques. Resistivity mapping is important to show areas of oil accumulation. When resistivity mapping is combined with subsurface mapping the most probable areas of fracturing can be predicted. Logging technologies available to identify fractured reservoirs are geophysical logs such as

the FMS, FMI and CAST logs. Horizontal drilling and multi-stage hydraulic fracturing offer technologies to economically produce hydrocarbons from the reservoir.




Figure 5. Niobrara Van Krevelen diagram. Niobrara source rocks are Type-II (oil prone) kerogens based on Rock Eval data. With increasing burial depth and thermal maturity the HI values decrease significantly. Data from Rice (1984); Barlow (1985); Pollastro (1985); after Sonnenberg and Weimer (1993).

An understanding of the regional stress field is important in most tight oil and gas plays. The direction of maximum horizontal stress (S_{hmax}) is generally the direction of open fractures. Regional horizontal stress maps have been published for North America. The present-day stress field reflects Neogene extensional tectonics and the epeirogenic uplift that has taken place in the western United States.

SUMMARY

Widespread source and reservoir rocks make the Niobrara Formation an attractive target for exploration across the Rocky Mountain region. The Niobrara contains mature source rocks interbedded with brittle limestones (chalks) in the deeper parts of many basins in the Rocky Mountain region. Thermogenic production occurs from the chalk intervals in the eastern part of the region and from siliciclastics and shales in the western and southwestern parts of the Rocky Mountain regions (Uinta and San Juan basins). Biogenic gas production occurs at shallow depths along the eastern Rocky Mountain region in Colorado, Kansas, and Nebraska. Generally production comes from depths less than 3500 feet. Shallow gas production also occurs in several areas of north-central Montana. The shallow gas production generally is structurally controlled.

The Niobrara reservoirs generally have low permeabilities so natural fracturing plays a role in economic production. The limestone (chalk) beds behave in a brittle manner, whereas, the adjacent calcareous shales often behave in a ductile manner. Fractures occur for a variety of reasons and several models can be used for exploration. Early created fractures are susceptible to extreme diagenesis and thus generally completely cemented. Late stage structural movement can help re-open old fractures or create new ones. Regional epeirogenic uplift of western North America and subsequent erosion (denudation) may play a role in Niobrara microfractures. The removal of overburden results in lowered effective stress in rocks that may also be overpressured. This mechanism may be important in all tight-reservoir plays in the Rocky Mountain Region.




Figure 6. Niobrara producing areas across the north Rockies (Oil fields-green; gas fields-red)(modified from Longman et al., 1998). Basin abbreviations are as follows: AB-Alberta Basin; CM-Crazy Mountain; WB-Williston Basin; BB-Bighorn Basin; PRB-Powder River Basin; WRB-Wind River Basin; GGRB-Greater Green River Basin; NPB-North Park Basin; PB-Piceance Basin; UB- Uinta Basin; SPB-South Park Basin; FCCB-Florence-Canon City Basin; SJB-San Juan Basin; RB-Raton Basin; DB-Denver Basin; EB-Estancia Basin. Distribution of sapropelic oil-generation-prone Niobrara source rocks within brown dashed line (Meissner et al., 1984). Dot-dashed line equals 3,000 ft current burial depth; biogenic accumulations east of line; thermogenic accumulations west of line (from Lockridge and Scholle, 1978).

REFERENCES

Barlow, L.K., 1986, An integrated geochemical and paleoecological approach to petroleum source rock evaluation, lower Niobrara Formation (Cretaceous), Lyons, Colorado: *The Mountain Geologist*, v. 23. p. 107-112.

Clayton, J.L., and P.J. Swetland, 1980, Petroleum generation and migration in Denver Basin: *AAPG Bulletin*, v. 64, p. 1613-1633.

Friedman, M., and D.V. Wiltschko, 1992, An approach to exploration for naturally fractured reservoirs, with examples from the Austin Chalk, in J.W. Schmoker, E.B. Coalson, C.A. Brown, eds., *Geological studies relevant to horizontal drilling: examples from western North America: RMAG Guidebook*, p. 143-153.

Landon, S.M., M.W. Longman, and B.A. Luneau, 2001, Hydrocarbon source rock potential of the Upper Cretaceous Niobrara Formation, Western Interior Seaway of the Rocky Mountain region: *The Mountain Geologist*, v. 38, p. 1-18.

Lockridge, J.P., 1977, Beecher Island Field, Yuma County, Colorado in H.K. Veal, ed., *Exploration frontiers of the Central and Southern Rockies: RMAG Guidebook*, p. 272-279.

Lockridge, J. P., and P. A. Scholle, 1978, Niobrara gas in eastern Colorado and northwestern Kansas: in J.D. Pruitt, and P.E. Coffin, eds., *Energy resources of the Denver Basin: RMAG Guidebook*, p. 35-49.

- Longman, M. W., B. A. Luneau, and S. M. Landon, 1998, Nature and distribution of Niobrara lithologies in the Cretaceous Western Interior Seaway of the Rocky Mountain region: *The Mountain Geologist*, v. 35, p. 137-170.
- Lorenz, J.C., L.W. Teufel, and N.R. Warpinski, 1991a, Regional fractures 1: a mechanism for the formation of regional fractures at depth in flat-lying reservoirs, *AAPG Bulletin*, v. 75, p. 1714-1737.
- Mallory, W.W., 1977, Oil and gas from fractured shale reservoirs in Colorado and northwest New Mexico: RMAG Special Publication no. 1, 38 p.
- Meissner, F.F., J. Woodward, and J.L. Clayton, 1984, Stratigraphic relationships and distribution of source rocks in the greater Rocky Mountain region, *in* J. Woodward, F.F. Meissner, and J.L. Clayton, eds., *Hydrocarbon source rocks of the greater Rocky Mountain region: RMAG Guidebook*, p. 1–34.
- Perry, S. L., 1991. A statistical approach for fracture analysis using satellite imagery, Niobrara Formation: Wyoming and Colorado examples (abs.), *in* RMAG Short Course Notes: Exploration for Hydrocarbons in the Niobrara Formation, Rocky Mountain Region, p. 17.
- Pollastro, R.M., 1992, Natural fractures, composition, cyclicity, and diagenesis of the Upper Cretaceous Niobrara Formation, Berthoud Field, Colorado, *in* J.W. Schmoker, E.B. Coalson, and C.A. Brown, eds., *Geological studies relevant to horizontal drilling—Examples from western North America: RMAG Guidebook*, p. 243–255.
- Pollastro, R.M., and C.J. Martinez, 1985, Mineral, chemical and textural relationships in rhythmic-bedded, hydrocarbon-productive chalk of the Niobrara Formation, Denver Basin, Colorado: *The Mountain Geologist*, v. 22, p. 55-63.
- Pollastro, R. M., and P. A. Scholle, 1986, Exploration and development of hydrocarbons from low-permeability chinks--An example from the Upper Cretaceous Niobrara Formation, Rocky Mountain region, *in* C.W. Spencer and R. J. Mast, eds., *Geology of tight gas reservoirs: AAPG Studies in Geology No. 24*, p. 129-141.
- Rice, D.D., 1975, Origin of and conditions for shallow accumulations of natural gas, *in* F. Exum and G. George eds., *Geology and mineral resources of the Bighorn Basin: Wyoming Geological Association 27th Annual Field Conference Guidebook*, p. 267-271.
- Rice, D.D., 1984, Relation of hydrocarbon occurrence to thermal maturity of organic matter in the Upper Cretaceous Niobrara Formation, eastern Denver Basin: Evidence of biogenic versus thermogenic origin of hydrocarbons, *in* J. Woodward, F. F. Meissner and J. C. Clayton, eds., *Hydrocarbon source rocks of the greater Rocky Mountain Region: RMAG Guidebook*, p. 365-368.
- Rice, D.D., and G.E. Claypool, 1981, Generation, accumulation, and resource potential of biogenic gas: *AAPG Bulletin*, v. 65, p. 5-25.
- Smagala, T.M., C.A. Brown, and G.L. Nydegger, 1984, Log-derived indicator of thermal maturity, Niobrara Formation, Denver Basin, Colorado, Nebraska, Wyoming, *in* J. Woodward, F.F. Meissner, and J.C. Clayton, eds., *Hydrocarbon source rocks of the greater Rocky Mountain region: RMAG Guidebook*, p. 355-363.
- Sonnenberg, S. A., and R.J. Weimer, 1981, Tectonics, sedimentation and petroleum potential of the northern Denver Basin, Colorado, Wyoming, and Nebraska: *Colorado School of Mines Quarterly*, v. 7, n. 2, 45 p.
- Sonnenberg, S.A., and R.J. Weimer, 1993, Oil production from Niobrara Formation, Silo Field, Wyoming: Fracturing associated with a possible wrench fault system: *The Mountain Geologist*, v. 30, p. 39-53.
- Stearns, D.W., and M. Friedman, 1972, Reservoirs in fractured rock: Geologic exploration methods, *in* H.R. Gould, ed., *Stratigraphic oil and gas fields--Classification, exploration methods, and case histories: AAPG Memoir 16*, p. 82-106.
- Stone, D. S., 1969, Wrench faulting and Rocky Mountain tectonics: *The Mountain Geologist*, v. 6, p. 67-79.

- Svoboda, J.O., 1995, Is Permian salt dissolution the primary mechanism of fracture genesis at Silo Field, Wyoming? *in* R.R. Ray, ed., High-definition seismic: 2-D, 2-D swath, and 3-D case histories: RMAG Guidebook, p. 79-85.
- Vincelette, R.R., and N.H. Foster, 1992, Fractured Niobrara of northwestern Colorado, *in* J.W. Schmoker, E.B. Coalson, and C.A. Brown, eds., Geological studies relevant to horizontal drilling—Examples from western North America: RMAG Guidebook, p. 227–239.
- Weimer, R.J., 1960, Upper Cretaceous Stratigraphy, Rocky Mountain Area: AAPG Bulletin, v. 44, p. 1-20.
- Weimer, R.J., 1978, Influence of Transcontinental Arch on Cretaceous marine sedimentation: A preliminary report, *in* J.D. Pruit and P.E. Coffin, eds., Energy resources of the Denver Basin: RMAG Guidebook, p. 211-222.

Utah Shales, U.S.

By Thomas Chidsey and Michael D. Vanden Berg (Utah Geological Survey)

The high price of crude oil, coupled with lower natural gas prices, has generated renewed interest in exploration and development of liquid hydrocarbon reserves in Utah. Following on the success of the recent shale gas boom and employing many of the same well completion techniques, petroleum companies are now exploring for liquid petroleum in shale formations in the state. In fact, many shales or low-permeable (“tight”) carbonates recently targeted for natural gas include areas in which the zones are more prone to liquid production. Organic-rich shales in the Uinta and Paradox Basins have been the source for significant hydrocarbon generation, with companies traditionally targeting the interbedded sands or porous carbonate buildups for their conventional resource recovery. With the advances in horizontal drilling and hydraulic fracturing techniques, operators in these basins are now starting to explore the petroleum production potential of the shale and interbedded tight units themselves.

Uinta Basin

Overview

The Uinta Basin is the most prolific petroleum province in Utah. It is a major depositional and structural basin that subsided during the early Cenozoic along the southern flank of the Uinta Mountains. Lake deposits filled the basin between the eroding Sevier highlands to the west and the rising Laramide-age Uinta Mountains, Uncompahgre uplift, and San Rafael Swell to the north, east, and south, respectively. The southern Eocene lake, Lake Uinta, formed within Utah’s Uinta Basin and Colorado’s Piceance Creek Basin.

The Green River Formation consists of as much as 6000 ft of sedimentary strata (Hintze and Kowallis, 2009; Sprinkel, 2009) and contains three major depositional facies associated with Lake Uinta sedimentation: alluvial, marginal lacustrine, and open lacustrine (Fouch, 1975). The marginal lacustrine facies, where most of the hydrocarbon production is found, consists of fluvial-deltaic, interdeltic, and carbonate flat deposits, including microbial carbonates. The open-lacustrine facies is represented by nearshore and deeper water offshore muds, including the famous Mahogany oil shale zone, which represents Lake Uinta’s highest water level.

The Uinta Basin is asymmetrical, paralleling the east-west trending Uinta Mountains. The north flank dips 10-35° southward into the basin and is bounded by a large north dipping, basement-involved thrust fault. The southern flank gently dips between 4-6° north-northwest.

Activity

Recent drilling and exploration activities in the Uinta Basin are targeting relatively thin porous carbonate beds of the Uteland Butte Limestone Member of the lower Green River Formation (figures 1 and 2), particularly in an area referred to as the “Central Basin region” between Altamont-Bluebell field to the north and Monument Butte field to the south. The Uteland Butte has historically been a secondary oil objective of wells tapping shallower overlying Green River reservoirs and deeper fluvial-lacustrine Colton Formation sandstone units in the western Uinta Basin.

The Uteland Butte records the first major transgression of Eocene Lake Uinta after the deposition of the alluvial Colton Formation, and thus it is relatively widespread in the basin (figure 3). The Uteland Butte ranges in thickness from less than 60 ft to more than 200 ft and consists of limestone, dolomite, organic-rich calcareous mudstone, siltstone, and rare sandstone (figures 2, 4, and 5). The dolomite (figure 2), the new horizontal drilling target, often has more than 20% porosity, but is so finely crystalline that the permeability is very low (single mD or less).

Several companies (Berry/LINN, Bill Barrett Corporation, EP Energy, Newfield, QEP Resources, Devon, and Petroglyph) have had recent and continued success targeting the Uteland Butte with horizontal wells in both the central, normally pressured part of the basin near Greater Monument Butte field, and farther north in the overpressured zone in western Altamont field (figure 1). There are over 50 active horizontal wells producing from the Uteland Butte. Production from these wells averages 500-1500 BOE per day from horizontal legs up to 4000 ft in length. However, at the end of 2013, Newfield Production Company announced the completion of three high-volume producers in the Central Basin region with initial rates of 1213-1337 barrels per day (IHS Inc., 2013a). According to the Utah Division of Oil, Gas, and Mining, as of January 2014, there were over 200 APDs for horizontal wells targeting the Uteland Butte and other potential Green River tight oil zones (figure 1).

Paradox Basin

Overview

The Paradox Basin is located mainly in southeastern Utah and southwestern Colorado with small portions in northeastern Arizona and the northwestern corner of New Mexico. The Paradox Basin is an elongate, northwest-southeast-trending, evaporitic basin that predominately developed during the Pennsylvanian, about 330 to 310 Ma. The basin was bounded on the northeast by the Uncompahgre Highlands as part of the Ancestral Rockies. As the highlands rose, an accompanying depression, or foreland basin, formed to the southwest—the Paradox Basin. Rapid basin subsidence, particularly during the Pennsylvanian and continuing into the Permian, accommodated large volumes of evaporitic and marine sediments that intertongue with non-marine arkosic material shed from the highland area to the northeast. Deposition in the basin produced a thick cyclical sequence of carbonates, evaporites, and organic-rich shale of the 500- to 5000-ft-thick Pennsylvanian Paradox Formation (Hintze and Kowallis, 2009).

Rasmussen (2010) divided the middle part of the Paradox Formation in the evaporite basin into as many as 35 salt cycles that onlap onto the basin shelf to the west and southwest (figure 6). Each cycle consists of a clastic interval/salt couplet. The clastic intervals are typically interbedded dolomite, dolomitic siltstone, anhydrite, and black, organic-rich shale—the sources of the petroleum in the basin. The clastic intervals typically range in thickness from 10 to 200 ft and are generally overlain by 200 to 400 ft of halite.

The Paradox Basin can generally be divided into three areas: the Paradox fold and fault belt in the north, the Blanding sub-basin in the south-southwest, and the Aneth platform in the southernmost part in Utah. The area now occupied by the Paradox fold and fault belt was the site of greatest Pennsylvanian/Permian subsidence and salt deposition. Folding in the Paradox fold and fault belt began as early as the Late Pennsylvanian as sediments were laid down thinly over, and thickly in areas between, rising salt. Spectacular salt-cored anticlines extend for miles in the northwesterly trending fold and fault belt. Reef-like buildups or mounds of carbonates consisting of algal bafflestone and oolitic/skeletal grainstone fabrics in the Desert Creek and Ismay zones of the Paradox Formation are

the main hydrocarbon producers in the Blanding sub-basin and Aneth platform. Oil in these zones is sourced above, below, or within by the organic-rich Gothic, Chimney Rock, Hovenweep, and Cane Creek shales (figure 6).




Figure 1. Map of the Uinta Basin, Utah, showing play areas for the Uteland Butte Limestone Member of the Tertiary Green River Formation, APD horizontal well locations, and active horizontal wells by operators.

Activity

The Cane Creek shale zone of the Paradox Formation has been a target for exploration on and off since the 1960s and produces oil from several small fields (figure 7). The play generated much interest in the early 1990s with the successful use of horizontal drilling. Currently, eight active fields produce from the Cane Creek in the Paradox Basin fold-and-fault belt, with cumulative oil production nearly 5 million barrels (Utah Division of Oil, Gas, and Mining, 2014). Once again, the Cane Creek and other Paradox zones are being targeted for exploration using horizontal drilling.

The Cane Creek shale zone records an early stage of a transgressive-regressive sequence (cycle 21) in the Paradox Formation and consists of organic-rich marine shale with interbedded dolomitic siltstone and anhydrite (figure 8). The unit is up to 160 ft thick and areally extensive within the Paradox Basin. It is divided into the A, B, and C zones, with the shale and silty carbonates of the B zone considered both the source rock and reservoir. The A and C zones are anhydrite rich and provide an upper and lower seal to the B zone. The unit is highly overpressured, with measurements ranging between 5000 and 6200 psi, which is probably the result of hydrocarbon generation between very impermeable upper and lower anhydrite seals. The B zone is naturally fractured, and oriented cores show that fractures trend northeast-southwest, matching the regional structural trend.



Figure 2. Uteland Butte core from the Bill Barrett 14-1-46 well. The horizontal drilling target is the roughly 5-ft light brown dolomitic interval. Porosity in this interval ranges from 15-30% and permeability averages 0.06 mD. The dolomite is interbedded with organic-rich mudstones and limestones averaging between 1% and 3% TOC. Note the abundant shell fragments indicating deposition in a freshwater lacustrine environment.




Figure 3. General stratigraphy of the lower to middle Green River Formation in the western Uinta Basin (not to scale).




Figure 4. Outcrop of the Uteland Butte Member of the Green River Formation, Nine Mile Canyon, central Utah.

Two new Cane Creek shale horizontal well discoveries were announced in 2013 (figure 7): Fidelity Exploration & Production Company's 17-1 Cane Creek Unit (SWSE section 17, T. 26 S., R. 20 E., Salt Lake Basin Line & Meridian [SLBL&M], Grand County) just east of Park Road field, and Southwestern Energy Production Company's 1-16H SEPCO-State 30-23 (SESE section 16, T. 30 S., R. 23 E., SLBL&M, San Juan County). The 17-1 well was drilled in a south-southeast direction and averaged 524 BOPD and 242 MCFGPD in June 2013. Fidelity completed additional wells in Big Flat and Park Road fields in 2012 and 2013. The 36-1 Cane Creek Unit well (SWSW section 36, T. 25 S., R. 19 E., SLBL&M, San Juan County) in Big Flat field flowed over 1250 BOPD (IHS, Inc., 2013b). The company has identified 50 to 75 Cane Creek locations with an estimated recovery of 250,000 to 1 million bbls of oil per well (IHS Inc., 2013c). The 1-16H well was drilled in a northwest direction and in October 2013 was testing oil into onsite production facilities. It is located 5 miles south of Stone Energy Corporation's 2011 29-28 La Sal Unit Cane Creek discovery (SESE section 29, T. 29 S., R. 23 E., SLBL&M, San Juan County; see figure 7). That well initially flowed 248 BOPD and 320 MCFGPD from a northeast-directed horizontal lateral. At the end of 2013, Fidelity staked horizontal wells targeting the Cane Creek, one northeast of Hell Roaring field and two west of Big Flat field.

The U.S. Geological Survey (2012) re-assessed the undiscovered oil resource in the Cane Creek at 103 million barrels at a 95% confidence level and 198 million barrels at a 50% confidence level. In addition to the Cane Creek, several other organic-rich shale zones are present in the Paradox Formation, creating the potential for significant reserve base additions. The Gothic, Chimney Rock, and Hovenweep shales (figure 6) in the Blanding sub-basin and Aneth platform are estimated to hold an undiscovered oil reserve of 126 million barrels at a 95% confidence level and 238 million barrels at a 50% confidence level (U.S. Geological Survey, 2012). These zones are also actively being evaluated for tight oil potential and several wells were staked in 2013. Anadarko E&P Onshore LLC. drilled a horizontal well, the 3424-2-1H Lewis Road-Fee (SWSW section 2, T. 34 S., R. 24 E.,

SLBL&M, San Juan County), targeting the Gothic shale; no information has been released (IHS Inc., 2013d). Anadarko has three additional horizontal Gothic wells staked 5, 8, and 17 miles to the south, southwest, and southeast, respectively, from the Lewis Road well.



Figure 5. Fresh road cut exposure of Uteland Butte Member of the Green River Formation consisting of interbedded dolomite and mudstone/limestone, Nine Mile Canyon, central Utah.




Figure 6. Pennsylvanian stratigraphic chart for the Paradox Basin, informal organic-rich shale units are highlighted. Modified from Hite (1960), Hite and Cater (1972), and Reid and Berghorn (1981).




Figure 7. Thickness map and exploration play area of the Cane Creek shale zone of the Pennsylvanian Paradox Formation, northern Paradox Basin, Utah, showing Cane Creek fields and 2013 discoveries. Contour interval = 40 ft.



Figure 8. Cane Creek core from the Union Pacific Resources Remington 21-1H well (section 21, T. 31 S., 23 E., SLBL&M, San Juan County, Utah) displays interbedded medium gray dolomite with organic-rich dark gray/black shale. Also present is mottled light gray to white anhydrite.

New Research

The Utah Geological Survey has been awarded funding from the National Energy Technology Laboratory, U.S. Department of Energy for a three-year project titled “Liquid-Rich Shale Potential of Utah’s Uinta and Paradox Basins: Reservoir Characterization and Development.” The overall goal of

this study is to provide reservoir-specific geological and engineering analyses of the (1) emerging Green River Formation tight oil plays (such as the Uteland Butte Limestone Member, Black Shale facies, deep Mahogany zone, and other deep Parachute Creek member high-organic units) in the Uinta Basin, and (2) the established, yet understudied Cane Creek shale (and possibly other shale units such as the Gothic and Chimney Rock shale zones) of the Paradox Formation in the Paradox Basin. To accomplish this goal, the project will:

- Characterize geologic, geochemical, and petrophysical rock properties of target zones in the two designated basin areas by compiling various sources of data and by analyzing newly acquired and donated core, well logs, and well cuttings.
- Describe outcrop reservoir analogs of Green River Formation plays and compare them to subsurface data (not applicable in the Paradox Basin since the Cane Creek shale is not exposed).
- Map major regional trends for targeted liquid-rich intervals and identify “sweet spots” that have the greatest oil production potential.
- Suggest techniques to reduce exploration costs and drilling risks, especially in environmentally sensitive areas.
- Improve drilling and fracturing effectiveness by determining optimal well completion design.
- Suggest techniques to reduce field development costs, maximize oil recovery, and increase reserves.

The project will therefore develop and make available geologic and engineering analyses, techniques, and methods for exploration and production from the Green River Formation tight oil zones and the Paradox Formation shale zones where operations encounter technical, economic, and environmental challenges.

In addition to a thorough geologic characterization of the target zones, tests will be performed to characterize the geomechanical properties of the zones of interest to inform/guide well completion strategies. The brittle characteristics of the target intervals will be studied in detail using energy-based calculations. This approach acknowledges both mechanical properties and in-situ stress conditions, as well as geometric lithologic constraints and the mineralogy that regulates fracturing. The study will establish a template for more effective well planning and completion designs by integrating the geologic characterization and formation evaluation with state-of-the-art rock mechanical analyses. This will help companies access oil they know is present, but technically difficult to recover.

To aid in the identification of hydrocarbon “sweet spots,” novel concepts for exploration will be employed such as the use of low-cost, low-environmental impact, epifluorescence analysis of regional core and well cuttings. Epifluorescence microscopy is a technique used to provide information on diagenesis, pore types, and organic matter (including “live” hydrocarbons) within sedimentary rocks. It is a rapid, non-destructive procedure that uses a petrographic microscope equipped with reflected-light capabilities, a mercury-vapor light, and appropriate filtering. Epifluorescent intensities obtained from core and cuttings will be mapped to help identify areas with potential for significant hydrocarbon production. The detailed reservoir characterization and rock mechanics analyses will provide the basis for identification of “sweet spots” and improve well completion strategies for these undeveloped and under-developed reservoirs.

For more information about this ongoing project, including available posters and talks (in pdf), refer to the Utah Geological Survey’s project website: http://geology.utah.gov/emp/shale_oil.

Recent Presentations

- “Liquid-Rich Shale Potential of Utah’s Uinta Basin: Reservoir Characterization and Development,” by Michael D. Vanden Berg, January 10, 2013, quarterly Uinta Basin Oil and Gas Collaborative Group Meeting, Vernal, Utah.
- “The Uteland Butte Member of the Eocene Green River Formation: An Emerging Unconventional Carbonate Tight Oil Play in the Uinta Basin, Utah,” by Michael D. Vanden Berg, Craig D.

Morgan, Thomas C. Chidsey, Jr., Peter Nielsen, May 19-20, 2013, AAPG Annual Convention, Pittsburgh, Pennsylvania.

- “Current Understanding of the Sedimentology, Stratigraphy, and Liquid-Oil Potential of the Pennsylvanian Cane Creek Shale of the Paradox Formation, Southeastern Utah,” by Peter Nielsen, Craig D. Morgan, and Michael D. Vanden Berg, September 22-24, 2013 AAPG Rocky Mountain Section Meeting, Salt Lake City, Utah.
- “Detailed Sedimentology and Stratigraphy of the Remington 21-1H Cane Creek Shale Core, Pennsylvanian Paradox Formation, Southeastern Utah: Implications for Unconventional Hydrocarbon Recovery,” by Peter J. Nielsen, Craig D. Morgan, and Michael D. Vanden Berg, September 22-24, 2013 AAPG Rocky Mountain Section Meeting, Salt Lake City, Utah.
- “Reservoir Characterization of the Uteland Butte Formation in the Uinta Basin,” by Jason Anderson and John Roesink, September 22-24, 2013 AAPG Rocky Mountain Section Meeting, Salt Lake City, Utah.
- “Temporal and Spatial Variations in Lacustrine Depositional Controls from the Middle to Upper Green River Formation, Central and Western Uinta Basin, Utah,” Leah Toms, Lauren Birgenheier, Michael D. Vanden Berg, September 22-24, 2013 AAPG Rocky Mountain Section Meeting, Salt Lake City, Utah.
- “Geologic Evaluation of the Cane Creek Shale, Pennsylvanian Paradox Formation, Paradox Basin, Southeastern Utah,” Stephanie M. Carney, Peter J. Nielsen, and Michael D. Vanden Berg, April 9, 2014 AAPG Annual Convention, Houston, Texas.

References Cited

- Dubiel, R.F., 2003, Geology, depositional models, and oil and gas assessment of the Green River total petroleum system, Uinta-Piceance Province, eastern Utah and western Colorado, *in* U.S. Geological Survey Uinta-Piceance Assessment Team, compilers, Petroleum systems and geologic assessment of oil and gas in the Uinta-Piceance Province, Utah and Colorado: U.S. Geological Survey Digital Data Series DDS-69-B.
- Fouch, T.D., 1975, Lithofacies and related hydrocarbon accumulations in Tertiary strata of the western and central Uinta Basin, Utah, *in* Bolyard, D.W., editor, Symposium on deep drilling frontiers in the central Rocky Mountains: Rocky Mountain Association of Geologists Guidebook, p. 163-173.
- Hintze, L.F., and Kowallis, B.J., 2009, Geologic history of Utah: Brigham Young University Geology Studies Special Publication 9, 225 p.
- Hintze, L.F., Willis, G.C., Laes, D.Y.M., Sprinkel, D.A., and Brown, K.D., 2000, Digital geologic map of Utah: Utah Geological Survey Map 179DM, scale 1:500,000.
- Hite, R.J., 1960, Stratigraphy of the saline facies of the Paradox Member of the Hermosa Formation of southeastern Utah and southwestern Colorado, *in* Smith, K.G., editor, Geology of the Paradox Basin fold and fault belt: Four Corners Geological Society, Third Field Conference Guidebook, p. 86-89.
- Hite, R.J., and Cater, F.W., 1972, Pennsylvanian rocks and salt anticlines, Paradox Basin, Utah and Colorado, *in* Mallory, W.W., editor, Geologic atlas of the Rocky Mountain region: Rocky Mountain Association of Geologists Guidebook, p. 133-138.
- IHS Inc., 2013a, Rocky Mountain regional report, November 25, 2013, non-pagenated.
- IHS Inc., 2013b, Rocky Mountain regional report, November 4, 2013, non-pagenated.
- IHS Inc., 2013c, Rocky Mountain regional report, August 14, 2013, non-pagenated.
- IHS Inc., 2013d, Rocky Mountain regional report, November 19, 2013, non-pagenated.
- Rasmussen, D.L., 2010, Halokinesis features related to flowage and dissolution of Pennsylvanian Hermosa salt in the Paradox Basin, Colorado and Utah [abs]: American Association of Petroleum Geologists, Rocky Mountain Section Meeting Program with Abstracts, p. 59.

- Reid, F.S., and Berghorn, C.E., 1981, Facies recognition and hydrocarbon potential of the Pennsylvanian Paradox Formation, *in* Wiegand, D.L., editor, *Geology of the Paradox Basin: Rocky Mountain Association of Geologists Guidebook*, p. 111-117.
- Sprinkel, D.A., 2009, Interim geologic map of the Seep Ridge 30' x 60' quadrangle, Uintah, Duchesne, and Carbon Counties, Utah, and Rio Blanco and Garfield Counties, Colorado: Utah Geological Survey Open-file Report 549, compact disc, GIS data, 3 plates, scale 1:100,000.
- Utah Division of Oil, Gas, and Mining, 2014, Oil and gas summary production report by field, October 2013: Online, fs.ogm.utah.gov/pub/Oil&Gas/Publications/Reports/Prod/Field/Fld_Oct_2013.pdf, accessed March 2014.
- U.S. Geological Survey, 2012, Assessment of undiscovered oil and gas resources in the Paradox Basin province, Utah, Colorado, New Mexico, and Arizona, 2011: U.S. Geological Survey Fact Sheet 2012-3021, March 2012, 4 p., online, <http://pubs.usgs.gov/fs/2012/3031/FS12-3031.pdf>, accessed July 25, 2012.

Utica Shale (Ordovician), Appalachian Basin, U.S.

By Rich Nyahay

The Ordovician Utica (Indian Castle), Dolgeville, and Flat Creek are the formations of interest. These shales and interbedded limestones range in TOC from 1- 5% in the dry gas window. They cover an area from Mohawk Valley south to the New York State boundary line with Pennsylvania and extend west to the beginning of the Finger Lakes region and east to the Catskill Mountain region. These three formations have a total thickness from 700 to 1,000 feet.


In Ohio and Pennsylvania the Utica is underlain by organic rich Point Pleasant Formation that is in part the lateral equivalent of the upper portion of the Trenton limestone and is in the gradational relationship with the overlying Utica shale which thickens into the Appalachian Basin. (Wickstom, 2011). The Utica –Point Pleasant interval is up to 300 feet thick in Ohio and over 600 feet thick in southwestern Pennsylvania. The TOC in this interval ranges from 1 to 4 % (Harper, 2011). In Ohio, gas prone areas will be found in the deeper parts of the basin well as appreciable amounts of oil (Ryder, 2008).

In Michigan, the Utica is underlain by the Collingwood Formation in the northern central part of the state. This formation consist of shales that are black to brown and dark gray in color, with a thickness between 25 to 40 feet and TOC range between 2-8 percent (Snowdon, 1984).

GEOLOGY:

The Late Ordovician Utica shale was deposited in a foreland basin setting adjacent to and on top of, the Trenton and Lexington carbonate platforms. Initial deposition of the Trenton and Lexington platform began on a relatively flat Black River passive margin. Early tectonic activity from the Taconic orogeny created the foreland bulge that would become the Trenton and Lexington platforms. Carbonate growth was able to keep up with the overall rise in seal level while areas stayed relatively deeper until increased subsidence in the foreland basin lowered the ramps out of the photic zone and inundated the passive margin with fine grained clastics.(Willan et al. 2012).

The Trenton/Lexington limestone through the Utica Shale comprise the transgressive systems tract (TST) of a large second-order sequence, superimposed with four, smaller scale third-order composite sequences. Third order sequences are regional correlative, aggradational, and lack lowstand deposits. Sequences are separated by type 3 sequence boundaries that amalgamate with transgressive surfaces and separate underlying highstand system tracts(HST's) from overlying TST's(McClain, 2012).




(Riley & Baranowski, 2011)



Smith, 2013 proposes the organic rich section were deposited in shallow water to the west and becomes progressively less organic rich approaching what was the deepest part of the basin due to progressively more dilution from clay and silt that are sourced from the highlands to the east, but it may be the longest duration of anoxic conditions occurred in the shallowest water.

Well Activity:

With the current regulatory moratorium in place in New York, activity has been focused in eastern Ohio, western Pennsylvania and northern Michigan. Ohio current drilling activity as of March, 2014 lists 1148 Utica permits, 770 wells drilled and 385 producing wells (ODNR, 2014). The three biggest operators in the play are Chesapeake Energy with 584 permits, Gulfport Energy with 109 permits, and Antero Resources with 62 permits (Downing, 2014). Well activity has been concentrated further to the south producing mostly dry gas and companies are moving slowly to the west in search of more oil rich deposits (see Initial map production figure below).



(Joy et al. 2000)



Earlier expectations have been dampened by larger companies selling large acreage parcels, pipeline infrastructure not in place, and construction of gas processing units. This concern may be changing because at the current activity has doubled the number of producing wells again from the latest 3rd quarter production reports of 2013. Three cryogenic natural gas plants have been added in Columbia, Harrison, and Noble counties to separate and purify natural gas. (Downing, 2013).

Kinder Morgan Energy Partners LP and Mark West Energy Partners LP and planning a Utica-Marcellus Pipeline to Texas. This project has a target date of second quarter 2016. Spectra Energy Corp is also planning a Utica to Gulf Coast pipeline to operational by November 2015 (Knox, 2014).

An average Ohio Utica well takes between 22-23 days to drill and costs between 8 to 10 million dollars (Downing, 2014).


Ohio:

Three wells in Monroe County are permitted to tap both the Marcellus and Utica Shales. The Magnum Resources Stadler No 3UH was drilled to a depth of 10,653 feet and horizontally drilled 5,050 feet and completed in 20 stages producing 32,5MM cfpd of 97 % methane (Oil & Gas Journal, 2014).

Pennsylvania:

Mercer County of Pennsylvania has been gaining interest with well permits by Halcon Resources(7), Hilcorp Energy(5), Shell Western E&P Inc. – a division of Royal Dutch Shell(3), and Chevron –Appalchia(3).Shell Western E&P Inc. – a division of Royal Dutch Shell also permitted a well in Lawrence County, PA.

OHIO DEPARTMENT OF NATURAL RESOURCES
HORIZONTAL UTICA - PT PLEASANT WELL ACTIVITY IN OHIO




EXPLANATION

- Horizontal well status as of 3/1/2014
- PERMITTED - Permitted, Not Drilled, or Canceled (373)
 - DRILLED - Drilled or Drilling (349)
 - PRODUCING - Producing or Plugged Back (385)
 - INACTIVE - Drilled Inactive or Shut in (1)
 - PLUGGED - Final Restoration or Lost Hole (12)
 - Dry and Abandoned (3)

Well permit information from the ODNR Division of Oil and Gas Resources Management
Recommended citation:
 Ohio Department of Natural Resources, 2014, Horizontal Utica-Point Pleasant Well Activity in Ohio: Columbus, scale 1:1,300,000, revised 3/5/2014.


OPERATOR	COUNT
AMERICAN ENERGY UTICA LLC	11
ANADARKO E & P ONSHORE LLC	12
ANTERO RESOURCES CORPORATION	63
ATLAS ENERGY LLC	8
BEUSA ENERGY LLC	1
BP AMERICA PRODUCTION COMPANY	4
BRAMMER ENGINEERING INC	2
CARRIZO UTICA LLC	5
CHESAPEAKE CORPORATION LLC	618
CHEVRON APPALACHIA LLC	7
ONE GAS COMPANY LLC	39
ENVIRON ENERGY PRODUCTION CO	19
EQUIPS RESOURCES LP	26
EM ENERGY ONSHORE LLC	2
ENERVEST OPERATING LLC	17
EQZ PRODUCTION COMPANY	8
GAFFNEY ENERGY CORPORATION	119
HALLCO OPERATING COMPANY INC	11
HALL DRILLING LLC OIL & GAS	5
HESS OHIO DEVELOPMENTS LLC	46
HILCORP ENERGY LLC	23
HILCORP ENERGY COMPANY	15
INDEN ENERGY SERVICES LLC	5
PRD ENERGY INC	20
RE GAS DEVELOPMENT LLC	28
RESOURCES LLC	4
SERRA RESOURCES LLC	3
SWEP LP	1
TRAD HUNTER LLC	8
UTICA ENERGY INC	5
TOTAL	1128

Map of Southern Ohio Counties with permitted wells with stack reservoirs




(Wickstrom and Shumway, 2014)

Legend for Initial Production




(Wickstrom and Shumway, 2014)

Map of Initial Production



(Wickstrom and Shumway, 2014)




(Harper, 2013)

Halcon Resources tested wells in Crawford, Mercer, and Venango Counties Pennsylvania and has taken 1844 feet of conventional core.

- The Staab1H was drilled to a total measured depth of 11,166 feet, a lateral length of 4,364 feet and completed with 17 frac stages in Crawford County.
- The Pilgrim 2-3H was drilled to a total measured depth of 16,185 feet, a lateral length of 7,320 feet and completed with 31 frac stages in Mercer County.
- The Yoder 2H was drilled to a total measured depth of 10,825 feet, a lateral length of 3,810 feet and completed with 14 frac stages in Mercer County.
- The Phillips 1H was drilled to a total measured depth of 12,411 feet, a lateral length of 5,360 feet and completed with 20 frac stages in Mercer County. It has 304 feet of net pay with an average of 5.1% effective porosity and 72% hydrocarbon saturation.
- The Allam 1H was drilled to a total measured depth of 14,300 feet, a lateral length of 5,580 feet and completed with 21 frac stages in Crawford County. It has 266 feet of net pay with an average of 4.4% effective porosity and 75% hydrocarbon saturation.

Both Phillips and Allam wells were located in the gas/condensate window of the play and have BTU contents of 1250 and 1210, respectively. (Halcon Resources June 13, 2013 news release)

Northwest PA – Utica/Point Pleasant Potential




Note: * CHK rates include ethane



22

Target is Point Pleasant Carbonate Section



23

(Slides Taken from Range Resources Corporation Presentation, July 1, 2012)


Michigan:

Michigan Department of Environmental Quality said it is proposing new rules for the operation commonly known as fracking and expects to implement them next year. (Downing, 2013). This might signal increased exploration activity of the Collingwood.

HIGH VOLUME HYDRAULIC FRACTURING

ACTIVE APPLICATIONS AND ISSUED PERMITS - SINCE 2008*

AS OF 03/18/2014



(Michigan Department of Environmental Quality, 2014)

Completion Techniques:


A new technique used to test the possible productivity of a new well is to set a permanent plug isolating the final stage or the stage closest to the well head while letting the other stages rest, usually three or more months (EID, 10/10/2012).

Gulfport Energy found a 225 foot optimum stage length and is now thinking about 250 ft between laterals.33

HIGH VOLUME (>100,000 gallons) HYDRAULIC FRACTURING SINCE 2008 - ACTIVE PERMITS													
#	Permit #	Company Name	Well Name	Well No.	County	Wellhead T/R/S	Pilot Boring	Comments	Target formation	Well Type	Well Status	Well Status	Confidential
1	181112	BEACON EXPLORATION AND PRODUCTION CO LLC	SCHULTZ	1-38	SANILAC	12N 15E 36	NA	well completed Feb 2012	A1 Carbonate	Oil	Shut-in	NO	NO
2	181123	CHRYSLER ENERGY CO	SCOPER	1-25	OSHTON	17N 10W 26	NA	well completed Aug 2008	Antrim	Gas	Plugging complete	NO	NO
3	180979	ENCANA OIL AND GAS USA INC	PIONEER	1-3	MISSAUKEE	24N 7W 3	59B19	well completed Feb 2010	Utica-Collingwood	Gas	Temporarily abandoned	NO	NO
4	180941	MERT ENERGY COMPANY	HUBBEL	2-22	HDI	MONTMORENCY	28N 1E 22	NA	well completed June 2010	Niagara	Oil	Producing	NO
5	181011	ATLAS RESOURCES LLC	STATE NORMON	1-4	HDI	MISSAUKEE	28N 8W 6	NA	well not hydraulically fractured to date	Utica-Collingwood	Dry Hole	Temporarily abandoned	NO
6	180178	ENCANA OIL AND GAS USA INC	STATE KOEHLER & KENDALL	1-37	HDI	CHEBOYGAN	35N 2W 33	60133	well completed Oct 2010	Utica-Collingwood	Oil	Temporarily abandoned	NO
7	180198	ATLAS RESOURCES LLC	LUCAS	1-13	HDI	KALKASKA	28N 8W 13	60138	well not hydraulically fractured to date	Utica-Collingwood	Not available	Temporarily abandoned	NO
8	180213	COUNTRYMARK RESOURCES INC	KELLY ETAL	1-28	HDI	HILLSDALE	65 2W 26	60538	well completed Sept 2011	Black River (Van Wert)	Production	Producing	NO
9	180380	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	1-13	HDI	KALKASKA	27N 8W 24	60557	well completed Nov 2011	Utica-Collingwood	Gas	Producing	NO
10	180498	TIFFER DEVELOPMENT LLC	STATE GARFIELD & TIGER	1-14	HDI	KALKASKA	25N 8W 14	NA	Well completed Oct 2013	Collingwood	Gas	Temporarily abandoned	NO
11	180380	DEVON ENERGY PRODUCTION COMPANY LP	SCORP	1-24	HDI	OSHTON	15N 10W 26	60539	well completed April/May 2012	A1 Carbonate	Gas	Plugging complete	NO
12	180398	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	1-25	HDI	KALKASKA	28N 8W 1	NA	well completed Nov 2011	Utica-Collingwood	Gas	Producing	NO
13	180452	DEVON ENERGY PRODUCTION COMPANY LP	WILEY	1-18	HDI	GLADWIN	18N 2W 18	60461	well completed May/June 2012	A1 Carbonate	Gas	Plugging complete	NO
14	180528	DEVON ENERGY PRODUCTION COMPANY LP	SCHOK	1-28	HDI	HILLSDALE	65 2W 26	60538	well not hydraulically fractured	A1 Carbonate	Other	Plugging complete	NO
15	180531	CONTINENTAL RESOURCES INC	MCHAR ETAL	1-28	HDI	HILLSDALE	65 2W 26	NA	well completed Oct 2012	Black River (Van Wert)	Gas	Producing	NO
16	180545	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	2-25	HDI	KALKASKA	28N 8W 1	NA	well completed Oct 2012	Utica-Collingwood	Gas	Producing	NO
17	180548	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	2-25	HDI	KALKASKA	28N 8W 1	NA	well completed Oct 2012	Utica-Collingwood	Gas	Producing	NO
18	180560	DEVON ENERGY PRODUCTION COMPANY LP	STATE GARFIELD	1-34	HDI	ROSSCOMMON	22N 1W 27	60569	well completed Nov 2012	Collingwood	Gas	Plugging complete	NO
19	180575	ALTA ENERGY OPERATING LLC	RILEY	1-22	HDI	OCEANA	15N 18W 22	60574	Well completed Dec 2012/May 2013	A1 Carbonate	Oil	Well complete	NO
20	180578	ENCANA OIL AND GAS USA INC	STATE GARFIELD	1-25	HDI	KALKASKA	25N 8W 38	NA	Well completed Dec 2012	Utica-Collingwood	Gas	Well Complete	NO
21	180582	DEVON ENERGY PRODUCTION COMPANY LP	DAVIDS ACRES, LLC	1-19	HDI	OSHTON	22N 4E 19	60561	well not hydraulically fractured	A1 Carbonate	Other	Plugging complete	NO
22	180587	COUNTRYMARK ENERGY RESOURCES LLC	ARNO	1-25	HDI	HILLSDALE	65 2W 26	NA	permit for horizontal well	Black River (Van Wert)	Location	Permitted Well	NO
23	180598	COUNTRYMARK ENERGY RESOURCES LLC	ARNO & TIMMONS	1-24	HDI	HILLSDALE	65 2W 24	NA	permit for horizontal well	Black River (Van Wert)	Location	Permitted Well	NO
24	180601	ENCANA OIL AND GAS USA INC	WESTERMAN	1-32	HDI	KALKASKA	28N 8W 28	60600	No completion records on file	Utica-Collingwood	Location	Drilling complete	NO
25	180608	ENCANA OIL AND GAS USA INC	STATE MENTOR	1-17	HDI	CHEBOYGAN	34N 3W 17	NA	permit for horizontal well (05052)	Utica-Collingwood	Location	Permitted Well	YES
26	180615	ROSETTA RESOURCES OPERATING LP	STATE ORANGE & CHRISTENSEN	1-21	HDI	IONA	8N 8W 21	60614	Well completed June 2013	A1 Carbonate	Dry Hole	Well complete	NO
27	180617	DEVON ENERGY PRODUCTION COMPANY LP	TOUNMAN	1-29	HDI	MISSAUKEE	21N 8W 28	60601	well not hydraulically fractured	Utica	NA	Plugging complete	NO
28	180621	ENCANA OIL AND GAS USA INC	STATE BEAVER CREEK	1-23	HDI	CRAWFORD	25N 4W 11	60620	well completed May 2013	Utica-Collingwood	Gas	Well Complete	NO
29	180622	COUNTRYMARK ENERGY RESOURCES LLC	STEVENSON & FRENCH	1-25	HDI	HILLSDALE	65 2W 24	NA	well not hydraulically fractured	Black River (Van Wert)	Dry Hole	Plugging complete	NO
30	180672	ENCANA OIL AND GAS USA INC	STATE ROSSCOMMON	1-13	HDI	ROSSCOMMON	21N 4W 17	60670	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
31	180674	MILZI OIL CORPORATION	BURNS	1-13	HDI	HILLSDALE	65 2W 22	NA	permit for horizontal well	Black River (Van Wert)	Location	Permitted Well	NO
32	180688	ENCANA OIL AND GAS USA INC	STATE GARFIELD	1-23	HDI	KALKASKA	25N 8W 28	60665	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
33	180718	JORDAN DEVELOPMENT CO LLC	STATE JEROME & STARNES	1-5	HDI	MELAND	8N 1W 8	60717	No completion records on file	Dundee	Location	Drilling complete	NO
34	180748	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	1-14	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
35	180747	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	1-12	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
36	180748	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	1-11	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
37	180749	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	2-14	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
38	180750	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	2-12	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
39	180755	ROSETTA RESOURCES OPERATING LP	SWANSON TRUST	1-11	HDI	MISSAUKEE	4N 14W 11	60754	permit for horizontal well	A1 Carbonate	Location	Permitted Well	YES
40	180755	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	3-12	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
41	180758	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	4-12	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
42	180757	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	5-12	HDI	KALKASKA	27N 8W 24	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
43	180758	UNION GAS OPERATING COMPANY	MERTEN	1-24	HDI	OCEANA	15N 17W 24	60787	permit for horizontal well	A1 Carbonate	Location	Permitted Well	NO
44	180800	WHITING OIL AND GAS CORPORATION	WALKER	11-25	HDI	SANILAC	12N 15E 25	60888	permit for horizontal well	A1 Carbonate	Location	Permitted Well	NO
45	180811	OCOSOUTHERN OPERATING LLC	SHERWOOD	1-22	HDI	LIVINGSTON	4N 3E 23	60884	permit for horizontal well	A1 Carbonate	Location	Permitted Well	YES
46	180818	ENCANA OIL AND GAS USA INC	STATE OLIVER	2-13	HDI	KALKASKA	28N 8W 1	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
47	180818	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	4-25	HDI	KALKASKA	28N 8W 1	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
48	180820	ENCANA OIL AND GAS USA INC	STATE OLIVER	2-13	HDI	KALKASKA	28N 8W 1	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
49	180821	ENCANA OIL AND GAS USA INC	STATE OLIVER	1-13	HDI	KALKASKA	28N 8W 1	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
50	180822	ENCANA OIL AND GAS USA INC	STATE EXCELSIOR	5-28	HDI	KALKASKA	28N 8W 1	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
51	180826	WHITING OIL AND GAS CORPORATION	STATE WHEATLAND & RENELET	11-17	HDI	SANILAC	13N 14E 7	60855	permit for horizontal well	A1 Carbonate	Location	Permitted Well	YES
52	180848	ENCANA OIL AND GAS USA INC	STATE PIONEER	3-4	HDI	MISSAUKEE	34N 7W 3	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
53	180891	ENCANA OIL AND GAS USA INC	STATE NORMON	2-12	HDI	KALKASKA	25N 8W 28	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
54	180892	ENCANA OIL AND GAS USA INC	BLACK RIVER CONSERVATION ASSN	1-8	HDI	KALKASKA	27N 5W 28	NA	permit for horizontal well	Utica-Collingwood	Location	Permitted Well	YES
55	180922	OIL ENERGY CORP	STATE CUSTER AND MUNN	00-8	HDI	ANTRIM	28N 7W 6	NA	permit for directional well	Antrim	Location	Permitted Well	NO
56	180930	WHITING OIL AND GAS CORPORATION	RICH ET AL	11-23	HDI	SANILAC	12N 15E 4	60907	permit for horizontal well	A1 Carbonate	Location	Permitted Well	YES

HIGH VOLUME (>100,000 gallons) HYDRAULIC FRACTURING PROPOSALS - ACTIVE APPLICATIONS													
#	App #	Company Name	Well Name	Well No.	County	Wellhead T/R/S	Pilot Boring	target formation	comments				
1	14130152	BLACK RIVER CONSERVATION ASSN	STATE CUSTER AND BOG	03-31	KALKASKA	27N 5W 28	NA	Utica-Collingwood	application for horizontal well				
2	24130184	DILL ENERGY CORP	STATE CUSTER AND BOG	03-31	ANTRIM	28N 7W 6	NA	Antrim	application for a directional well				

(Michigan Department of environmental Quality, 2014)



(Michigan Department of environmental Quality, 2014)


The basic completion concept is to drill with long laterals, have short stages, and shut in the well for a determined resting period.

The Utica is still in its infancy, everyone is still trying to get the oil and liquids from the Formation. With all the wells scheduled to be drilled in 2013, looking at more geological and petrophysical data that will be generated from each well will further define the future of Utica Play in the Appalachian Basin.

GEOCHEMISTRY:


In May of 2012, a TOC (Total Organic Content) map generated by the Ohio Geological Survey caused a fall out between the State Geologist and critics from southeastern counties of Ohio. The main criticism of the map was the limited amount data points in the southeastern part of the state which may have caused limited interest and lower lease and bonus prices offered to landowners. This newer map does seem to justify extending the play to the southeast.

New SEM images from Gulfport Energy well show porosity and permeability is associated with organic matter and organic horizontal fractures might indicate overpressure.




Optimum Stage Length


(Gulfport Energy Inc DUG East 11-14-2012)



Lateral spacing consideration of Gulfport Energy Inc (Gulfport Energy Inc DUG East 11-14-2012)



Production Log from a Gulfport Energy well (Gulfport Energy Inc DUG East 11-14-2012)




(ODNR, March 2013)

ISSUES: The Ohio Division of Natural Resources confirmed 11 low magnitude earthquakes that occurred near Hilcorp Energy Corp’s well pad operations in Poland Township Ohio. The series of earthquakes were recorded by both the USGS and Columbia University’s Lamont-Doherty Earth Observatory. The USGS confirmed five earthquakes ranging from 2.1 - 3.0 magnitude and Columbia University’s Lamont-Doherty Earth Observatory registered six lower magnitude shocks in other places in the region (McParland, T., 2014)

The first quake occurred at a depth of 1.2 miles and the second quake was recorded at a depth of 3 miles (Obrien, D., 2014). The Precambrian basement is at 9000 feet and the vertical depth of the Hilcorp Energy well in the area is at a depth of 7900 feet.

These earthquakes have brought attention to whether fracking causes these earthquakes or are they naturally occurring. Ohio records show that the area between 1950 and 2009 averaged 2 earthquakes annually with magnitude 2.0 or greater. Between 2010 and 2014 the average rose to nine (Drabold, W., 2014). The Ohio Division of Natural Resources has halted operations and have been petitioned by local residences to set up a seismic network in the area to monitor operations. The area is close to the Youngstown where an injection well was determined to cause earthquakes in 2011.

Governor Kasich has proposed a flat tax of 2.75% on producer’s gross receipts (Provance, J., 2014).



Ion Milled SEM Images of the Point –Pleasant Formation (Gulfport Energy Inc DUG East 11-14-2012)

SITES:

<http://geosurvey.ohiodnr.gov/major-topics/interactive-maps> This website will lead you downloadable oil and gas data in Ohio as well as information on type logs, cores and instructions on how to download digital and raster geophysical logs.

<http://esogis.nysm.nysed.gov> This is the website to go for information on well logs, formation tops, core, and well samples. At this website many studies on New York reservoirs sponsored by NYSERDA can be downloaded for free.

<http://www.dec.ny.gov/energy/205.html> This is the website to find out information on wells being permitted, well spacing and all state regulations regarding oil and gas well drilling. This also the website to download the 1000 page draft Supplemental Generic Environmental Impact.

<http://oilandgas.ohiodnr.gov/shale#SHALE> This is the website to get weekly activity and yearly production information in Ohio.

REFERENCES CITED:

- Baird, G.C., and Brett, C.E., 2002, Indian Castile: late synorogenic siliciclastic succession in an evolving Middle to Late Ordovician foreland basin, eastern New York State. *Physics and Chemistry of the Earth*, v. 27, p. 203-230.
- Cole, G.A., and others, 1987, Organic Geochemistry and Oil-Source Correlations, Paleozoic of Ohio, *AAPG Bulletin*, v. 71, No. 7, p. 788-809.
- Cross, G.E., 2004, Fault-related mineralization and fracturing in the Mohawk Valley, Eastern New York State. Master’s Thesis, SUNY at Buffalo, 251p.
- Drabold, W., 2014, Scientists study Ohio’s quakes, fracking, <http://www.dispatch.com/content/stories/local/2014/03/16/scientists-study-quakes-fracking.html>
- Downing, R., 2014, “More details from anticipated state report on Utica shale drilling”, posted 03-17-2014. <http://Ohio.com>
- Energy In Depth, “Update II- Gulfport Has More Exciting New’s For Ohio’s Utica Shale” posted 10-10-2012. <http://www.eidohio.org/gulfport-has-more-exciting-news-for-Ohioans/>

- Fisher, D.W., 1979, Folding in the Foreland, Middle Ordovician Dolgeville Facies, Mohawk Valley. *Geology*, v.7, p. 455-459.
- Goldman, D., Mitchell, C.E, Bergstrom, S.M, Delano, J.W., and Tice, S., 1994, K-Bentonite and graptolite biostratigraphy in the Middle Ordovician of New York State and Quebec: A new chronostratigraphic model. *Palaios*, v. 9, p. 124-143.
- Gulfport Energy Incorporated, Proving up the Utica's Liquids Window, Presentation made at DUG in Pittsburgh, PA, November 14, 2013.
- Halcon Resources, 2013, Halcon Provides Operational Update: Halcon Resources Press Release, June 10, 2013, <http://investors.halconresources.com/releasedetail.cfm?ReleaseID=770152>
- Jarvie, D.M., 2012, Geochemical Assessment of the Utica and Point Pleasant Shale, Ohio, USA: Abstracts with Programs Association of Petroleum Geologist, Eastern Section Meeting, Cleveland, Ohio, p38.
- Jacobi, R.D., and Mitchell, C.E., 2002, Geodynamical Interpretation of a major unconformity in the Taconic Foredeep: Slide scar or onlap unconformity. *Physics and Chemistry of the Earth*, v. 27, p.169-201.
- Joy, M.P., Mitchell, C.E., and Adhya, S., 2000, Evidence of a tectonically driven sequence succession in the Middle Ordovician Taconic Foredeep. *Geology*, v. 28, p.727-730.
- Joy, M.P., 1996, Evolution of the Facies Mosaic in the Taconic Foredeep Basin, Central Mohawk Valley, NY: A Graphic Correlation Approach. unpublished MA thesis, SUNY Buffalo, Buffalo, NY, 101 pp.
- Knox, T., 2014, "Open season over for Kinder Morgan – Mark West pipeline project" posted 03-03-2014. <http://www.bizjournals.com/columbus/news/2014>
- Laughrey, C.D., Ruble, T.E., Wickstrom, L.H., Kostelnik, J., Drozd, R.J., Heim, L.R., and Alcorn, G.A., 2012, Geochemical Interpretation Pitfalls in the Utica, Point Pleasant, and Trenton Formation (Upper Ordovician) Tight Petroleum Play, Eastern Ohio, USA: Abstracts with Programs Association of Petroleum Geologist, Eastern Section Meeting, Cleveland, Ohio, p43.
- Martin, J.P., Hill, D.G., Lombardi, T.E., and Nyahay, R., 2008, A primer on New York's gas shales. *New York State Geological Association Guidebook*, p A1 - A32.
- McClain, T.G., 2012, Sequence Stratigraphy and Petrophysics of the Utica Shale and Associated Late Ordovician Strata, Eastern Ohio and Western Pennsylvania: Abstracts with Programs Association of Petroleum Geologist, Eastern Section Meeting, Cleveland, Ohio, p47.
- McParland, T, 2014, Frackfree group expresses concern, <http://www.vindy.com/news/2014/mar/13/data-on-poland-quakes-studied/?fracking>
- Mehrtens, C.J., 1988, Bioclastic turbidites in the Trenton Limestone: Significance and criteria for recognition. In: Keith, B.D., (Ed.), *The Trenton Group (Upper Ordovician Series) of eastern North America; deposition, diagenesis, and petroleum*. American Association of Petroleum Geologists Studies in Geology, 29, p. 87-112
- Michigan Department of Environmental Quality, 2014, <http://michigan.gov/deq>
- Morgan, R., Youngstown residents react to fracking wastewater dump: *Timesonline.com.*, February 6, 2013.
- Nyahay, R. E., Leone, J., Smith, L., Martin, J., and Jarvie, D., 2007, Update on Regional Assessment of Gas Potential in the Devonian Marcellus and Ordovician Utica Shales of New York, Thirty-Sixth Meeting of the Eastern Section, American Association of Petroleum Geologists, Lexington, KY, September 16-18, 2007, Search and Discovery Article #10136.
- Obrien, D., 2014, Drilling halted after quakes near Hilcorp wells, <http://businessjournaldaily.com/drilling-down/drilling-halted-after-quakes-near-hilcorp-wells-2014-3-11>
- Ohio Division of Natural Resources, 2014, <http://oilandgas.ohiodnr.gov/shale>
- Oil and Gas Journal, 2014, Magnum-Hunter find Utica gas, <http://www.ogj.com/articles/2014/02/magnum-hunter-finds-utica-gas.html>

- Passey, Q.R., Creany, S., Kulla, J.B., Moretti, F.J., and Stroud, J.D., 1990, A Practical Model for Organic Richness from Porosity and Resistivity Logs: The American Association of Petroleum Geologists Bulletin, v. 74, no.12, p. 1777-1794
- Provance, J., 2014, Ohio Funding – Governor proposes tax changes-Kasich eyes boosting cigarette, drilling fees, <http://www.toledoblade.com/Politics/2014/03/12/Governor-proposes-tax-changes.html>
- Reed, J., Brown, S., and Zumberge, J., 2012, Hydrocarbon Potential of the Utica/Point Pleasant In Eastern Ohio and Western Pennsylvania: Abstracts with Programs Association of Petroleum Geologist, Eastern Section Meeting, Cleveland, Ohio, p54.
- Range Resources Corporation, 2012, Infection Report “An event that results in a significant change in the progress of a company”: Range Resources Corporation Presentation July 1, 2012.
- Riley, R.A., 2010, A Utica-Point Pleasant type log for eastern Ohio: Ohio Department of Natural Resources, Division of Geological Survey, one sheet (PDF), available at <http://www.dnr.state.oh.us/Portals/10/Energy/Utica/TuscarawasWellRockAnalyses.pdf>
- Riley, R.A., and Baranowski, M., Regional Stratigraphic and Facies Relationships of the Ordovician Utica/Point Pleasant Interval in the Appalachian Basin: Taking a Deeper Look at Shales: Geology and Potential of the Upper Ordovician Utica Shale in the Appalachian Basin, June 21, 2011, New Philadelphia, Ohio.
- Ryder, R.T., 2008, Assessment of Appalachian basin oil and gas resources: Utica-Lower Paleozoic Total Petroleum System: U.S. Geological Survey Open-File Report 2008–1287
- Ryder, R.T., Burruss, R.C., and Hatch, J.R., 1998, Black Shale Source Rock and Oil Generation in the Cambrian and Ordovician of the Central Appalachian Basin, USA: American Association of Petroleum Geologists Bulletin, v.82, p 412 – 441.
- Smith, L.B., 2013, Shallow Transgressive Onlap Model for Ordovician and Devonian Organic-Rich Shales, New York State: SPE Unconventional Resources Technology Conference, 12-14 August, Denver, Colorado, USA
- Snowdon, L.R., 1984, A comparison of RockEval pyrolysis and solvent extract from the Collingwood and Kettle Point oil shales, Ontario: Bulletin of Canadian Petroleum Geology, v.32, p. 327-334.
- United States Geological Survey, 2012, Assessment of Undiscovered Oil and Gas Resources of the Ordovician Utica Shale of the Appalachian Basin Province, 2012: USGS Fact sheet 2012-3116, 6p.
- Wallace L.G. and Roen, J.B., 1989, Petroleum source rock potential of the Upper Ordovician black shale sequence, northern Appalachian basin: U. S. Geological Survey Open-file report 89-488, 66 p.
- Willan, C.G., McCallum, S.D., and Warner, T.B., 2012, Regional Interpretation of the Late Utica Ordovician Shale Play in the Appalachian Basin: Abstracts with Programs Association of Petroleum Geologist, Eastern Section Meeting, Cleveland, Ohio, p 62.
- Wickstrom, L.H., J.D. Gray, and R.D. Stieglitz, 1992, Stratigraphy, structure, and production history of the Trenton Limestone (Ordovician) and adjacent strata in northwestern Ohio; Ohio Division of Geological Survey, Report of Investigations No. 143, 78 p., 1 pl.
- Wickstrom, L.H., Erenpreiss, M., Riley, R., Perry, C., and Martin, D., 2012, Geology and Activity Update of the Ohio Utica-Point Pleasant Play, <http://www.ohiodnr.com/portals/10/energy/Utica/Utica-PointPleasantPlay.pdf>
- Wickstrom, L.H., and Shumway, 2014, 2013 Ohio Exploration Report, <http://ooga.org/wp-content/uploads/2014OOGAWM-FRI-Exploration-Wickstrom-small.pdf>

Woodford Shale (Late Devonian-Early Mississippian), Anadarko, Arkoma, and Ardmore Basins, U.S.

by Brian Cardott (Oklahoma Geological Survey).

The Oklahoma Geological Survey has a database of all Oklahoma shale gas and shale oil well completions (<http://www.ogs.ou.edu/level3-oilgas.php>). The database of 3,195 well completions from 1939 to February 2014 contains the following shale formations (in alphabetical order) and number of completions: Arkansas Novaculite (3), Atoka Group shale (1), Barnett Shale (2), Caney Shale or Caney Shale/Woodford Shale (107), Excello Shale/Pennsylvanian (2), Sylvan Shale or Sylvan Shale/Woodford Shale (13), and Woodford Shale (3,037). Shale wells commingled with non-shale lithologies are not included. Exceptions include 18 Sycamore Limestone/ Woodford Shale, 9 Mississippian/Woodford Shale, and 3 Hunton Group carbonate/Woodford Shale horizontal completions where non-Woodford perforations were minimal. The database was originally restricted to shale-gas wells. Shale-oil wells have been added since 2004. Figure 1 illustrates 2,996 Oklahoma shale gas and shale oil well completions (1939–2013) on a geologic provinces map of Oklahoma.




Figure 1. Map showing Oklahoma shale gas and shale oil well completions (1939–2013) on a geologic provinces map of Oklahoma.

Since 2004, the Woodford Shale-only plays of Oklahoma have expanded from primarily one (Arkoma Basin) to four geologic provinces (Anadarko Basin, Ardmore Basin, Arkoma Basin, and Cherokee Platform) and from primarily gas to gas, condensate, and oil wells (Figure 2). The recent low price of natural gas has shifted the focus of the plays more toward condensate (“Cana” for western Canadian County or “SCOOP” for “South Central Oklahoma Oil Province” play in the Anadarko Basin and western Arkoma Basin) and oil (northern Ardmore Basin, “Cana”, “SCOOP”, and north-central Oklahoma) areas. Of the 3,017 Woodford-only well completions from 2004–February 2014, 420 wells are classified as oil wells and 2,614 wells are horizontal wells. Vertical depths range from 388 ft (Mayes Co.) to 16,259 ft (Caddo Co.). Initial potential gas rates range from a trace to 12 million cubic feet per day. Initial potential oil/condensate rates range from a trace to 1,059 barrels per day. Reported oil gravities range from 21 to 66 API degrees.




Figure 2. Map showing 2,822 Woodford Shale-only gas and oil well completions (2004–2013) on a geologic provinces map of Oklahoma.

The annual peak of 534 Woodford Shale wells occurred in 2008 (Figure 3). Following the drop in natural gas prices in 2008, the emphasis in the Woodford Shale plays has been for oil- and condensate-producing wells. Figure 4, showing Woodford Shale wells from 2011–2013, illustrates the expansion of the Woodford Shale condensate play in the Anadarko Basin which began in Canadian County (“Cana”) in 2007 and South Central Oklahoma Oil Province (“SCOOP”) in 2012.




Figure 3. Histogram showing numbers of Woodford Shale and Caney Shale well completions, 2004–February 2014.

The four Woodford shale plays in Oklahoma are as follows:

- 1) western Arkoma Basin in eastern Oklahoma with thermogenic methane production at thermal maturities from <1% to >3% vitrinite reflectance (VRo) and condensate production up to 1.67% VRo (Figure 5);
- 2) Anadarko Basin (“Cana” and “SCOOP” plays) in western Oklahoma with thermogenic methane production at thermal maturities from 1.1% to >1.6% VRo and condensate production at thermal maturities up to ~1.5% VRo (Figure 6);
- 3) Ardmore Basin in southern Oklahoma with oil, condensate, and thermogenic methane production at thermal maturities in the oil window (<1.8% VRo) (Figure 7);
- 4) north-central Oklahoma (Cherokee Platform and Anadarko Shelf) with oil and thermogenic methane production at thermal maturities <1.0% VRo (Figure 2).




Figure 4. Map showing Woodford Shale-only gas and oil well completions (2011-2013) on a geologic provinces map of Oklahoma.




Figure 5. Map showing initial potential liquid hydrocarbon production of Woodford Shale-only gas and oil well completions (2004-2013) in the Arkoma Basin of eastern Oklahoma.




Figure 6. Map showing initial potential liquid hydrocarbon production of Woodford Shale-only gas and oil well completions (2004-2013) in the Anadarko Basin of western Oklahoma.

Of 32 operators active in Oklahoma shales during 2013, the top ten operators (for number of wells drilled during 2013) are:

- (1) Devon Energy Production Co. LP (145)
- (2) XTO Energy (103)
- (3) Cimarex Energy (41)
- (4) Continental Resources (37)
- (5) Newfield Exploration Mid-Continent Inc. (29)
- (6) Red Fork (USA) Investments (18)
- (7) QEP Energy (14)
- (8) Petroquest Energy (12)
- (9) Marathon Oil (9)
- (10) BP America Production Company (8)




Figure 7. Map showing initial potential liquid hydrocarbon production of Woodford Shale-only gas and oil well completions (2004-2013) in the Ardmore and Marietta basins of southern Oklahoma.

References

Cardott, B.J., 2012, Thermal maturity of Woodford Shale gas and oil plays, Oklahoma, USA: International Journal of Coal Geology, v. 103, p. 109-119.

Cardott, B.J., 2013a, Woodford Shale: From hydrocarbon source rock to reservoir: AAPG Search and Discovery Article 50817, 85 p.

Cardott, B.J., 2013b, Overview of Oklahoma shale resource plays: Oklahoma Geological Survey, Oklahoma Shale Gas and Oil Workshop presentation, 56 slides. <http://www.ogs.ou.edu/MEETINGS/Presentations/2013Shale/2013ShaleCardott.pdf>

Cardott, B.J., 2014, Determining the thermal maturity level at which oil can be economically produced in the Woodford Shale: American Business Conferences, Woodford Oil Congress 2014 presentation, 92 slides. <http://www.ogs.ou.edu/fossilfuels/pdf/2014CardottOilCong.pdf>

Canadian Shales

By Jock McCracken (Egret Consulting)

Even though Canada has an abundance of conventional oil and natural gas, new unconventional gas, liquids and oil plays dominate the headlines. Most of these shale opportunities lie within the Western Canadian Sedimentary Basin (WCSB) which is a vast sedimentary basin underlying 1,400,000 square kilometres (540,000 sq mi) of Western Canada including southwestern Manitoba, southern Saskatchewan,

Alberta, northeastern British Columbia, southeast corner of the Yukon and the southwest corner of the Northwest Territories. It consists of a massive wedge of sedimentary rock extending from the Rocky Mountains in the west to the Canadian Shield in the east. This wedge is about 6 kilometres (3.7 mi) thick under the Rocky Mountains, but thins to zero at its eastern margins. The WCSB contains one of the world's largest reserves of petroleum and natural gas and supplies much of the North American market, producing about 658,000 BOPD and 14 MCFD gas. It also has huge reserves of coal. Of the provinces and territories within the WCSB, Alberta has most of the oil and gas reserves and almost all of the oil sands.

The first announcement of new discoveries in shale occurred in Canada at the beginning of 2008, six years ago. Now, about 25% of Canada's natural gas is coming from unconventional which would include tight sands. The state of development for the shale plays range from speculative to exploratory to emerging to developing and under increasing commercial production. Typically, production numbers from government websites are up to one year or more behind. Additional production numbers and exploration statistics for this report are therefore gathered from press releases and presentations from some of the key companies involved with the plays. As a result of the low natural gas prices operators have been focusing exploration and production into the liquids-rich hydrocarbons. The following plays are under development and increasing the production yearly: Horn River and Montney in N.E. B.C., Duvernay and Alberta Bakken in Alberta and the Bakken oil play (tight oil play encased in shale) in Saskatchewan and Manitoba.

There have been other shale that have been disappointments for technical and regulatory reasons. Significant shale gas wells have been drilled and tested in the St. Lawrence Lowlands of Québec but a government freeze on fracking because of about environmental concerns will slow down any future exploration and production. The positive announcements out of New Brunswick have been tempered by recent disappointing results and low gas prices. To date there is shale exploration activity in 9 provinces of Canada out of the 10 with Prince Edward Island being the exception. One of the three Territories of Canada, the Northwest Territories, is just now seeing the drilling of their first wells into a possible oil-bearing shale section. The Yukon is evaluating their shale plays as well.

As a further note, there has been significant public concern in the press about hydraulic fracturing in various locations across Canada which is hindering or slowing down exploration and/or production. These concerns, especially in Provinces where there is limited oil and gas exploration and production, are being with by greater transparency and self-imposed industry guidelines.

<http://www.capp.ca/aboutUs/mediaCentre/NewsReleases/Pages/GuidingPrinciplesforHydraulicFracturing.aspx>


<http://www.capp.ca/getdoc.aspx?DocId=210903&DT=NTV>

A number of provincial and territorial governments are reviewing these practices (Quebec, Nova Scotia, New Brunswick and Newfoundland and both the Yukon and North West Territory). Alberta recently updated their regulations. It is hopeful, at the end of this discussion, hydraulic fracturing will be managed such that it will minimize potential risks and allow the public to have a balanced and realistic sense of the costs and benefits.

NORTHEAST BRITISH COLUMBIA

Northeast British Columbia contains Cretaceous to Devonian aged shale deposits that potentially could contain 1200 TCF of natural gas of which 78 TCF is estimated to be marketable. This shale gas interest has therefore dominated the sale of petroleum and natural gas (PNG) rights from the province in the last eight years with the Horn River Basin, the Cordova Embayment and the Montney Play trend generating the most interest. Recently the Liard Basin or Beaver River Area has come on to the radar screen with most of the basin almost entirely licensed. British Columbia has developed Natural Gas and Liquefied Natural Gas Strategies considering the immensity of this resource. The Montney play is garnering much interest because of its liquids component and is now producing at more than 1.74 BCFD as of March 2013. Crown land sale bonuses for these NE BC areas accounted for almost \$5 billion since the record year in 2008. The total for 2013 was \$225 million (see chart below). Capital spending by operators was estimated to be approximately 11 billion in 2011 and 2012. Operators are now conducting

evaluation and drilling programs on their accumulated lands. These BC shale regions are summarized below from Adams, 2013.





http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/statsactivity/Documents/Summary%20of%20Shale%20Gas%20Activity%20in%20NEBC%202012_Oil%20and%20Gas%20Reports%202013-1.pdf


<http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/statsactivity/Documents/5th%20NE%20BC%20Nat%20Gas%20Summit.pdf>

<http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/statsactivity/Documents/Adams.pdf>


The gas production for the Horn River and Montney are also shown.

http://www.csur.com/images/CSUG_presentations/Allan_presentation_CERI_2014_Natural_Gas_Conference.pdf





Bonuses Paid for PNG Rights in BC's Shale Gas Regions



- Land brokers and producers have focused on purchasing PNG rights in the Montney play trend in 2011, 2012 and 2013.
- Shale gas regions accounted for 87% of total bonuses in 2012.
- So far this year, over 98% of the bonus total has resulted from PNG rights sold within the Montney play region.







TABLE 1. POTENTIAL SHALE GAS FORMATIONS IN NORTHEAST BRITISH COLUMBIA

PROSPECTIVE HORIZONS						
	Formations	Description	Depth	Average Thickness	Total Organic Carbon	Gas in Place
LOWER CRETACEOUS	Wirich and Buckingham shales	Potential interbedded sand/siltstone	800 to 1,200 metres	100 metres	2.3%	60 Bcf per section
JURASSIC	Nordegg and Fernie shales	Recognized source rocks	1,200 to 2,500 metres	Up to 30 m organic rich section	up to 14%	>20 Bcf per section
TRIASSIC	Doig, Doig Phosphate and Montney	Montney turbidites may increase permeability Phosphate units have high TOC and are excellent source rocks	1,200 to 3,000 metres	300 to 500 metres	0.5 to >10%	10 to 110 Bcf per section
DEVONIAN	Exshaw, Besa River, Fort Simpson Horn River and Muskwa	Exshaw and Muskwa are widely distributed organic shales Fort Simpson and Besa River are thick basin-filling shales	1,800 to 3,500 metres	Huge thicknesses are common with some high TOC intervals	0.5 to >10%	10 to 100 Bcf per section
GEOLOGIC ANALOGUE						
MISSISSIPPIAN	Barnett Shale (Fort Worth Basin)	Marine-shelf deposit	2,000 to 2,500 metres	100 metres	4.5%	140 Bcf per section



Upper and Middle Devonian, Evie (Klua), Otter Park and Muskwa members of the Horn River Formation Horn River Basin, Cordova Embayment and the Liard Basin

Of these very far north basins, the Horn River has the most activity. Recent government reports state that the Horn River production was, March 2013, approximately 480 MMCFD from 121+ producing wells increasing from roughly 80 MMCFD at the end of 2009 and a cumulative gas production of approximately 343 BCF (April 2013).



The following eleven operators form the Horn River Producers Group, which is a co-operative endeavor set up to share ideas and reduce the footprint: Apache, ConocoPhillips, Devon, EnCana, EOG Resources, Imperial Oil, Nexen, Pengrowth, Suncor, Quicksilver and Stone Mountain. There are another 18+ companies working this area including SMR Oil and Gas, Spoke Resources, Husky, Harvest, Taqa North, Storm Gas Resources, Canadian Natural Resources, Ramshorn Canada, Husky Oil and Delphi. There have been 379 shale gas –directed wells drilled since 2003. The companies with the most acreage are Encana, 260,000 ac, ExxonMobil, 250,000 ac., Apache, 200,000 ac., EOG, 130,000 ac., Quicksilver, 127,000 ac., Devon, 100,000 ac., Nexen, 88,000 ac., and Taqa North, 31,500 ac. (Hart E&P May 2011) It is said that the entire Horn River has marketable gas at 78 TCF. <http://www.energy-pedia.com/news/canada/new-150721> The five companies with the most drilling, as of end of 2011, were Apache, Encana, Nexen, EOG, Imperial Oil, Devon and Quicksilver. Encana has been the most active drilling 82 shale wells since 2003 with their production (April 2013) at 144 MMCFD. They lead the way with multiple fracture stimulations of up to 28 per well as well as the longest laterals of up to 3 kilometres long. Apache has been active since 2003. Their production (April 2013) in the Horn River was 45MMCF/D from 72 wells on 7 pads. Their net recoverable resource is 9.2 TCF. Apache has up to 16 wells on a pad.

Encana and Apache have entered into a partnership sourcing fracturing water from the Mississippian Debolt Formation. Encana and Kogas Canada Ltd., a subsidiary of Korea Gas Corporation (KOGAS), have entered into a three-year exploration and production agreement with the first well pad expecting gas production this summer. EOG completed 11 wells in 2010 but planning minimal drilling after that to hold the acreage. They drilled three wells testing and producing the Evie member at 16-22 MMCFD. In the first quarter of 2013 they decided to sell their interest in the Kitimat LNG project as well as 28,000 acres of their Horn River acreage to Chevron. They still hold 127,000 acres with an estimated 7 TCF potential until 2020. Nexen, which was recently purchased by CNOOC Limited of China, is expecting production to be 200 MMCF/D by 2013. By the 3rd quarter of 2011, they fractured and completed and brought on stream gas from their 9 well pad. With the completion of this pad they expect to ramp up production to 50 MMCFD. They have another pad with 18 wells coming on stream in late 2012. They have drilled, as of April 2013, 66 wells and are producing 52 MMCF/D. Their previously announced shale gas joint venture with INPEX Gas British Columbia Ltd. (IGBC) closed in August. Devon with 174,000 acres has the potential to produce up to 700 MMCFD based on its good land position and in the thickest part of the Basin. They have drilled 26 wells. Eight horizontal wells are producing.

ExxonMobil and its 50% partner Imperial Oil have been encouraged by their 10 plus wells over their large 340,000 acre position. They are therefore setting up a multi-well horizontal pad pilot development in one of their areas. Production began on schedule from an eight-horizontal-well pad in August 2012 to assess productivity and improve development costs. Imperial continues to evaluate information from the pilot phase to determine long-term plans for the development.

Quicksilver has drilled 16 wells on their 140,420 acreage and are now producing at an average 50 MMCF/D. They were also planning to drill an oil-rich horizontal leg into a section considered to be “Exshaw/Bakken zone” within the Horn River area which was probably uneconomic.





- Calendar daily gas production in April 2013 was approximately 374 mmcf per day from 121 producing shale gas wells.
- Cumulative production of 343 Bcf from April 2005 to April 2013
- No production volumes reported for wells that remain on confidential status.

The Laird Basin, straddling the Yukon, North West Territory and British Columbia, containing has great potential with 3 million acres and 5 kilometres of section from the Cambrian to the Upper Cretaceous. It remains relatively unexplored with only a few recent shale-targeted wells but Houston-based independent Apache Corp. calls the Lower Besa River black shale “the best unconventional gas reservoir evaluated in North America with excellent vertical and lateral reservoir continuity.”

<http://www.ogj.com/articles/print/vol-110/issue-8b/regular-features/journally-speaking/liard-and-the-besa-river.html>

http://geoconvention.org/archives/2013abstracts/263_GC2013_Liard_Basin_Hydrocarbon_Project.pdf






From Apache presentation Jun 2012.

http://www.google.com/url?sa=t&rct=j&q=&esrc=s&source=web&cd=6&cad=rja&uact=8&ved=OCEwQFjAF&url=http%3A%2F%2Ffiles.shareholder.com%2Fdownloads%2FAPA%2F2148221537x0x577564%2Fd3ace688-47ba-48e4-8179-83b15adb6881%2FApache_Investor-Day_20120614.pdf&ei=NJg4U53sA-66yAGXsoDACQ&usq=AFQjCNHNYyC2VdJ9Etmrv3Uxkf8KzrfBRw&bvm=bv.63808443,d.aWc

LIARD BASIN

BEST UNCONVENTIONAL GAS RESERVOIR IN NORTH AMERICA



Reservoir	Units	Liard	NE-PA Marcellus	Haynesville
Depth	(ft)	9500 - 15000	7000 - 11000	10000 - 13000
Thickness	(ft)	400 - 1000	150 - 400	100 - 300
Porosity	(%)	3 - 8	6 - 12	4 - 7
Water Saturation	(%)	15 - 20	15 - 45	20 - 40
OGIP / Sec	(BCF)	170 - 500	30 - 200	50 - 100
Thermal Maturity	(VRo)	>1.5	>1.6	>1.7
Pressure	(Psi/ft)	0.85 - 0.92	0.5 - .65	~0.85
GOR		Dry Gas	Dry Gas	Dry Gas
Quartz+Carb	(Vol %)	>90	65 - 90	60 - 70
TOC	(Wt. %)	3 - 6	2 - 10	2 - 4

- Lower Besa River First Black Shale
- Best gas-shale reservoir evaluated in North America
- Excellent vertical and lateral reservoir continuity

Gas Filled Porosity

84

Apache

In 2012, Apache, with 430,000 acres, reported that one of their wells (Apache HZ Patry d-34-K/94-O-5) recorded a 30 day initial production rate of 21.3 MMCF/D on a six-stage fracturing operation (3.6 MMCF/D per hydraulic fracture). The well was drilled in 2010 to a vertical depth of 3843 m with a horizontal leg of 885 m and has an estimated ultimate recovery (EUR) of 17.9 BCF. It is considered to be one of the best shale gas resource tests in any of North America's unconventional reservoirs (Apache Canada Ltd., 2012).

Apache is targeting the Upper Devonian Lower Besa River Black Shale and estimates that its Liard Basin lands carry a net gas-in-place of 201 TCF, which could yield net sales gas of 48 TCF. The shale is 400-1,000 ft. thick lying at depths of 9,500-15,000 ft. Porosity range is 3-8% and water saturation

is 15-20%. Total organic carbon values are 3-6 wt. %. Apache showed a development model that would involve recovery of 54 TCF of raw gas using 731 well locations on 61 pads with two drilling rigs per pad

The company's vertical C-86-F well went to 15,000 ft. and had a 30-day initial potential of 9.8 MMCFD, and the vertical D-28-B well went to 13,200 ft. and flowed 4.6 MMCFD. The two vertical wells had only a single frac apiece. Net pay thickness is 1,024 ft. at C-86-F and 708 ft. at D-28-B. In its development model, Apache envisions drilling horizontal wells with 7,050-8,040-ft laterals with 18 fracs per lateral. The company estimates 400 ft. spacing between fracs and 600 m between wells. Drilling time is 110-120 days/well. The company plans to drill tenure wells in this year's second half followed by more concept wells in 2013.

Paramount and Nexen are actively drilling in this basin. Nexen have 128,000 acres of highly prospective shale gas lands in the Laird basin, with between 5 and 23 TCF of unrisks prospective resource. Paramount evaluation, after a few wells, suggest that the Laird Basin holds an original gas-in-place of 170-500 BCF per section with an expected recovery of 20%. Transeuro Energy are proceeding to develop the pre-existing Beaver River gas field. They are continuing to develop this field with the hopes that the surrounding shales are feeding these reservoirs. Currently they are producing 1.1MMCF/D down from previous production. Future plans include drilling 6 more wells to target 14 horizons.

The Cordova Embayment area, an area of 936,000 acres where most blocks of land were purchased in 2007, is now being drilled. B.C. has an experimental scheme ownership where operations are kept confidential for three years of which Nexen, Penn West and Canadian Natural Resources Ltd. have participated. To date, Sept. 2014, 22 wells are producing at a combined average rate of 42 MMCF/D from the Devonian Sequences in the Muskwa, Otter Park and Evie. Nexen has drilled two vertical and three horizontals and Penn West has drilled 28 wells so far. Penn West just announced an \$850 million Joint Venture with Mitsubishi to help develop their property in this area.

Recently, EnCana entered into an agreement with Enbridge Inc. for the sale of its majority stake at the Cabin Gas Plant in Horn River Basin. Phase 1 of the development will have 400 MMCFD of natural gas processing capacity. This phase is to be deferred. Phase 2 will add an additional 400 MMCFD of capacity but this has been deferred as well.

Spectra Energy Corp. transportation system stretches from Fort Nelson, in northeast British Columbia and Gordondale at the British Columbia/Alberta border, to the southern-most point at the British Columbia/U.S. border at Huntington/Sumas. They have about 2,800 kilometres (1,700 miles) of natural gas transmission pipeline which can transport 2.9 BCFD. TransCanada Corp. has filed an application for an Alberta pipeline extension subject to regulatory approvals, the approximate \$310 million project is expected to be operational early in second quarter 2012 with commitments for contracted gas rising to approximately 540 MMCFD by 2014.

Triassic Doig and Montney Fort St. John/Dawson Creek Area

The Montney is a liquids-rich tight gas/shale gas play, now producing at more than 1.7 BCFD as of March 2013. This Montney Play Trend, of 6.6 million acres, is now one of the most active natural gas plays in North America. The primary zones are the Upper Middle and Lower Montney as well as the Doig and Doig Phosphate. The major facies include fine-grained shoreface, shelf siltstone to shale, fine-grained sandstone turbidites, and organic rich phosphatic shale. This play varies from the traditional distal shale facies along the Alberta/British Columbia border to a tight calcareous siltstone and sandstone in Central Alberta. The current trend for companies is to explore up dip towards the "oil window" in search of liquids-rich gas. The main Montney players in order of rig utilization are Shell Canada Ltd, Encana Corp, Progress Energy Ltd Talisman Energy Ltd, Tourmaline Oil Corp, Murphy Oil Co. Canadian Natural Resources Ltd., ARC Resources Ltd as well as, at least, another 23 operators. This report will just cover the most active players.

Shell Canada Limited keeps expanding their program in the Sunset Prairie-Groundbirch area where they have only tapped into 5% of their resource estimate of 8 TCF for the area. Shell's Groundbirch venture currently includes five natural gas processing plants, over 250 wells and 900+ kilometres of pipeline which are producing over 190 million standard cubic feet of raw gas per day as of mid-2012. The heart of this tight gas formation lies in a wide layer of siltstone, sandstone and shale some

8,200 to 9,800 feet below ground, and the producing zone is approximately 500 feet thick Groundbirch is still being explored, so the current drilling program includes a mix of single and multiple well pads. Eventually, most of the wells will be drilled on pads containing up to 26 wells, with two such pads for every three square miles of land.


Encana is one of the biggest players with 482 rig releases since 2005. They drilled 90 wells in 2009 with 8 to 10 wells per section, 62 wells in 2010, 43 in 2011 and 41 wells in 2012. The horizontal section are up to 2400m long with up to 17 fracs per well with some recent IP at 10 MMCFD. They believe they have an estimated 70 TCF of gas in place in their trend. Their Montney, Cutbank Ridge area was producing at the end of 2011 at 428 MMCFD and 1.1 MB of liquids/D and in 2012 it was 433 MMCFD and 1.5 MB of liquids/D with their current forecast for 2014 at 600 MMCFD. They have advanced their resource hub design to a new level with 8-12 wells per hub, 100-200 completions per hub, up to 17 stages per well, laterals of 650-100 ft., horizontals of 6500-10,000 ft. and completions every 450 ft. They have announced one well with a 8,935 ft lateral, 12 frac and an IP of 19 MMCF/D. Their completion costs have been reduced by approximately 60 % in the last 5 years. They have recently announced 40 % sale of some of their acreage in the area to Mitsubishi Corporation

Murphy Oil Corporation, in their Tupper Creek Area, has now reached a production level of over 197 MMCFD. They have almost 144,000 net acres in the Montney Trend and drilled 60 wells last year. Their Tupper West gas plant has the capacity of 180 MMCFD with the current production of 150 MMCFD from 59 wells. Recently, because of price, they have curtailed production and reduced spending


ARC Resources Ltd. has now increased their daily production to 235 MMCFD and 1,800 barrels per day of liquids. They have stated that they could sustain rates of up to 800 MMCFD and 17,000 BPD of liquids for a period of 10 years based on their resource portfolio. The first two of three 60 MMCFD gas plants are on stream at full capacity. Some of their wells are producing 30 to 200 barrels per/MMCF. Another recent well of theirs is producing 4.7 MMCFD from a 100 metre section in the Upper Montney. The total BC Montney 2012 Q4 production was 235 MMCF/D and 2600 BOPD.

This play keeps expanding both aerially and stratigraphically as operators are searching for the more liquids-rich sections. See the map below. Two other operators are partnering up with other international players where Progress Energy Resources Corp. created 50/50 partnership with the Malaysian PETRONAS and Talisman Energy Inc. partnered up with South Africa's Sasol Ltd. Other companies have reported liquid yields per MMCF of 20 BBL (Terra Energy Inc.), 30 BBL (Canadian Spirit Resources Inc.), 35 to 50 BBL (Tourmaline Oil Corp.), and 60 to 85 BBL Crew Energy Inc.) A very extreme gas rate of 24.5 MMCFD was announced by Painted Pony Petroleum Ltd.

The graph below shows the well production in the Montney from the Adams, 2013 report.




- Large proportion of the Montney play has economically benefitted by the presence of liquids rich gas.
- Focused development of the Montney wet gas trend began in 2009/2010 as natural gas commodity prices were falling.
- The current rate of development is not only an indication of the more favourable reservoir characteristics (*porosity, organic carbon content, pressures*), but also a reflection of the higher natural gas liquid (C2–C4) and condensate (C5–C12) concentrations of the formation.
- Producers continue to push the limits of the northeastern, liquids-rich portion of the fairway.



Zones of dry gas, wet gas, wet gas+oil, and oil within the Montney Formation (derived from sales gas data). Source: Geoscience Reports 2013, BC Ministry of Natural Gas Development

The graph below shows the gas deliverability 2004 to 2015. Note the increasing Montney contribution. <http://www.neb-one.gc.ca/clf-nsi/rnrgynfmtn/nrgyrprt/ntrlgs/ntrlgsdlvrblty20132015/ntrlgsdlvrblty20132015ppndc-eng.pdf>

Outlook for Total Canadian Gas Deliverability - Mid-Range Price Case



The following table is from Adams, 2013.

Parameter	Shale Gas Play					
	Horn River Basin	Montney (B.C. only)	Barnett	Marcellus	Haynesville	Fayetteville
Basin Area (km ²)	11 500	1 600 to 10 000	1 900	95 000	9 000	9 000
Depth (m)	1 800 to 3 000	1 000 to 3 500	2 000 to 2 600	2 500 to 3 000	3 000	350 to 2 300
Thickness (m)	50 to 350	50 to > 300	15 to 182	12 to 275	75	16 to 180
Porosity (%)	2 to 8	1 to 6	4 to 5	10	8 to 9	2 to 8
Total Organic Content (%)	1 to 8	1 to 7	4.5	3 to 12	0.5 to 4.0	4.0 to 9.8
Reservoir hydrocarbons	dry gas	wet gas, dry gas	wet gas, dry gas	wet gas, dry gas	dry gas	dry gas
Natural Fracturing	Yes	Yes	Yes	Yes	Yes	Yes
Pressure regime	Overpressured	Overpressured	Overpressured	Normal to overpressured	Overpressured	Normally pressured
Proximity to major consuming markets	Distant	Distant	Close	Very close	Close	Close
GIP (billion m ³)	12 629 (10 466 to 14 894)	2 270 to 19 800	9 263	42 492	2 0311	1 473
GIP (Tcf)	448 (372 to 529)	80 to 700	327	1 500	717	52
Marketable (billion m ³)	2 198 (1 715 to 2 714)	Uncertain	1 246	7 422	7 110	1 178
Marketable (Tcf)	78 (61 to 96)	Uncertain	44	262	251	41.6
State of development	very early	early	medium	early	medium	medium
Notes:	hybrid shale/tight-gas					

Source: U.S. data from U.S. Department of Energy *Modern Shale Gas Development in the United States: A Primer*

Lower Cretaceous – Gething and Buckingham N.E. British Columbia

Shale gas activity directed towards Cretaceous horizons is being assessed in several areas of the Fort St. John and Northern Foothills regions. The Blair Creek and Farrell Creek areas in the Northern Foothills region have seen a steady increase in the sale of petroleum and natural gas rights over the last four years. Lower Cretaceous sequences are the exploration focus in the Beg/Jedney areas and further south in the Blair Creek and Farrell Creek areas. Each of these areas has unique characteristics in terms of its shale gas potential. Companies currently operating in these areas are evaluating fracture stimulation programs and continue to optimize completion methods that could potentially increase well productivity. The Buckingham Formation is about 1000m thick in some places. Painted Pony Petroleum has 82,465 net acres of Buckingham potential with recompletion and testing of 3 wells and 2 more wells drilled. No production numbers announced yet as they experiment with drilling and completion techniques. They have announced that 2 existing wells will be fracked in 2013. Canadian Spirit is another player in the area, mostly with experimental schemes, on the Gething. No production volumes reported yet. Unconventional Gas Resources is experimenting with the Buckingham shale. The Asian gas market is being targeted by 11 joint venture export groups with the building of LNG terminals in Kitimat, Prince Rupert and Grassy Point BC, 643 kilometers north of Vancouver. These projects are summarized below:

Canadian LNG export projects in development are: as of Nov 2013:

Kitimat LNG (Chevron, Apache), 1.4 BCF/D, Permits received; awaiting investment decision, **BC LNG Export Co-operative**, 0.125 BCF/D, Permits received, **LNG Canada** (Shell, KOGAS, Mitsubishi, PetroChina), 2.0 – 3.2 BCF/D, Feasibility stage; applied for some permits, **Pacific Northwest LNG** (Progress/Petronas, Japex), 2.0 BCF/D (Merger approval granted), Completed feasibility, progressing to pre-FEED, **Nexen/Inpex**, Conducting feasibility, **Prince Rupert LNG** (BG Group), 3.0 BCF/D, Advancing feasibility, applying for permits, **AltaGas/Idemitsu Kosan**, 0.27 BCF/D, Conducting feasibility, **ExxonMobil/Imperial Oil (WCC LNG Ltd)**, 4.0 BCF/D, Applied for export license, **Woodfibre LNG**, 0.3 BCF/D, Applied for export license. Expressions of interest to proceed with a project have also been made by; **Woodside Petroleum & South Korea E&S**.

Canada's Minister of Natural Resources, on March 27, 2014, announced the Government of Canada's approval of four long-term liquefied natural gas (LNG) export licences for Pacific North West LNG, Prince Rupert LNG, WCC LNG and Woodfibre LNG.


<http://bit.ly/1pyT8DD>

<http://www.capp.ca/getdoc.aspx?DocId=233813&DT=PDF>

http://www.csur.com/misc/Oilweek_Top_%20100_%20Breakfast_%20June%2012.pdf

<http://engage.gov.bc.ca/Inginbc/>

LNG Exports and Pipeline Proposals



<http://www.theglobeandmail.com/report-on-business/industry-news/energy-and-resources/british-columbias-potential-lng-terminals/article8956483/>

B.C Shale information link: There is a wealth of data on this website.

<http://www.empr.gov.bc.ca/OG/OILANDGAS/PETROLEUMGEOLOGY/SHALEGAS/Pages/default.aspx>

<http://www.offshore-oil-and-gas.gov.bc.ca/OG/oilandgas/petroleumgeology/UnconventionalGas/Documents/C%20Adams.pdf>

<http://www.bcogc.ca/publications/reports>

Adams, C. (2012): Summary of shale gas activity in northeast British Columbia 2011, BC Ministry of Energy and Mines, pages 1-19.

<http://www.empr.gov.bc.ca/Mining/Geoscience/PublicationsCatalogue/OilGas/OGReports/Documents/2012/Summary%20of%20Shale%20Gas%20Activity%20in%20NEBC%202011%20Version%20HQ.pdf>

Adams, C., 2013, Summary of shale gas activity in Northeast British Columbia 2012; in Oil and Gas Reports 2013, British

Columbia Ministry of Natural Gas Development, pages 1–27.

<http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/statsactivity/Pages/default.aspx>

BC MEM/NEB Report, May 2011: Ultimate Potential for Unconventional Natural Gas in Northeastern British Columbia's Horn River Basin

http://www.em.gov.bc.ca/OG/Documents/HornRiverEMA_2.pdf

<http://www.aapg.org/explorer/2010/10oct/regsec1010.cfm>

Geoscience BC is an industry-led, industry-focused, applied geoscience organization.

Their mandate is to encourage mineral and oil & gas exploration investment in British Columbia through the collection, interpretation and marketing of publically available.

Some of their major projects have been aquifer studies.

<http://www.geosciencebc.com/s/AboutUs.asp>


This link below summarizes news items concerning the Horn River area.

<http://hornrivernews.com/>

ALBERTA

The shales and tight rocks of the Western Canada Sedimentary Basin have been under investigation for the last number of years. The Alberta portion of this basin, Alberta Basin, has been studied thoroughly by Alberta Energy Resources Conservation Board (ERCB), Alberta Geological Survey (AGS), Geological Survey of Canada (GSC) and National Energy Board (NEB).

Alberta has extensive experience in the development of energy resources and has a strong regulatory framework already in place. Shale gas and liquids is regulated under the same legislation, rules and policies required for conventional natural gas. The Energy Resources Conservation Board (ERCB) regulates exploration, production, processing, transmission and distribution of natural gas within the province. Estimates of shale resources within the Western Canada Sedimentary Basin (see map below) vary from 86 to 1000 TCF. This early estimate did not include liquid phase. While there is a huge potential in Alberta, commercial shale production is at early stages but additional new plays have suddenly begun to emerge.



In Oct 2011 the NEB published the “Tight Oil Developments in the Western Canada Sedimentary Basin” which included Plays highlighted are the Bakken/Exshaw Formation (Manitoba, Saskatchewan, Alberta, and British Columbia), Cardium Formation (Alberta), Viking Formation (Alberta and Saskatchewan), Lower Shaunavon Formation (Saskatchewan), Montney/Doig Formation (Alberta), Duvernay/Muskwa Formation (Alberta), Beaverhill Lake Group (Alberta) and Lower Amaranth Formation (Manitoba). The list did not include potential formations, such as the Second White Specks, Nordegg, and Pekisko and others, largely because these new developments are at very early stages. The NEB estimated that Canadian tight oil production, at March, 2011, to be over 160,000 BBL/D. It is too early to estimate with any degree of confidence what the ultimate impact of exploiting tight oil plays in western Canada might be; however, there are some indications. The Alberta Energy Resources Conservation Board’s latest Supply and Demand report estimates that Alberta’s tight oil plays will add an additional 170,000 BBL/D to conventional light oil production by 2014. In Saskatchewan, tight oil production in the first quarter of 2011 was 90,000 BBL/D, while Manitoba, reached 25,000 BBL/D. Companies have so far identified just over 500 million barrels of proved and probable reserves in their plays of interest and not all companies active in those plays have issued formation-specific reserves. This is enough oil to provide production of about 134,000 BBL/D over a period of 10 years. As well, the technologies used to develop tight oil will continue to evolve, likely increasing the amount of recoverable oil from these plays. Since 2007, the various governments have been collecting and still in the progress of collections data on the following formations: Colorado Group-First White Speckled Shale, Puskwaskau, Wapiabi, Colorado Shale, Muskiki, Second White Speckled Shale, Blackstone, Kaskapau, Fish Scales, Shaftesbury, Joli Fou, Wilrich Formation, Bantry Shale member, Fernie Formation, Fernie Shale, Pokerchip Shale, Nordegg, Rierdon, Montney, Lower Banff, Exshaw, Duvernay and Muskwa.

In October 2012 a very comprehensive study was published by Rokosh et al.: “Summary of Alberta's Shale- and Siltstone-Hosted Hydrocarbons”. This study concluded that the shale gas resources (hydrocarbon endowment) in Alberta alone are estimated to be 3,424 TCF of natural gas, 58.6 Billion Barrels of NGL’s, and 423.6 Billion Barrels of oil. They evaluated the geology, distribution,

characteristics, and hydrocarbon potential of key shale and/or siltstone formations (units) in Alberta. Five units show immediate potential: the Duvernay Formation, the Muskwa Formation, the Montney Formation, the Nordegg Member, and the basal Banff and Exshaw formations (sometimes referred to as the Alberta Bakken by industry). The study also includes a preliminary assessment of the Colorado, Wilrich, Rierdon, and Bantry Shale units. These units were systematically mapped, sampled, and evaluated for their hydrocarbon potential. In total, 3385 samples were collected and evaluated for this summary report. The following table and 4 maps are from this report.

Table 1. Summary of estimates of Alberta shale- and siltstone-hosted hydrocarbon resource endowment.

Unit	Adsorbed Gas Content %*	Natural Gas (Tcf)	Natural-Gas Liquids (billion bbl)	Oil (billion bbl)
Duvernay P50	6.8	443	11.3	61.7
Duvernay P90–P10	5.6–8.5	353–540	7.5–16.3	44.1–82.9
Muskwa P50	6.9	419	14.8	115.1
Muskwa P90–P10	4.1–10.5	289–527	6.0–26.3	74.8–159.9
Montney P50	17.7	2133	28.9	136.3
Montney P90–P10	10.8–26.0	1630–2828	11.7–54.4	78.6–220.5
Basal Banff/Exshaw P50 (preliminary data; see Section 5.1)	5.7	35	0.092	24.8
Basal Banff/Exshaw P90–P10	3.2–10.0	16–70	0.034–0.217	9.0–44.9
North Nordegg P50 (preliminary data; see Section 5.1)	18.2	148	1.4	37.8
North Nordegg P90–P10	4.6–34.8	70–281	0.487–3.5	19.9–66.4
Wilrich P50 (preliminary data; see Section 5.1)	33.7	246	2.1	47.9
Wilrich P90–P10	6.2–59.2	115–568	0.689–4.449	20.2–172.3
Total P50 (medium estimate) resource endowment	n/a	3424	58.6	423.6

* The percentage of adsorbed gas represents the portion of natural gas that is stored as adsorbed gas.

The resource estimates listed above provide an estimate of total hydrocarbons-in-place. Geological and reservoir engineering constraints, recovery factors, and additional economic factors, as well as social and environmental considerations, will ultimately determine the potential recovery of this large resource.

In November the National Energy Board (NEB) in conjunction with their provincial agencies, an ultimate potential of the Montney was released (see below): “The Ultimate Potential for Unconventional Petroleum from the Montney Formation of British Columbia and Alberta”

<http://www.neb-one.gc.ca/clf-nsi/nrgynfmrtn/nrgyrprt/ntrlgs/ltmtpntnlmntnyfrmtn2013/ltmtpntnlmntnyfrmtn2013-eng.html>




Figure 2.3.7. Thermal maturity map of the Montney Formation.




Figure 2.2.6. Thermal maturity map of the Muskwa Formation.




Figure 2.1.7. Thermal maturity map of the Duvernay Formation.




Figure 2.5.7. Thermal maturity map of the north Nordegg.

Thermal Maturity Maps of the Montney, Muskwa, Duvernay and Nordegg from Rokosh et al 2012.

Table 1. Ultimate potential for Montney unconventional petroleum in British Columbia and Alberta.

Hydrocarbon Type	In-Place			Marketable		
	Low	Expected	High	Low	Expected	High
Natural Gas – billion m ³ (trillion cubic feet)	90,559 (3,197)	121,080 (4,274)	153,103 (5,405)	8,952 (316)	12,719 (449)	18,257 (645)
NGLs – million m ³ (million barrels)	13,884 (87,360)	20,173 (126,931)	28,096 (176,783)	1,540 (9,689)	2,308 (14,521)	3,344 (21,040)
Oil – million m ³ (million barrels)	12,865 (80,949)	22,484 (141,469)	36,113 (227,221)	72 (452)	179 (1,125)	386 (2,430)

¹⁹ NEB. *Canada Energy Overview 2012, 2013*. Available at: www.neb-one.gc.ca.

²⁰ NEB. *Natural Gas Supply Costs in Western Canada in 2009, 2010*. Available at: www.neb-one.gc.ca.

²¹ NEB. *Short-term Canadian Natural Gas Deliverability 2013-2015, 2013*. Available at: www.neb-one.gc.ca.

²² NEB. *Canada's Energy Future: Energy Supply and Demand Projections to 2035, 2011*. Available at: www.neb-one.gc.ca.

Cretaceous Colorado Group Eastern Alberta

This play is potentially widespread but there has been limited shale gas activity and production within this interval mostly as a result of the gas price. The shale gas intervals are normally co-mingled so numbers are difficult to grasp for the shales. There have been small companies producing gas from this zone but they are limited and some are selling their interests. Some companies are now focusing on the liquids potential of the Second White Specs.

Lower Jurassic Nordegg (Gordondale) West Central Alberta

Anglo Canadian Oil Corp. now Tallgrass Energy Corp. has been playing the potential of the Nordegg Member which is a source rock composed of basinal shales, silts and carbonates. They feel that the Nordegg Member contains a huge amount of oil. They are drilled a horizontal well to test this play producing limited liquids. Athabasca Oil Sands second Kaybob Nordegg horizontal well, at 04-11-63-20w5, offsetting its first Nordegg horizontal well. After a 16-stage slickwater frac and 4 days of clean-up, the 04-11 well made 335 b/d of 41° gravity oil and 500 MCFD of gas at 910 psig flowing pressure. There are others in this play but information is tight: Penn West, EOG, Apache, Surge, Nordegg, Petro-Bakken, Altima, Long Run and others. See Meloche in references.

Triassic Montney Shale Western Alberta

The Montney fairway extends in Alberta where this play is being picked up for both gas and liquids rich gas. Some of this Montney is classified as conventional because of facies change. Companies actively testing oil-prone Montney exploration acreage include ARC Resources Ltd. at Ante Creek and Tower, Athabasca Oil Sands at Kaybob, Celtic Exploration at Karr, CIOC at Karr and Simonette, Canadian Natural Resources Ltd. at Tower, Crew Energy Inc. at Tower, Harvest at Ante Creek, Imperial Oil at Berland, Long Run at Girouxville, RMP Energy Inc. at Grizzly and North Waskahigan, Seven Generations at Karr, and Triology Energy Corp. at Kaybob West.

<http://www.ogj.com/articles/print/volume-111/issue-4/general-interest/montney-duvernay-will-be-key-to-canada.html>

Devonian Duvernay/ Muskwa Shales Western Alberta

The exciting new liquids play, Duvernay Shale is the stratigraphic equivalent to the Muskwa in N.E. B.C. The Duvernay has been credited as the source rock for most of the gigantic Devonian oil and gas pools of Alberta. This zone compares favorably to other North American shale plays with its position in the liquids window, organic content, porosity, thickness and over pressuring. The Duvernay is often compared to the prolific Eagle Ford of Texas because they are both shale plays that offer a full spectrum, from dry gas through liquids-rich gas to oil. According to the Energy Resources Conservation Board, the Duvernay holds an estimated 443 trillion cubic feet of gas, 11.3 billion barrels of natural gas liquids and 61.7 billion barrels of oil. It is estimated that \$4.2 has been spent on this play as of Jun 2012. This BMO Capital markets research report, June 2012, has a wealth of data on this play. Encana believes that this play is 2 times the size of the Eagle Ford Play.

<https://bmo.can.idrsite.com/Login%20Page%20Document%20Library/ADLibrary/Presentations/BMO%20Duvernay%20DUG%20June%202012.pdf>

<http://www.junewarren-nickles.com/alberta-oil-and-gas-update/>

The Duvernay play is divided into the Western and Eastern Shale Basin with the West divided into three drilling districts, Kaybob, Edson and Pembina. The companies involved in this deep and expensive play of 3100 to 3700 m are numerous, some of which are: Celtic now Exxon (paid C\$2.6 billion), Encana, ConocoPhillips, Husky, Athabasca, Chevron, Trilogy, Shell, Talisman, Yoho, Taqa North amongst others.

Encana has accumulated a 253,000 acre position in this play. Initially they announced that their first two wells produced 2 to 5 MMCFD and 158 to 390 bbl. per day respectively. Their well costs are \$12 million with a EUR per well at 3 – 6 BCF and 350 – 600 MBBL over a lateral length: 3,500 – 6,500 feet and at a TVD of 8,300 – 13,000 feet. Their yield is 159 to 320 bbl. (50 to 60 ° API) per MMCF. Just recently they announced that one well had an initial production rate of 1400 B/D of condensate and 4 MMCF/D of gas over its first 30 days of production and continues, after 160 days, at 350 B/D of condensate and 2 MCF/D of gas. They planned 20 wells in 2013 with an exit rate of 1,500 BD of liquids. They recently announced a joint working interest with PetroChina. Encana’s Duvernay comparison is shown below.

Duvernay – World Class Reservoir

Encana controls one third of the top tier land in the condensate window*

Reservoir Attribute	Duvernay	Marcellus	Eagle Ford
TVD Depth (ft)	8,200 – 13,100	400 – 8,400	8,800 – 13,800
Gross Thickness (ft)	65 – 230	50 – 200	50 – 280
Porosity (%) / Permeability (nD)	3 – 8 / 10 – 400	10 / 20 – 55	10 – 11 / 50 – 1200
Reservoir Temperature (°F)	220 – 250	130 – 170	220 – 280
Gas Composition	Wet / Dry	Wet / Dry	Wet / Dry
Total Organic content (TOC %)	1 – 20	3.0 – 12.0	4.5
Maturation (Ro %)	0.6 – 2.9	1.4 – 3.0	0.6 – 2.2
Pressure Gradient (PSI/ft)	0.72 – 0.96	0.45 – 0.60	0.60 – 0.80
EUR (MMboe / well) (6:1)	0.7 – 1.6	0.3 – 1.0	0.5 – 1.3


*Encana estimate

Source: RBC Richardson Barr / RBC Rundle estimates, industry estimates, DOE April 2009 publication “Modern Shale Gas: A Primer”

Talisman has drilled and released information on four wells into this play and has reported condensate rates of 120 to 733 B/D of 50 to 57⁰ API. They report that their liquids yield is 200 to 1,000 BBL per MMCF. They spent \$510 million in June increasing their footprint to 352,000 acres.

Late Devonian and Early Mississippian Alberta Bakken – Exshaw Southern Alberta

The Alberta Bakken (Exshaw) is another emerging tight oil resource play in SW Alberta to NW Montana consisting of three zones, Big Valley / Stettler Carbonates, Bakken/Exshaw dolomitic siltstones and Banff carbonates. This play gained momentum south of the border in Montana and has recently emerged into Alberta and there is rush to get a position. In a report late last year, research firm Wood Mackenzie said the tight oil play that straddles the Alberta-Montana border could contain a recoverable 2.6 billion barrels of oil. Production of about 300 to 350 BOPD has been published. There are a number of companies in this play. Over 30 horizontal wells have been drilled so far but with little publication of results. Crescent Point, Shell, Murphy, Torc, Argosy, Primary Nexen, Bowood/Legacy, Rosetta and Newfield are some of the companies involved. Crescent Point Energy has 1,000,000 acres, drilled eight wells in the 4th quarter of 2012. Murphy is drilling 6 to 9 wells with 5 drilled to date: 3 producers, one being evaluated and one awaiting completion. They have announced tests of 415 to 800 BOPD. Deethree Exploration said it has two drilling rigs operating on the lands of 200,000 acres, where they have tested 600 to 950 BBL/D of 30 °API oil. They have drilled 17 horizontal wells into this zone. Torc has reported that two of their wells have yielded IP rates of 510 and 514 BOPD. See Zaitlin 2011 and 2012.



The Alberta Energy Resources Conservation Board (ERCB) just recently published a document to clarify the definition of shale for shale gas development and to identify the geological strata from which any gas production will be considered to be shale gas.

<http://www.ercb.ca/docs/documents/bulletins/Bulletin-2009-23.pdf>

Alberta Energy Shale Gas <http://www.energy.alberta.ca/NaturalGas/944.asp>

The Alberta Geological Survey (AGS) is active in publishing geological studies including a number of studies on shales.

AGS Shale Gas Section

<http://www.ags.gov.ab.ca/energy/shale-gas/shale-gas.html>

AGS Reports <http://www.ags.gov.ab.ca/publications/pubs.aspx?tkey=shale%20gas>

AGS Conference Papers and posters

<http://www.ags.gov.ab.ca/conferences/geology-poster-ppt.html>

Alberta Duvernay/Muskwa and Montney Formations Shale Analysis poster by the ERCB and Alberta Geological Survey.

http://www.ags.gov.ab.ca/conferences/shale_gas_cspg_2009_poster.pdf

The Alberta Geological Survey has this link with documents on the Colorado Play.

<http://www.ags.gov.ab.ca/publications/pubs.aspx?tkey=colorado%20group>

In 2012 the Alberta Geological Survey just published a new document. Rokosh et al, Summary of Alberta's Shale- and Siltstone-Hosted Hydrocarbon Resource Potential. See the references

The ERCB is the regulator for Alberta. <http://www.ercb.ca/portal/server.pt>

SASKATCHEWAN

Upper Cretaceous Colorado Group – biogenic gas Central Saskatchewan

As in Alberta the Colorado Group shales have been produced in Saskatchewan at low volumes for a 100 years but the recent gas price decline has kept this play minimized. In this province, the past exploration focus has been primarily on two types of biogenic shale gas potential within the Upper Cretaceous. The first type is a hybrid shale gas play along the Saskatchewan–Alberta border, where thin laminae of sand and silt lie within the shales of the Upper Colorado Group. Other intervals within the Colorado Group that were once lumped and dismissed as ‘non-productive shale’ are also now being re-evaluated. The second type of play currently being evaluated is the Colorado shale gas play in the eastern half of the province. These highly organic shales have been the focus of exploration in the past, prior to World War II, when gas seeps were reported near the towns of Kamsack and Hudson Bay. Several wells near Kamsack produced from the early 1930s to late 1940s with total gas production of 168 MMCF. From 2001 to September 2008, 59 new wells, licensed for gas, were drilled in the Hudson Bay and Kamsack areas. There are still no major commercial discoveries and not much news out of Saskatchewan this year as a result of the lower gas price and the economy. There are however around 13 wells in SW Saskatchewan that under production from the Colorado shales.

Between 2004 and 2008 more than 50 test wells were drilled for shale gas in all areas in the province, including Watrous, Moose Jaw, Strasbourg, Foam Lake, Smeaton, Shell Lake and Big River but no commercial discoveries have been announced.

http://www2.canada.com/reginaleaderpost/news/business_agriculture/story.html?id=c41a6b5b-b892-40cc-8cb4-902156681111&k=18412


PanTerra Resource Corp. have drilled and cased thirty-six wells within their more than one million acres of land. They feel they have 3 TCF of recoverable gas. They had been coring, logging and fracture stimulating but no rates have been announced to date. Because of the low gas prices they have put this project on hold. There has also been some activity in the Pasquia Hills in central east Saskatchewan. Pasquia Hills has a huge potential for Oil Shale in this area but there have been about 23 wells drilled by various operators with gas shows and some limited gas tests. Nordic announced recently that survey work has now commenced for a five-well drilling program on the Company’s land in Preeceville. Nordic believes that with new drilling technology available, it will be successful in unlocking the enormous reserves of shale and natural gas. After drilling two unsuccessful wells they will be returning in the fall for another well. It is unclear whether this play is unconventional or conventional or both with both gas and oil as their targets. Recently Questerre announced a Pasquia Hills program. They acquired 100% interest in 39,000 acres. Situated in one of Canada’s largest oil shale deposits with plans of a 2012-2013 work program to include core holes and trenching to assess potential. They have partnered up with a USA firm uses the EcoShale In-situ capsule process which is an innovative approach that moves the machines to the rocks instead of moving the rocks to the machines to extract the oil. Drilled 16 wells in 2012 and analysis of core indicates recoveries between 10-20 gallons/ton with select intervals of up to 16-20 gallons/ton within a 20-35 m section. Ten more wells to be drilled beginning fall 2012 and then integrate core data and develop resource estimate by early 2013. Xtra Energy Corp. announced today that it has entered into a Letter of Intent with two corporations which own a 55% working interest in the Pasquia Hills oil shale permit SHP00008.

<http://www.saturnminerals.com/i/pdf/oilshalesaskatchewan.pdf>

Upper Devonian- Lower Mississippian Bakken

Saskatchewan is also reaping the benefits of the boom in horizontal and fracturing techniques drilling, especially in the Bakken. Production has risen from about 1-2,000 BOPD in 2005 to about 65,784 BOPD at the end of 2013 with a cumulative production of 21 MM M3 or 132 MM BBL. The

Bakken production comes from the tight siltstone and sandstone beds with in the shales (Kreis, L.K. and Costa, A. 2005) so it is not really a shale oil play. The Bakken wells tend to highly productive at 200 BOPD producing a light sweet crude oil with 41 °API gravity. There are many players in this zone. One of the two bigger players are Crescent Point with 704,000 net acres, 3,800 drilling locations, 198 wells to be drilled in 2012 and 4.6 Billion BOIP. They plan to drill 163 wells in 2013. Currently they are producing at 42,000 BPD. Their new waterflood has increased recovery factor by 3%. PetroBakken now Lightstream is the other one with 256,200 net acres, 979 producing wells, 700 net drilling locations and about 19,000 BPD.



Saskatchewan Government energy and resources is the regulator.

<http://www.er.gov.sk.ca/Default.aspx?DN=4c585c56-193a-485a-91fd-7c49f0104a60>

MANITOBA

Cretaceous Colorado Group

There is the potential of shale gas in Manitoba, but no activity or production. There have been a number of publications on the shallow shale potential by Nicholas and Bamburak.

http://www.wbpc.ca/assets/File/Presentation/11_Nicolas_Manitoba.pdf and Nicholas 2011

http://www.wbpc.ca/assets/File/2011%20Presentations/Tuesday/Nicolas%20WBPC%202011_Shale%20gas%20to%20Three%20Forks.pdf

Upper Devonian-Lower Mississippian Bakken

The production of oil from the co-mingled Bakken/Torquay, which began in the mid-1980's, continues, with about 640,740 BBL per month or 21,385 BBL/D. Cumulative historical production is 42,364,754 BBL from about 1831 producing wells. The Bakken produces more water than oil so water disposal is a continuing issue. The following graph shows production from the Bakken, Mississippian and Triassic (Lower Amaranth).

The Manitoba oil and gas is the regulatory agency.

<http://www.gov.mb.ca/stem/petroleum/index.html>


Manitoba Mineral Resources

<http://www.manitoba.ca/iem/mrd/index.html>

Manitoba Geological Survey

<http://www.manitoba.ca/iem/mrd/geo/index.html>

Annual Production



ONTARIO

Upper Devonian Kettle Point Shale (Antrim Shale Equivalent)

Middle Devonian Marcellus Shale

Upper Ordovician Blue Mountain and Collingwood Shale (Utica Equivalent)

Exploitation of these shales has been very quiet with only a few operators discussing the evaluation of these shale targets. These shales are mostly considered secondary targets but only one well has been drilled to test these zones to date. The only drilling activity is by the Ontario Geological Survey. They drilled two stratigraphic tests last year to assess the shale gas potential of the Kettle Point Formation. They have just released a request for proposals to drill two more stratigraphic test wells to test the Collingwood-Blue Mountain. No results have been published yet. In the spring of 2010, 2 boreholes were drilled through the Kettle Point Formation. Core samples were collected to evaluate gas concentration and other key parameters. Similar work was performed in 2011 near Mount Forest in the County of Wellington to assess the shale gas potential of the Ordovician shale succession. Furthermore, in the summer of 2012, additional rock samples were collected from previously drilled wells from southern Ontario and were analyzed for mineralogy and Rock-Eval® 6 pyrolysis parameters. These analyses may assist in refining stratigraphic correlations across provincial and international borders. This project is referenced in Béland Otis 2012. A new company was recently formed Ontario Oil and Gas with their total objective to acquire 60,000 acres of shale lands over the next three years. OSO currently controls 2,500 net acres and anticipates growing this quickly over the coming months.

The Ministry of Natural Resources of Ontario is the regulator.

http://www.ogsrlibrary.com/government_ontario_petroleum.html

http://www.ogsrlibrary.com/downloads/Ontario_Shale_Gas_OPI_2009_Nov11.pdf


http://www.wnloilandgas.com/media/uploads/Carter_Presentation.pdf

<http://www.ogsrlibrary.com/>

Ontario Geological Survey

<http://www.mndm.gov.on.ca/en/mines-and-minerals/geoscience/non-renewable-energy>

<http://www.geologyontario.mndmf.gov.on.ca/mndmfiles/pub/data/imaging/OFR5716/OFR5716.pdf>



QUEBEC – ST. LAWRENCE LOWLANDS

Ordovician Lorraine and Utica Shale

The other potential bright light in Canadian shale exploration in 2008 was in Quebec, within a 300 km by 100 km fairway between Montreal and Quebec. The Upper Ordovician Utica and Lorraine shales are the targets. On March 8 2011, the Quebec Provincial Government effectively declared a temporary moratorium on the use of chemical fracturing during shale gas drilling pending stricter a full environment assessment audit. <http://www.bape.gouv.qc.ca/sections/rapports/publications/bape273.pdf> in French only

As well, no new wells will be drilled without local approval. This review conducted by an 11 person committee could take up to 30 months. The government had previously awarded permits for 29 drilling sites where fracking has taken place on 18 locations. A year ago, when Quebec Environment Minister Pierre Arcand announced the \$7-million Strategic Environmental Assessment (SEA) on shale gas, he said it was in part to reassure the public that shale gas development will not go ahead in Quebec unless it is determined to be safe. But a year into that process, opposition remains as fierce as ever. The committee's final report is to be submitted to the government by November 2013. It is now estimated it might be complete in 2014.

<http://www.montrealgazette.com/technology/year+later+opposition+shale+exploration+still+fierce/6327547/story.html#ixzz1qkV4IfFA>

Less than 24 hours after being sworn in, Quebec's new natural resources minister has shut the door nearly definitively on shale gas exploration and commercialization in the province.

<http://business.financialpost.com/2012/09/20/quebec-hints-at-long-term-shale-gas-ban-citing-ecological-risks/>

As of February 2013 Quebec announced a moratorium on shale gas development in the St. Lawrence Valley until after the above review is complete. Talisman has suspended shale gas exploration here.

Industry has drilled or evaluated 23 wells and spent \$200 million. Assuming a green light after the environment review finishes industry is saying that it would take 3 to 4 years before the production stage is reached. CERI published Potential Economic Impacts of Developing Quebec's Shale Gas in March 2013.

http://www.ceri.ca/images/stories/2013-03-08_CERI_Study_132_-_Quebec_Shale.pdf

Both Forest Oil Corporation and their partners and Talisman and their partners have drilled to evaluate both the Lorraine (up to 6,500 feet thick) and the Utica (300 to 1,000 ft. thick). Talisman with their partners and a 771,000 acre land position has drilled six vertical wells with tested rates at from 300 to 900 MCFD. In 2009 and 2010 they drilled or will be drilling five horizontals which were currently being evaluated. Talisman has since suspended its shale gas exploration in Quebec. <http://www.theglobeandmail.com/globe-investor/talisman-suspends-shale-gas-exploration-in-quebec/article4753334/>. Forest, after drilling two vertical wells with production rates up to 1 MMCFD and three horizontals, is waiting for the rock work and the analysis before proceeding further. The horizontals rates range from 100 to 800 MCFD with 4 stage fracs. These are ten year leases. Forest estimated 4.1 TCF resource potential at 20% recovery. These black shales of 1 to 3% TOC are 500 ft. thick within the gas window. Cambrian, Gastem, Junex, Questerre, Molopo, Intragaz, Petrolympic and Altai are among the other interest holders in this play. Questerre Energy Corporation reported on the test results from the St. Edouard No. 1A horizontal well. The horizontal well was successfully completed with 8 stage fracture stimulations. Clean-up and flow back commenced January 29, 2010. During the test, the well flowed natural gas at an average rate of over 6 MMCFD.

http://www.questerre.com/assets/files/PDF/101121_QEC_Presentation-Update.pdf

Upper Ordovician Macasty Shale

In addition, the Upper Ordovician Macasty Shale (Utica Equivalent) drilled by Corridor and Petroliia on Anticosti Island in the Gulf of St. Lawrence has seen some interest, largely as a secondary target, with results from recent coring identifying shale oil potential. Corridor reported the results of an independent resource assessment of the Macasty Shale which resulted in a best estimate of the Total Petroleum Initially-In-Place 33.9 billion barrels of oil equivalent (BBOE) for Corridor's land holdings with the low estimate at 21.4 BBOE and the high estimate at 53.9 BBOE. Corridor and Petroliia have announced a new program where coring, water wells, and data collection are expected to be completed by the end of 2012, with the final analytical results due in 2013. These results were just announced in Jan 2013. Junex has a position in Anticosti Island as well.

<http://www.corridor.ca/investors/documents/March2011TechnicalPresentationonAnticostiIsland.pdf>

http://www.corridor.ca/documents/Martel_Anticosti_NAPE_2012.pdf

<http://www.corridor.ca/media/2011-press-releases/20110713.html>

<http://www.petroliagaz.com/imports/pdf/en/18168.Petroliia.FinalReport.pdf>

Utica Emerges in Quebec Shale Play Extends to Canada by Susan Eaton

<http://www.aapg.org/explorer/2010/01jan/shale0110.cfm>

In a surprise move Quebec announced Feb. 13 2014 that it would move ahead with oil exploration on Anticosti with the province pledging \$115-million to finance drilling for two separate joint ventures. These shales will have to be fracked. Quebec would become an equity partner with five separate firms, controlling 50% of the licences and rights to 60% of any commercial profit. Shale gas plays in the province's St. Lawrence Lowlands enjoy another advantage in being close to the northeast U.S. gas market. The *Association pétrolière et gazière du Québec* (Quebec Oil and Gas Association). APGQ/QOGA membership : Altai Resources Inc., Canadian Forest Oil, Canadian Quantum, Cambrian, Dessau (Associate member), Gastem, Intragaz, Junex, Molopo, Questerre, Roche (Associate member), SNC-Lavalin (Associate member) and Talisman Energy Inc.

Quebec Shale Conference 2013, 2012, 2010 and 2009

<http://www.apgq-qoga.com/en/>

<http://www.apgq-qoga.com/en/2011/07/20/qoga-annual-conference/>


<http://www.apgq-qoga.com/wp-content/uploads/2012/09/Programme-APGQ-2012-HR.pdf>

<http://www.apgq-qoga.com/en/conference-2013-2/>

Ministère des Ressources naturelles et de la Faune de Québec is the regulator.

<http://www.mrnf.gouv.qc.ca/english/energy/oil-gas/oil-gas-potential.jsp>

St. Lawrence Lowlands, Quebec: Shale Gas Area (Séjourné et al




2013)

NEW BRUNSWICK

Lower Mississippian Fredrick Brook Shale Moncton Basin

The Lower Mississippian Fredrick Brook Shale in the Moncton Basin has been the focus of thermogenic gas exploration in this province. The Green Road G-41 well was drilled by Corridor Resources in November, 2009 and tested in two zones in the Fredrick Brook, after fracing with propane. The lower black shale interval of the formation flowed at a rate of 0.43 MMCFD, whereas the upper silty/sandy shale zone of the formation tested at initial peak rates of 11.7 MMCFD with a final rate of 3.0 MMCFD. Corridor also announced the farmout of 116,018 acres this shale-potential land to Apache. Apache drilled their second well into this play and proceeded to run five slickwater stimulations per well with no gas recovery. Apache has left the project. Ten wells have been drilled into this play with seven completed and 6 testing gas. The rates have not been consistent. Another appraisal well has been recently spudded. Their plans are to try to develop this thick play of greater than 500 m vertically. During 2011 Corridor completed the drilling of the vertical Will DeMille O-59 shale gas appraisal well to a total depth of 3188 meters measured depth. Strong gas shows were encountered within Hiram Brook sandstones and the Upper Frederick Brook shale. Based upon initial analysis of well log information, the well intersected at least eight intervals with significantly elevated gas shows that are considered frac candidates. Corridor plans to evaluate these intervals with logs and sidewall cores in order to select the intervals for future fracture stimulation. The Will DeMille O-59 well is located north of Elgin, New Brunswick. The Province of New Brunswick has recently issued recommendations for new proposed environmental requirements which allow for the exploration and development of oil and gas in New Brunswick. Corridor is working with the government and other stakeholders to ensure best practices are followed and oil and gas activities can be completed in a safe and responsible manner. Corridor plans to stimulation in 2014 at their Elgin shale gas project using the new government guidelines. Details of their plays can be found at <http://www.corridor.ca/documents/CorridorOverviewMemorandumUpdateFB.pdf>

Contact Exploration and PetroWorth Resources are also re-evaluating their shale gas potential in the Fredrick Brook. On March 16, 2010, Southwestern Energy Company bid \$47 million for 2.5 million acres in two areas for both conventional and unconventional resources of the Mississippian Horton Group. The company has completed airborne magnetic and gravity acquisition and is in the second phase of surface geochemical sampling and the acquisition phase of approximately 250 miles of 2-D data. Interpretation of the data is underway. \$10.7 million was invested in 2010 with \$14.2 million investment planned for 2011 and then \$14.2 million in 2012 with possible well(s). In consultation with the New Brunswick Department of Natural Resources and other key government officials, SWN Resources Canada will defer their planned 2012 exploration program until 2013 to provide additional time for public engagement and completion of the permitting process. Just recently they have applied to the government for a one year extension on their permits with the plans for a further 130 miles of 2D seismic with the plans of future drilling. They just finished their seismic program in Dec 2013.



“Frederick Brook Shale spurs Canadian exploration,” by Susan Eaton *AAPG Explorer*, August 2010, p.6-10.

<http://www.aapg.org/explorer/2010/08aug/fredrick0810.cfm>

New Brunswick Natural Resources, Minerals and Petroleum is the regulator for this province.

<http://www.gnb.ca/0078/minerals/index-e.aspx>

http://www.gnb.ca/0078/minerals/GSB_Hydrocarbon_Basin_Analysis-e.aspx#Objective

Shale Gas Website http://www2.gnb.ca/content/gnb/en/corporate/promo/natural_gas_from_shale.html

Update on New Brunswick by Steven Hinds

http://www.wnoilandgas.com/media/uploads/Hinds_Nfld2011.pdf

Update on Fracking

Energy and Mines Minister Craig Leonard is promising to review two new reports on the shale gas industry before the provincial government acts on any of their recommendations.

<http://www2.gnb.ca/content/dam/gnb/Corporate/pdf/ShaleGas/en/ExecSummary.pdf>

In February 2013, New Brunswick released their new rules for industry by pushed ahead with dozens of new regulations governing shale gas exploration.

In bringing forward 97 new rules that will cover the oil and gas industry’s practices, the government said it’s striking a balance between environmental protection and the economic potential that fracking for shale gas represents.

<http://www2.gnb.ca/content/dam/gnb/Corporate/pdf/ShaleGas/en/RulesforIndustry.pdf>

NOVA SCOTIA

Upper Devonian/Lower Mississippian Horton Bluff Kennetcook Basin

The Upper Devonian-Lower Mississippian Horton Bluff Shale in the Kennetcook Basin has been the primary target for thermogenic shale gas exploration in the province by Triangle (Elmworth) Petroleum since May 2007. A 2D and 3D seismic program was initiated and a total of 5 vertical exploration wells have been drilled since May 2007. Various fracture treatments have been performed although none have successfully produced gas so far. On April 16, 2009, Triangle executed a 10-year production lease on its Windsor Block in Nova Scotia which covers 474,625 gross acres (270,000 net acres) with a potential of 20 TCF recoverable. They have agreed to drill at least 7 more wells in this block before 2014. In 2009 they conducted a 30 km 2D seismic program to try to pinpoint areas with structure for future shale targets. Currently there has been no work this year as they are looking for partners. The Government is appointing in the Spring of 2011, an internal committee of officials from the Departments of Energy and Environment to examine the environmental issues associated with hydraulic fracturing in shale gas formations and make recommendations on any additional required regulatory measures was to be finished in early 2012 but now has been extended to 2014 with another independent review pending starting in the fall of 2013.

<http://www.gov.ns.ca/nse/pollutionprevention/docs/Hydraulic.Fracturing.Web.Update-2012.07.pdf>

<http://www.cbc.ca/news/canada/nova-scotia/story/2012/04/17/ns-fracking-decision-delay.html>

<http://novascotia.ca/news/release/?id=20130828001>

There are currently no applications for hydraulic fracturing of shales in Nova Scotia and none are anticipated soon until this review is complete.

<http://www.novascotia.ca/nse/pollutionprevention/consultation.hydraulic.fracturing.as>

This abstract is from “The Horton Bluff Formation Gas Shale Opportunity, Nova Scotia, Canada, Adam MacDonald, 2012 AAPG Search and Discovery

<http://www.searchanddiscovery.com/abstracts/html/2011/annual/abstracts/MacDonald.html?q=%2BtitleSt+rip%3Acanada+%2ByearSort%3A%5B2011+TO+2012%5D>

The Horton Bluff Formation gas shale’s are within the Carboniferous lacustrine Horton Group of the Maritimes Basin. Gas in place (GIP) estimates are 69 TCF and leading indicators of a prospective shale gas play such as TOC at >5.5 % , Maturity (Ro) of 1.6, thickness of >500 meters and estimates of 100 Bcf per section across an area of > 2 million acres, have generated an increased interest in the Horton Bluff Formation within this frontier basin. Comparison of this shale play characteristics to many others (mineralogy, gas filled porosity, pressure gradient, adsorbed gas) across North America ranks the Horton Bluff shale as among some of the most prospective. The Nova Scotia Department of Energy (NSDOE), working closely with industry, has recently undertaken the task of trying to understand the resource potential. GIP or “size of the prize” is determined by the shales’ gas generating potential, the mineralogy which may dictate the fracturing techniques and lead into the engineering solutions that need to be achieved through the drilling and piloting phase to reach commercial producibility.

The energy trader who co-founded Galveston LNG Inc. and later sold the Kitimat LNG scheme to Apache Canada and EOG Resources for roughly \$300 million is back with a new plan to export natural gas from Canada’s east coast. Alfred Sorensen said today that his new company, Pieridae Energy Canada, plans to build an export terminal at Goldboro, Nova Scotia. It is contemplated that the gas source come from the Marcellus, New Brunswick and offshore Nova Scotia.

<http://www.albertaoilmagazine.com/2012/10/pieridae-energy-proposes-east-coast-lng-facility/>

The Goldboro LNG Facility is to include a gas liquefaction plant and facilities for the storage and export of LNG, including a marine jetty for off-loading, and upon completion, is expected to ship approximately five million metric tons of LNG per year and have on-site storage capacity of 420,000 cubic metres of LNG. The Goldboro LNG Facility is to be located adjacent to the Maritimes & Northeast Pipeline, a 1,400-kilometre transmission pipeline system built to transport natural gas between Nova

Scotia, Atlantic Canada and the North eastern United States. Pieridae Energy (Canada) Ltd. (“Pieridae”) is pleased to announce that the Province of Nova Scotia, has issued environmental assessment (EA) approval, with conditions, for company’s proposed Goldboro LNG project in March of 2014.

The Nova Scotia Department of Energy is the regulator for the province.

<http://www.gov.ns.ca/energy/oil-gas/onshore/>

NEWFOUNDLAND

Ordovician Green Point Shale

Western Newfoundland

The Cambro-Ordovician Green Point Formation is the focus of exploration activity for oil bearing shale in the western parts of the province. This Green Point interval has been studied in outcrop by the Geological Survey of Canada and is summarized in Hamblin (2006). Oil seeps have been documented along the entire coastline and some oil production from as early as the 1900’s have been recorded. A well drilled in 2008 from the onshore to the near offshore by Shoal Point Energy and partners encountered about 500 to 1000 m of shale with siltstone stringers with high gas and oil shows throughout the formation but no testing was attempted then. The geochemistry analysis indicates that this zone is in the oil window. Further drilling of the shale oil potential in this formation was undertaken by reentry of the previous well bore, sidetracking and testing. These plans were unsuccessful and discontinued because of severe formation damage. The company has recently locked up contiguous blocks of land of about 720,000 acres to the north stretching more than 160 km. Just recently Black Spruce Exploration made an agreement to drill up to 12 wells in this play over the entire length of this play.

These projects are delayed since the government announced a study of the future of fracking.

<http://www.releases.gov.nl.ca/releases/2013/nr/1104n06.htm>

The Newfoundland Department of Natural Resources is the regulator for the onshore portion of the province. <http://www.nr.gov.nl.ca/mines&en/oil/>

<http://www.nr.gov.nl.ca/nr/energy/petroleum/onshore/onshore.html>

This is the latest publication by the DNR on the Shale Oil Potential of the Anticosti Basin.

<http://www.internationalpavilion.com/NAPE%202012%20Presentations/J%202.48-3.00%20Wednesday%20Newfoundland%20and%20Labrador.pdf>

The Canada-Newfoundland Labrador Offshore Board is the regulator for the offshore portion.

<http://www.cnlopb.nl.ca/>

NORTHWEST TERRITORIES

Devonian Canol Shale

The Northwest Territory Geoscience Office commissioned Dr. Brad Hayes of Petrel Robertson Consulting Ltd. of Calgary to undertake a regional-scale study of the unconventional shale gas and shale oil potential of the southern and central Northwest Territories. His report assembles available outcrop and subsurface data to systematically assess shale gas and oil potential and is available as NWT Open File 2011-08 (See below). The work follows on an earlier unconventional natural gas scoping study for the NWT also authored by Dr. Hayes (NWT Open File 2010-03) (See references below). Canada’s Northern Oil & Gas Directorate held lease sales in 2011 and 2012 where industry has committed \$628 million in work commitments on 13 exploration licenses in the central Mackenzie region. It is speculated the Canol Shale play was the main target. The Canol shale formation could be as big as the prolific Bakken light oil play. Initial estimates peg the Canol play at two to three billion barrels of recoverable crude in a region which has seen drilling activity for almost a century but has yet to reap substantial economic benefit because of its remote and challenging terrain. The plan is for companies such as Imperial Oil, Shell Canada and MGM Energy, ConocoPhillips and Husky Energy to continue activity to prove up the resource and eventually produce crude for southern market.

<http://m.theglobeandmail.com/globe-investor/husky-prepares-an-arctic-expedition/article4179898/?service=mobile>

MGM in partnership with Shell, who farmed in, were the first to announce the results of drilling into this new play. Their vertical well into the Canol shale resulting in the recovery of approximately 140 barrel of fluid consisting of frack fluid, crude oil and natural gas. According to MGM, the Canol/Hare Indian shale is 30-170 metres thick at a depth of 1,000-2,500 metres. In addition, the Bluefish Shale is 15-25 metres thick at a depth of 1,000-2,700 metres. Both are highly brittle, which is a key attribute for successful fracturing. Their independent reserve estimate on four exploration licenses are about 11 Billion Barrels oil in place, mean. Drilling is restricted to the months of January to March. Husky drilled two vertical exploratory wells into the oil mature Devonian- aged Canol and Hare Indian/ Bluefish Shales south of the community of Norman Wells in the Central Mackenzie Valley. They plan to test them this year. They have built an all-weather road into the drill site. Meanwhile, ConocoPhillips drilled two wells on its lone license in the Canol shale this winter and is planning to drill two horizontal wells in the winter of 2013-2014. <http://www.albertaoilmagazine.com/2013/03/mgm-energy-releases-underwhelming-results-for-canol-shale-well/>

The Enbridge Norman Wells to Alberta pipeline runs through the area flowing 40,000 barrels of oil per day. The Norman Wells oil field discovered in the 1920s, has been in decline for decade and the pipeline is running at 33% capacity.

See Hadlari and Issler and Pyle and Gal in References.

<http://www.ihs.com/products/oil-gas-information/source-newsletter/international/jan2012/canadian-alaskan-exploration.aspx>

Geoscience Office

<http://www.nwtgeoscience.ca/petroleum/>

http://www.nwtgeoscience.ca/petroleum/unconventional_gas.html

YUKON

Currently, the Yukon Geological Survey is conducting studies to determine the potential of shale gas in the territory. Shale gas has not been explored for or produced in Yukon; however, future oil and gas projects will most likely consider shale gas reservoirs as potential targets. Shale is likely found in all of Yukon's oil and gas basins. Whether or not the shale formations contain natural gas in sufficient quantity to produce has yet to be determined. The Yukon Geological Survey conducted a scoping study to identify the presence of shale gas and other unconventional oil and gas resources in the Yukon. The results of this study were published in 2012. http://ygsftp.gov.yk.ca/publications/miscellaneous/Reports/YGS_MR-7.pdf

Northern Cross Yukon acquired 15 exploration permits in Northern Yukon. There will be 4 wells drilled in the far north for conventional targets as well as consideration of the shale potential in the Devonian. In the south, in the Laird Basin, which extends into BC, EFLO Energy and partners are planning to exploit the Devonian/Mississippian shales near the Kotaneelee conventional field. This resource has the potential of 500 to 100 BCF of conventional gas and 7.2 to 13 TCF of shale gas. A sales gas pipeline exists to Ft. Nelson.

The Yukon government has established a committee to review hydraulic fracturing before it is permitted.

<http://www.legassembly.gov.yk.ca/rbhf.html>

Yukon Energy, Mines and Resources

<http://www.geology.gov.yk.ca/>

<http://www.emr.gov.yk.ca/oilandgas/>

NUNAVUT

There are 12 Basins with potential and discovered hydrocarbons through to the Paleozoic. Nothing is being worked on but shale plays would exist within the many source rock intervals. It is too isolated to be commercial at present.

Canada-Nunavut Geoscience Office <http://cngo.ca/>

Other Important Canadian Websites

National Energy Board of Canada

<http://www.neb-one.gc.ca/clf-nsi/rcmmn/hm-eng.html>

Geological Survey of Canada

<http://www.nrcan.gc.ca/earth-sciences/about/organization/organization-structure/geological-survey-of-canada/9590>

Canadian Association of Oil Producers

<http://www.capp.ca/Pages/default.aspx>

Societies, Conferences and Courses

Canadian Society for Unconventional Gas (CSUR)

<http://www.csur.com/>

Annual Unconventional Resources Conference

2014 October 15 & 16 at the TELUS Convention Centre in Calgary, AB.

Note that they have technical luncheons for members.

<http://www.csur.com/events/technical-conference>

Canadian Society of Petroleum Geologists (CSPG)

Note the CSPG has technical luncheons throughout the year.

<http://www.cspg.org/>

GeoConvention 2014: Focus: Calgary TELUS Convention Centre, May 12 – 16, 2014

<http://www.geoconvention.com/>

CSPG Courses

http://www.cspg.org/CSPG/Education/Education_Week/CSPG/ConEd/Courses_By_Event.aspx?key=aa56013f-7c87-4cfd-af15-8aa5c9cece60

Other Meetings

CI Energy Group's 10th Annual Shale Oil & Gas Symposium, January 28-29, 2014 in Calgary

<http://www.shalegassymposium.com/>

2014 International LNG in B.C.: British Columbia's LNG in the Global Market May 21 – 23, 2014 | Vancouver Convention Centre

http://engage.gov.bc.ca/Inginbc/files/2014/02/LNG_BC_agenda_download1.pdf

8th Unconventional Gas Technical Forum on June 5 and 6, 2014 at the Victoria Conference Centre - Victoria, B.C.

<http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/UnconventionalGas/Pages/default.aspx>

2014 Williston Basin Conference, Bismarck, North Dakota, May 20-22, 2014

<http://www.wbpc.ca/>

Hart Energy's Developing Unconventionals (DUG™) Canada conference and exhibition, Feb 25-27 2012 at the TELUS Convention Centre, in Calgary, Alberta, Canada.

Hart Energy's Developing Unconventionals (DUG™) Canada conference and exhibition, Feb 24-26 2013 at the TELUS Convention Centre, in Calgary, Alberta, Canada.

Feb 24-26, 2014 at the TELUS Convention Centre in Calgary, Alberta, Canada

<http://www.dugcanada.com/>

Exploration, Mining and Petroleum New Brunswick 2013, Delta Hotel Fredericton, November 3 to 5. 2014

http://www2.gnb.ca/content/gnb/en/departments/energy/conference/Conf_home.html

9th International Symposium of West Newfoundland Oil and Gas 10-11 Sept 2014, Corner Brook area of West Newfoundland.

<http://www.wnloilandgas.com/international-symposium/>

Key References and Information on Canadian Shales:

- Adams, C., 2010, Shale gas activity in British Columbia – exploration and development of BC’s shale gas areas: Presentation to 4th annual Unconventional Technical Forum, Victoria, BC.
- Adams, C., 2011. Overview of shale gas operator activity in the Horn River Basin: Presentation to 5th annual Unconventional Technical Forum, Victoria, BC.
- Adams, C., 2012, Summary of shale gas activity in northeast British Columbia 2011: BC Ministry of Energy and Mines, pages 1-19.
<http://www.empr.gov.bc.ca/Mining/Geoscience/PublicationsCatalogue/OilGas/OGReports/Documents/2012/Summary%20of%20Shale%20Gas%20Activity%20in%20NEBC%202011%20Web.pdf>
- Adams, C., 2013, Summary of shale gas activity in Northeast British Columbia 2012; in Oil and Gas Reports 2013, British Columbia Ministry of Natural Gas Development, pages 1–27.
<http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/statsactivity/Pages/default.aspx>
- Adams, C., 2013 The Status of Drilling and Production in BC’s Shale Gas Plays September 23, 2013
<http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/statsactivity/Documents/5th%20NE%20BC%20Nat%20Gas%20Summit.pdf>
- BC MEM/NEB Report, May 2011, Ultimate Potential for Unconventional Natural Gas in Northeastern British Columbia’s Horn River Basin.
http://www.em.gov.bc.ca/OG/Documents/HornRiverEMA_2.pdf
- B.C. Oil and Gas Commission, October 2012 Montney Formation Play Atlas NEBC
<http://www.bcogc.ca/node/8131/download>
- Beaton, A.P., Pawlowicz, J.G., Anderson, S.D.A., Berhane, H. and Rokosh, C.D. (2010): Organic petrography of the Montney Formation in Alberta: shale gas data release; Energy Resources Conservation Board, ERCB/AGS Open File Report 2010-07, 129 p.
http://www.ags.gov.ab.ca/publications/OFR/PDF/OFR_2010_07.PDF
- Beaton, A.P., Pawlowicz, J.G., Anderson, S.D.A., Berhane, H. and Rokosh, C.D. (2010): Organic petrography of the Duvernay and Muskwa formations in Alberta: shale gas data release; Energy Resources Conservation Board, ERCB/AGS Open File Report 2010-06, 147 p.
http://www.ags.gov.ab.ca/publications/OFR/PDF/OFR_2010_06.PDF
- Béland Otis, Catherine, Carter, Terry and Fortner, Lee, 2011, Preliminary Results of a Shale Gas Assessment Project in Ontario, Canada: Search and Discovery Article #50390
- Béland Otis, C. 2012, Preliminary results: potential Ordovician shale gas units in southern Ontario; in Summary of Field Work and Other Activities 2012, Ontario Geological Survey, Open File Report 6280, p.29-1 to 29-12.
<http://www.geologyontario.mndm.gov.on.ca/mndmfiles/pub/data/imaging/ofr6280//OFR6280.pdf>
- Carter, Fortner and Béland-Otis, 2009, Ordovician and Devonian Black Shales and Shale Gas in Southwestern Ontario, Canada.
http://www.ogsrlibrary.com/downloads/Ontario_Shale_Gas_OPI_2009_Nov11.pdf
- CBM Solutions, 2005, Gas shale potential of Devonian strata, northeastern British Columbia. B.C. Ministry of Energy, Mines and Petroleum Resources, Resource Development and Geoscience Branch: Petroleum Geology Special Paper 2005-01, 110 p.
- Chalmers, G.R.L. and Bustin, R.M., 2008, Lower Cretaceous gas shales in northeastern British Columbia, Part II: evaluation of regional potential gas resources: Bulletin of Canadian Petroleum Geology, vol. 56, p. 22-61.

- Chalmers G.R.L and Bustin R.M., 2012, Light volatile liquid and gas shale reservoir potential of the Cretaceous Shaftesbury Formation in northeastern British Columbia, Canada: AAPG Bulletin, v. 96, no. 7, pp. 1333–1367.
- Churcher, P.L., Johnson, M.D., Telford, R.G. and Barker, J.F., 1991, Stratigraphy and Oil Shale Resource Potential of the Upper Ordovician Collingwood Member, Lindsay Formation, Southwestern Ontario: Ontario Geological Survey, Open File Report 5817, 98p.
<http://www.geologyontario.mndmf.gov.on.ca/mndmfiles/pub/data/imaging/OFR5817/OFR5817.pdf>
- Dixon, J, 2009, The Lower Triassic Shale member of the Montney Formation in the subsurface of northeast British Columbia: Geological Survey of Canada, Open File 6274, 9 p. + 10 figures + 5 appendices.
- Dunn, L., Schmidt, G., Hammermaster, K., Brown, M., Bernard, R., Wen, E., Befus, R., and Gardiner, S., 2012, The Duvernay Formation (Devonian): Sedimentology and Reservoir Characterization of a Shale Gas/Liquids play in Alberta, Canada: CSPG Convention.
http://www.cspg.org/documents/Conventions/Archives/Annual/2012/core/280_GC2012_The_Duvernay_Formation.pdf
- Faraj, B., H. Williams, G. Addison, B. McKinstry, R. Donaleshen, G., Sloan, J. Lee, T. Anderson, R. Leal, C. Anderson, C. Lafleur, and J. Ahlstrom, 2002, Gas shale potential of selected Upper Cretaceous, Jurassic, Triassic and Devonian shale formations in the WCSB of western Canada: Implications for shale gas production: Des Plaines, IL, Gas Technology Institute, GRI-02/0233, compact disc, 285 p.
- Faraj, B., H. Williams, G. Addison, and B. McKinstry, 2004, Gas potential of selected shale formations in the western Canadian sedimentary basin: GasTIPS, v. 10, no. 1, p. 21-25.
- Ferri, F., Hickin, A.S., and Huntley, D.H., 2011a, Besa River Formation, western Liard Basin, British Columbia (NTS 094N): geochemistry and regional correlations. In: Geoscience Reports 2011, B.C. Ministry of Energy and Mines, p. 1-18.
- Ferri, F., Hickin, A.S., and Huntley, D.H., 2011b, Geochemistry and shale gas potential of the Garbutt Formation, Liard Basin, British Columbia (Parts NTS 094N, O; 095B, C). In: Geoscience Reports 2011, B.C. Ministry of Energy and Mines, p. 19-36.
- Fiess, Kathryn M.; Filippo Ferri, Tiffani L. Fraser, Leanne J. Pyle, Jonathan Rocheleau, 2013, Liard Basin Hydrocarbon Project: Shale Gas Potential of Devonian-Carboniferous Strata in the Northwest Territories, Yukon and Northeastern British Columbia, 2013 CSEG CSPG CWLS Conference
http://geoconvention.org/archives/2013abstracts/263_GC2013_Liard_Basin_Hydrocarbon_Project.pdf
- Fraser, T.A., Allen, T.L., Lane, L.S., and Reyes, J.C., 2012, Shale gas potential of Devonian shale in north Yukon: Results from a diamond drillhole study in western Richardson Mountains. In: Yukon Exploration and Geology 2011, K.E. MacFarlane and P.J. Sack (eds.), Yukon Geological Survey, p. 45-74. http://www.geology.gov.yk.ca/pdf/04_fraser_etal.pdf
- Hadlari, Thomas and Issler, Dale R., 2012, Natural fracturing of the Canol Formation oil shale: an unconventional spin on unconventional spin on the Norman Wells oilfield: CSPG Convention.
http://www.cspg.org/documents/Conventions/Archives/Annual/2012/109_GC2012_Natural-Fracturing_of_the_Canol_Formation_Oil_Shale.pdf
- Hamblin, A.P., 2006, The “shale gas” concept in Canada: a preliminary inventory of possibilities: Geological Survey of Canada, Open File 5384, 108 p.
- Hannigan, P.K., Morrow, D.W., and MacLean, B.C., 2011, Petroleum resource potential of the northern mainland of Canada (Mackenzie Corridor): Geological Survey of Canada Open File 6757, 271 p.
- Hayes, B.J.R., 2010, Northwest Territories Unconventional Natural Gas Scoping Study: Northwest Territories Geoscience Office, NWT Open File 2010-03, 81 p.
<http://gateway.nwtgeoscience.ca/advancedsearch.php?rptnums=2010-03&authors=&rpttype=&datestart=&dateend>

- Hayes, B.J.R., 2011, Regional Characterization of Shale Gas and Shale Oil Potential, Northwest Territories: Northwest Territories Geoscience Office, NWT Open File 2011-08, 34 p. plus maps and cross-sections.
<http://gateway.nwtgeoscience.ca/advancedsearch.php?rptnums=2011-08&authors=&rpttype=&datestart=&dateend>
- Hayes, B.J.R. and Archibald, H.B., 2012, Scoping study of unconventional oil and gas potential, Yukon: Yukon Geological Survey, Miscellaneous Report 7, 100 p.
http://ygsftp.gov.yk.ca/publications/miscellaneous/Reports/YGS_MR-7.pdf
- Johnson, M.D., Telford, P.G., Macauley, G. and Barker, J.F., 1989, Stratigraphy and oil shale resource potential of the Middle Devonian Marcellus Formation, southwestern Ontario: Ontario Geological Survey, Open File Report 5716, 149p.
<http://www.geologyontario.mndmf.gov.on.ca/mndmfiles/pub/data/imaging/OFR5716/OFR5716.pdf>
- Kreis, L.K. and Costa, A., 2005, Hydrocarbon potential of the Bakken and Torquay formations, southeastern Saskatchewan: in Summary of Investigations, 2005, Volume 1, Saskatchewan Geological Survey, Sask. Industry Resources, Misc. Rep. 2005-4.1, CD-ROM, Paper A-10, 10p.
- Kreis, L.K., Costa, A.L., and Osadetz, K.G., 2006, Hydrocarbon potential of Bakken and Torquay formations, southeastern Saskatchewan: in Gilboy, C.F. and Whittaker, S.G. (eds.), Saskatchewan and Northern Plains Oil & Gas Symposium 2006, Saskatchewan Geological Society Special Publication 19, p118-137.
http://www.manitoba.ca/iem/mrd/geo/willistontgi/downloads/kreis_et_al_bakken-torquay_paper.pdf
- Kohlruss, D. and Nickel, E., 2009, Facies Analysis of the Upper Devonian – Lower Mississippian Bakken Formation, Southeastern Saskatchewan: in Summary of Investigations 2009, Volume 1, Saskatchewan Geological Survey, Sask. Ministry of Energy and Resources, Misc. Rep. 2009-4.1, Paper A-6, 11p.
- Kohlruss, Dan, Erik Nickel and Jeff Coolican, 2012 Stratigraphic and Facies Architecture of the Saskatchewan Oil Sands, Williston Basin Conference.
http://www.ndoil.org/image/cache/230pm_Wed_Kohlruss_WBPC_2012.pptx
- Lavoie, D., Hamblin, A.P., Thériault, R., Beaulieu, J. and Kirkwood, D., 2008, The Upper Ordovician Utica Shales and Lorraine Group flysch in southern Québec: Tectonostratigraphic setting and significance for unconventional gas: Geological Survey of Canada, Open File 5900, 56 pages.
http://geopub.nrcan.gc.ca/moreinfo_e.php?id=225728
- Lavoie, D., Pinet, N., Dietrich, J., Hannigan, P., Castonguay, S., Hamblin, A. P. and Giles, P., 2009, Petroleum Resource Assessment, Paleozoic successions of the St. Lawrence Platform and Appalachians of eastern Canada: Geological Survey of Canada, Open File 6174, 2009; 275 pages
http://geopub.nrcan.gc.ca/moreinfo_e.php?id=248071
- Lavoie, Denis, 2012, Lower Paleozoic Shale Gas and Shale Oil Potential in Eastern Canada: Geological Settings and Characteristics of the Upper Ordovician Shales: Search and Discovery Article #80242
- Lavoie, D. and Thériault, R. 2012. Upper Ordovician shale gas and oil in Quebec: sedimentological, geochemical and thermal frameworks; oral presentation, Canadian Society of Petroleum Geologist, GeoConvention 2012: Vision, Calgary, Alberta, May 14-18, 2012.
- Marcil, Jean-Sebastien, Dorrins, Peter K., Lavoie, Jérémie, Mechti, Nabila and Lavoie, Jean-Yves, 2012, Utica and Other Ordovician Shales: Exploration History in the Quebec Sedimentary Basins, Eastern Canada: Search and Discovery Article #10451
- McDonald, Adam, 2012, The Horton Bluff Formation Gas Shale Opportunity, Nova Scotia, Canada; AAPG Search and Discovery Article #90124
<http://www.searchanddiscovery.com/abstracts/html/2011/annual/abstracts/MacDonald.html?q=%2BtitleStirip%3Acanada+%2ByearSort%3A%5B2011+TO+2012%5D>

- Meloche, Dennis, 2011, How Deep is Shallow? Re-evaluation of Depositional Models for the Jurassic Nordegg and Rock Creek Members of the Fernie Group: CSPG Convention, Calgary.
http://www.cspg.org/documents/Conventions/Archives/Annual/2011/263-How_Deep_is_Shallow.pdf
- National Energy Board (NEB), November 2009, A Primer for Understanding Canadian Shale Gas
- National Energy Board (NEB), December 2011, Tight Oil Developments in the Western Canada Sedimentary Basin. <http://www.neb-one.gc.ca/clf-nsi/rnrgynfmtn/nrgyrprt/l/tghtdvlpmntwscsb2011/tghtdvlpmntwscsb2011-eng.pdf>
- National Energy Board (NEB), November, 2013. The Ultimate Potential for Unconventional Petroleum from the Montney Formation of British Columbia and Alberta
<http://www.neb-one.gc.ca/clf-nsi/rnrgynfmtn/nrgyrprt/ntrlgs/ltmptntlmntnyfrmtn2013/ltmptntlmntnyfrmtn2013-eng.html>
- Nicolas, M.P.B. and Bamburak, J.D. 2009, Geochemistry and mineralogy of Cretaceous shale, Manitoba (parts of NTS 62C, F, G, H, J, K, N): preliminary results: in Report of Activities 2009, Manitoba Innovation, Energy and Mines, Manitoba Geological Survey, p. 165-174.
- Nicolas, M.P.B., and J.D. Bamburak, 2009, Shallow unconventional Cretaceous shale gas in southwestern Manitoba: CSPG, CSEG, CWLS Convention, Calgary.
- Nicolas, M.P.B. 2011: Stratigraphy and regional geology of the Late Devonian–Early Mississippian Three Forks Group, southwestern Manitoba (NTS 62F, parts of 62G, K); Manitoba Innovation, Energy and Mines, Manitoba Geological Survey, Geoscientific Report GR2012-3, 92 p
<http://www.manitoba.ca/iem/mrd/info/libmin/GR2012-3.pdf>,
- Pawlowicz, J.G., Anderson, S.D.A., Rokosh, C.D., and Beaton, A.P., 2009a. Mineralogy, permeability, mercury porosimetry and scanning electron microscope imaging of the Banff and Exshaw formations; shale gas data release: Energy Resources Conservation Board, ERCB/AGS Open File Report 2008-13.
- Pawlowicz, J.G., Anderson, S.D.A., Rokosh, C.D., and Beaton, A.P., 2009b. Mineralogy, permeability, mercury porosimetry and scanning electron microscope imaging of the Colorado Group; shale gas data release: Energy Resources Conservation Board, ERCB/AGS Open File Report 2008-14.
- Pyle, Leanne J. and Gal, Leonard P., 2012, Devonian Horn River Group in Mackenzie Plain Area, Northwest Territories.
http://www.empr.gov.bc.ca/OG/oilandgas/petroleumgeology/UnconventionalGas/Documents/Devonian%20Horn%20River%20Group%20in%20Mackenzie%20Plain%20Area_NWT.pdf
- Rokosh, C.D., Pawlowicz, J.G., Berhane, H., Anderson, S.D.A., and Beaton, A.P., 2009. What is Shale Gas? An introduction to shale gas geology in Alberta: Energy Resources Conservation Board/Alberta Geological Survey Open File Report 2008-08, 26 p.
http://www.ags.gov.ab.ca/publications/OFR/PDF/OFR_2008_08.PDF
- Rokosh, C.D., Lyster, S., Anderson, S.D.A., Beaton, A.P., Berhane, H., Brazzoni, T., Chen, D., Cheng, Y., Mack, T., Pana, C. and Pawlowicz, J.G. (2012): Summary of Alberta's shale- and siltstone-hosted hydrocarbon resource potential; Energy Resources Conservation Board, ERCB/AGS Open File Report 2012-06, 327 p.
http://www.ags.gov.ab.ca/publications/abstracts/OFR_2012_06.html
- Ross, D., G. Chalmers, and R.M. Bustin, 2005, Reservoir characteristics of potential gas shales in the western Canadian sedimentary basin: in P. Lufholm and D. Cox, eds., 2005 WTGS Fall Symposium: West Texas Geological Society, Publication No. 05-115, p. 41.
- Ross, D.J.K., and R.M. Bustin, 2007, Shale gas potential of the Lower Jurassic Gordondale member, northeastern British Columbia, Canada: Bulletin of Canadian Petroleum Geology, v. 55, p. 51-75.
- Ross, D.J.K., and R.M. Bustin, 2008, Characterizing the shale gas resource potential of Devonian-Mississippian strata in the western Canada sedimentary basin: Application of an integrated formation evaluation: AAPG Bulletin, v. 92, p. 87-125.
- Russum, Dave, 2011, The Montney, A world class resource with a myriad of challenges and opportunities: CSPG CSEG CWLS Convention.

http://www.searchanddiscovery.com/documents/2011/80128russum/ndx_russum.pdf

Séjourné, S., Lefebvre, R., Malet, X., and Lavoie, D., 2013, Synthèse géologique et hydrogéologique du Shale d'Utica et des unités sus-jacentes (Lorraine, Queenston et dépôts meubles), Basses-Terres du Saint-Laurent, Province de Québec. Geological Survey of Canada, open file in press.

Séjourné Stephan, René Lefebvre, Denis Lavoie and Xavier Malet, 2013, Geological and Hydrogeological Synthesis of the Utica Shale and the Overlying Strata in Southern Quebec Based on Public Data in a Context of a Moratorium on Exploration CSPG Convention 2013

http://www.geoconvention.com/uploads/2013abstracts/066_GC2013_Geological_and_Hydrogeological_Synthesis.pdf

Walsh, W., Adams, C., Kerr, B., and Korol, J., 2006, Regional "shale gas" potential of the Triassic Doig and Montney formations, northeastern British Columbia: BC Ministry of Energy, Mines and Petroleum Resources, Resource Development and Geoscience Branch, Petroleum Geology Open File 2006-02, 19 p.

Wrolson, B.M. and Bend, S.L., 2012, High Resolution Organic Facies of the Bakken Formation, Williston Basin, Saskatchewan, Canada: Search and Discovery #50645.

Yurkowski, Melinda and Wilhelm, Bruce, 2009, Oil Shales in Saskatchewan

<http://www.saturnminerals.com/i/pdf/oilshalesaskatchewan.pdf>

Zaitlin, Brian, Berger, Zeev, Kennedy, Joyce and Kehoe, Steven, 2011, The Alberta Bakken: A Potential New, Unconventional Tight Oil Resource Play: CSPG Convention.

http://www.cspg.org/documents/Conventions/Archives/Annual/2011/137-The_Alberta_Bakken.pdf

Zaitlin, Brian 2012, An Emerging Unconventional Hybrid Light Tight Oil Play within the Southern Alberta Bakken-Exshaw Petroleum System: A Comparison between the Williston and Southern Alberta Basins. Williston Basin Conference, Regina.

http://wbpc.ca/+pub/document/2013_presentations/Zaitlin%20-%20An%20Emerging%20Unconventional%20Hybrid.pdf

Shale Gas/Shale Oil in Europe

By Ken Chew

Summary of the five months November 2013 – March 2014

Europe remains relatively unexplored for shale gas and, especially, shale liquids. In total some 110 exploration and appraisal wells with a shale gas exploration component have been drilled, including horizontal legs from vertical wells. 25 of these wells were shallow gas tests drilled in Sweden, largely using mineral exploration equipment. Up to 6 wells have been drilled to target shale liquids. Significant shale gas exploration activity since November 2013 has been limited to Poland, where 6 shale gas exploration wells were spudded, and England where one coal seam gas exploration well is also investigating shale gas potential. The first shale liquids test results have been reported from Poland.

Opposition to hydraulic fracturing and shale oil and gas exploration at grassroots level in general remains strong and major protests have taken place in the United Kingdom and Romania. Public pressure has resulted in moratoria being placed on some or all aspects of shale gas exploration and production in Bulgaria, Czech Republic, France, Germany and Netherlands, plus certain administrative regions in Spain and Switzerland. Proposed new environmental legislation has led OMV to abandon its plans for shale gas exploration in Austria. But at a European and national political level, one can detect a desire to permit and even encourage exploration. While Germany effectively introduced a moratorium on hydraulic fracturing in November 2013, the Spanish government has moved to explicitly legalise hydraulic fracturing and the European Commission clarified its position in January 2014 without issuing binding legislation.

Political institutions and major companies have noted the impact of shale gas and shale oil production on the U.S. economy and fear that European consumers are suffering from unduly high gas prices and that European companies are becoming uncompetitive compared with their North American rivals and even considering relocating businesses to North America. Politicians, especially in Eastern Europe, are expressing a desire for more energy independence and recent political upheavals in Ukraine have added to those concerns. In addition, technical experts such as the French Académie des Sciences and German Federal Institute for Geosciences and Natural Resources have challenged the views and reports of environmental authorities.

The decision by ExxonMobil to withdraw from its six licences in Poland, considered to be the most prospective European country for shale gas, has also had the effect of downgrading expectations in some quarters. Talisman has also withdrawn from Poland and Marathon and Eni have indicated their intention to do so. Nevertheless, Poland, in terms of current and proposed drilling activity, and the United Kingdom, in terms of farm-in activity and government support for the emerging shale gas industry, seem to be the two countries that offer most prospectivity in the medium term. The perceived prospectivity of the U.K. is indicated by farm-ins to acreage with shale gas potential by Centrica, GDF Suez and French major Total, all within the past nine months.

1. Shale gas in Europe

Europe is particularly well-suited to gas resource play exploitation on account of its large market, established pipeline infrastructure, increasing demand and current dependence on gas imports. Relatively high natural gas prices add to the attraction. Shale gas exploration in Europe is in its infancy. The first exploratory well was spudded in Scotland in 2005 and since then shale-specific exploratory drilling has been limited to five countries, with most wells being drilled from 2010 onwards. As a consequence, little is known about Europe's ultimate potential.

Resources.

Rogner's 1996 estimate of the in-place shale gas resource of Europe (including Turkey) was 550 Tcf. More recent studies indicate significantly larger in-place resources. In its assessment of the world's shale gas resource, the U.S. Energy Information Administration (EIA) estimated the European shale gas in-place resource for 9 countries at 2,314 Tcf with a combined technically recoverable resource of 563 Tcf (U.S. EIA, 2011). A revised and extended report published in June 2013 (U.S. EIA, 2013) increased the study to 12 countries and included additional areas within countries such as Poland. The gas in place estimate increased to 2,408 Tcf but the recoverable estimate decreased to 472 Tcf (Table 1).

The EIA study estimates a gross shale rock volume based on maps of areal distribution and cross sections indicating lateral extent, unit thickness and depth of burial. Free gas and adsorbed gas in place are then estimated using available organic content and maturity data. Technically recoverable gas is then calculated by applying one of three recovery factors (Favourable – 25%; Average – 20%; Less Favourable – 15%) based on clay content, geological complexity, reservoir pressure and gas-filled porosity. Clearly, these estimates must be treated with caution. Much of the detailed information required to make accurate assessments is simply not available in many areas and so the assessments are still relatively speculative as the following individual country reports frequently indicate.

Austria: OMV has suggested a potential recoverable shale gas resource of 15 Tcf in the Vienna Basin, Austria, from an in-place resource of 200-300 Tcf.

Denmark: The U.S. Geological Survey (2013) has estimated mean technically recoverable resources of Denmark's Alum Shale to be 6.935 Tcf, of which 0 to 4.848 Tcf (mean: 2.509 Tcf) occur onshore

and 0 to 8.492 Tcf (mean: 4.426 Tcf) lie offshore. The much larger EIA recoverable shale gas estimates (2011: 23 Tcf; 2013: 32 Tcf) are for the onshore area only.

	EIA 2011		EIA 2013	
	Gas Initially In Place	Technically-Recoverable	Gas Initially In Place	Technically-Recoverable
Bulgaria			66	17
Denmark	92	23	159	32
France	720	180	727	137
Germany	33	8	80	17
Lithuania	17	4	4	0
Netherlands	66	17	151	26
Norway	333	83	0	0
Poland	792	187	763	148
Romania			233	51
Spain			42	8
Sweden	164	41	49	10
United Kingdom	97	20	134	26
TOTAL	2,314	563	2,408	472

Table 1. Shale Gas Initially In Place and Technically Recoverable from selected European Countries rounded to nearest Trillion Cubic Feet (EIA, 2011, 2013)

Germany: In Germany the Federal Institute for Geosciences and Natural Resources (BGR) has estimated recoverable shale gas to be in the range 24 – 80 Tcf from an in-place resource of 240 – 800 Tcf.

Netherlands: TNO’s “best estimate” for “producible gas in place” in “high potential” areas of the Netherlands is 198 Tcf from an estimated in-place resource of 3,950 Tcf. This is substantially greater than either of the EIA estimates (Table 1 above).

Poland: Four estimates of Polish Shale Gas resources have been made public through end-2013 (Table 2). The variance between the estimates is in large part a result of differences in methodology, which are outlined below.

Poland Shale Gas		Gas Initially In Place (Tcf)	Technically-Recoverable (Tcf)			Recovery
Study	Basin	Risked / Mean	P95 / Min	Risked / Mean	P5 / Max	Percent
EIA 2011	Baltic	514		129		25.1%
EIA 2011	Lublin	222		44		19.8%
EIA 2011	Podlasie	56		14		25.0%
EIA 2011	Polish Foredeep Total	792		187		23.6%
Polish Geological Institute March 2012	Polish Foredeep Total		1.22 - 2.71	12.2 - 27.1	30.5 - 67.8	
U.S. Geological Survey July 2012	Polish Foredeep Total		0	1.345	4.086	
EIA 2013	Baltic	532.1		105.2		19.8%
EIA 2013	Lublin	45.8		9.2		20.1%
EIA 2013	Podlasie	53.6		10.1		18.8%
EIA 2013	Polish Foredeep Total	631.5		124.5		19.7%
EIA 2013	Fore Sudetic	106.7		21.3		20.0%
EIA 2013	Poland Total	738.2		145.8		19.8%

Table 2. Estimates of Polish In-place and Technically Recoverable Shale Gas Resources

Polish Geological Institute – National Research Institute (PGI).

The study was based on archive data from 39 wells drilled between 1950 and 1990. Cut-offs of 15m shale thickness (minimum), 2% TOC (minimum) and thermal maturity (Ro) in the range 1.1 – 3.5% were chosen. In the absence of key data such as porosity, permeability, mineral composition, reservoir pressure and initial production (IP), Estimated Ultimate Recovery (EUR) and average well drainage area were based on U.S. analogues. The range of estimates therefore reflects the combination of two uncertainties: EUR per well, for which the range uses the results of the most poorly performing, the main cluster, and best performing of U.S. basins; potentially productive area conforming to the cut-off criteria, for which the greatest uncertainty lies in estimating TOC, which was largely unrecorded and which therefore relied on extrapolation from Gamma Ray and other logs. A revised PGI estimate, based on testing of at least one significant horizontal leg, was planned for 2014 but it has also been suggested that a new summary report will await the drilling of 100 exploratory wells, which is still some way off.

U.S. Geological Survey (USGS): The study was based on archive data from 56 wells drilled before 1990. The methodology was broadly similar to that of the PGI study (as the USGS was involved in training PGI staff). There were, however, significant differences in some of the criteria adopted, as follows:

- The PGI study includes offshore whereas the USGS study is limited to onshore. Whereas this, and the estimation of other cut-off criteria, resulted in a potentially productive area in the range 18,540 – 41,140 km² in the PGI study, the modal value in the USGS study was 4,850 km² with a maximum value of 20,250 km².
- Based on U.S. analogues, the PGI study estimated EUR per well in the most likely case as 0.4 Bcf/well whereas the USGS estimates it as 0.2 Bcf/well.
- The USGS also applies an average success factor to drilled wells which, in the most likely case, it estimates at 50%.

The combination of these differences accounts for the variance between the PGI and USGS estimates.

U.S. Energy Information Administration (EIA): The EIA reports (U.S. EIA, 2011; U.S. EIA, 2013) were prepared on behalf of the EIA by Advanced Resources International (ARI).

Their methodology is fundamentally different from those of the PGI and USGS. As global studies, the reports rely on geological information and reservoir properties assembled from the technical literature and data from publically available company reports and presentations. Depths and thicknesses, for example, are typically assembled from regional cross sections. In addition, the methodology is based on making an estimation of gas initially in place and applying a recovery factor to this. The reports use one of three recovery factors: 15%; 20%; 25%. In the case of Poland they have generally selected a 20% recovery factor which is said to be applicable to plays with a medium clay content, moderate geologic complexity and average reservoir pressure and properties. In the case of Poland, this may be a rather optimistic outlook given that the only North American Lower Paleozoic analogue, the Utica Shale, is considered to have superior gas shale character to the Polish Foredeep shales but has recovery factors varying between 10 and 20%.

The 2011 study was limited to onshore but still considered the potentially productive area to be 53,115 km², greater than the maximum combined onshore and offshore area estimated by the PGI. All gas shale characteristics were based on those of the Lower Silurian. In the 2013 study, the potentially productive area of the onshore Polish Foredeep was reduced to 36,080 km², which is nevertheless some 3,000 km² greater than the maximum potentially productive onshore area estimated by the PGI. The 2013 report assessed the combined Lower Silurian, Ordovician and Upper Cambrian intervals.

Sweden: The initial (2011) EIA report provided an estimated technically recoverable resource of 41 Tcf for Sweden's Alum Shale, which Shell's three wells found to have a very limited content of natural gas which it was not possible to produce. In the 2013 report, the estimate of technically recoverable resources for the Alum Shale was reduced to 9.8 Tcf.

United Kingdom: Based on analogy with comparable shale plays in the U.S., in 2010 the British Geological Survey (BGS) tentatively estimated recoverable reserves (England only) at approximately 5.3 Tcf. In June 2013, the BGS and Department of Energy and Climate Change (DECC) produced an estimate for gas in place in the Bowland Shale in the Craven Basin across Central England (Andrews, 2013). Total gas in place is estimated to fall within the range 822 Tcf (P90) to 2,281 Tcf (P10) with the most probable estimate (P50) being 1,329 Tcf. Compared with the EIA analyses, the BGS study is very much "bottom-up", based on geological parameters, volumetrics and gas contents. A similar study is under way for the Weald Basin in southeast England and this will be followed by a study of the Carboniferous potential of central Scotland. The Midland Valley of Scotland, where Europe's first certification of recoverable shale gas resources has taken place, was considered in the initial (2011) EIA report to be non-prospective.

General: Given the potential size of the in-place resource it is not surprising that investigations have been proposed in at least seventeen countries. Company interest has ranged from super-majors, such as ExxonMobil and Shell, through majors (Chevron; ConocoPhillips; Eni; Total) and major independents (e.g. Marathon Oil; Talisman) to small niche players (e.g. Cuadrilla Resources) and coal seam gas explorers who may have some shale gas potential on their acreage (e.g. IGas Energy). Some of these companies have subsequently withdrawn from Europe (Talisman) or indicated their intention to do so (Marathon Oil; Eni). A number of companies have published resource estimates for their own acreage and these are reported in the shale gas plays section for individual plays by country (2.1 below).

2.1 Major shale gas plays in Europe

Organic-rich "bituminous" shales which form the self-contained source-reservoir petroleum systems that can be exploited for natural gas and hydrocarbon liquids occur at many stratigraphic levels. Global oceanic anoxic events (OAEs), which favour the preservation of organic matter, took place in the Late Ordovician and into the Silurian, in the Early Jurassic (Toarcian), and in the Late Cretaceous (Cenomanian-Turonian). In Europe, additional anoxic events occurred on a regional scale in the Late Cambrian, Visean (Middle Mississippian) to Namurian (Early Pennsylvanian), and Late Jurassic (Kimmeridgian-Tithonian). All of these units are under investigation in Europe, though the younger units tend to be more prospective for shale liquids than shale gas. There are three potentially major regional shale gas plays in Europe plus a number of others with more restricted distribution.

2.1.1 Lower Paleozoic

The oldest is a Lower Paleozoic play that occurs in northwest Europe running from eastern Denmark through southern Sweden to north and east Poland. The organic-rich shales with shale gas potential lie on the south western margin of the Baltica paleocontinent and tend to thicken towards the bounding Trans-European Suture Zone. This play was first tested in Sweden in 2009 and has since been the focus of exploratory drilling in Poland. In Denmark and Sweden the principal target is the kerogenous Alum Shale of Middle Cambrian to Early Ordovician (Tremadoc) age.

Denmark: Natural gas was first found onshore Denmark in Nordjylland (North Jutland) in 1873 in association with water wells. The first successful well was drilled in 1905, finding gas at intervals down to 600'. Commercial gas production took place from the late 1930s to the early 1950s in the Frederikshavn area. The source, however, is probably shallow biogenic gas. Today, licences have been awarded over the Fennoscandian Border Zone and Norwegian-Danish Basin onshore Denmark.

Total S.A. / Nordsøfonden. Total S.A. has been awarded two licences. In March 2012 Total applied for a third area relinquished by Schuepbach Energy in November 2011 but by September 2012 this application appears to have lapsed. Total and the Danish North Sea Fund (Nordsøfonden) commenced evaluation of the Alum Shale in the North Jutland area (Fennoscandian Border Zone) during 2012. Prior to the planned drilling of Vendsyssel-1 in Nordjylland, a well work program, including environmental studies, was submitted to Frederikshavn Municipality in October 2012. Despite reviews by the Danish Energy Agency, Environmental Protection Agency, Nature Agency and the Administration of Frederikshavn Municipality which raised no comments, Frederikshavn City Council decided on 27th February 2013 to request a full Environmental Impact Assessment (EIA). While disagreeing with the City Council's decision Total and Nordsøfonden decided not to contest it as this would just lead to further delays. On 26th February 2014 the Frederikshavn City Council agreed the EIA reports for publication and it entered an 8-week public consultation period. In August / September 2013, Total and Nordsøfonden undertook an airborne gravity and magnetic survey over the area of their Nordsjælland (North Zealand) licence.

Sweden:

Fennoscandian Border Zone

Shell. On 28th November 2009 Shell spudded the first well in a three-well test programme in Sweden's Colonussänkan permit. The permit overlies the Colonus Shale Trough, Fennoscandian Border Zone (also known as the Sorgenfrei-Tornquist Zone), southern Sweden. Lövestad A3-1, Oderup C4-1 and Hedeberga B2-1 ranged in depth from 2,448' to 3,134'.

The wells encountered Alum Shale (Alunskiffer) ranging in thickness from 225' to 345'. Total Organic Carbon (TOC) ranged from 3 – 16%, averaging 7%. Porosity averaged 6.5% and permeability was approximately 40 nanodarcies. Water saturation, however, was high (80%) and gas analysis (94% methane) indicated that gas content was approximately 30 scf/ton and that the Alum Shale is undersaturated. Vitrinite reflectance measurements from 1.7% to over 2% indicate that the shale is post mature with little capacity for further gas generation. In May 2011, therefore, Shell announced that its investigations had been completed, that the rock samples from the three wells found only very limited gas traces which are not producible, and that the licences would not be renewed when they expired at end-May 2011 (Svenska Shell 2011).

Östergötland Lower Paleozoic Basin

The Östergötland Lower Paleozoic Basin is an E-W faulted synclinal outlier within which the Alum Shale occurs at shallow depth and is thermally immature but the 45'-80' thick shale has high TOC contents of up to 20%. It has been considered by some to be analogous to the biogenic-sourced shale gas of the Antrim Shale in the Michigan Basin. In both basins, methanogenesis may be a consequence of dilution of saline formation brines by meltwater from overlying Pleistocene glaciers. Although the Alum Shale is thermally immature in Östergötland, bitumen is present in limestone concretions and thin sandstones. The origin of these oils is thought to be either long-distance migration or more local heating during the intrusion of Permo-Carboniferous sills. Gas analysis indicates a mixture of thermogenic gas and secondary biogenic gas resulting from the breakdown of these pre-existing hydrocarbons. Gas flows are known from water wells and seeps in the area and flows of up to 40,000 cf/d have been reported from wells. Local farmers use the gas as a heating source and the Linköping commune has a mining (processing) concession, valid until 2033. Four companies own a total of 24 licences in the Östergötland Lower Paleozoic Basin.

Aura Energy. In October 2011, Aura Energy, an Australian uranium exploration company that is investigating the uranium potential of Sweden's Alum Shale, commenced a 5-hole drilling programme at its Motala shale gas project in the Östergötland Lower Paleozoic Basin, south-central Sweden, on the east shore of Lake Vättern near the town of Linköping. The 5 shallow wells were completed during Q4 2011 and gas samples were sent for analysis.

Gripen Oil & Gas. In April 2012, Gripen Gas (now Gripen Oil & Gas), the largest licence holder with 17 permits, announced that it had tested biogenic gas from the Alum Shale at a depth of around 300' in 4 shallow wells drilled in the Ekeby permit in Östergötland. The best well, GH-2, flowed 97.5% methane and in Q3 2012 was appraised by 2 successful step-out wells and a further well drilled adjacent to GH-2 which cored the entire Alum Shale section. A further 3 appraisal wells were drilled in June 2013. All three wells flowed gas to surface from a 3" hole. OPC Ltd. has assigned a 2C contingent resource estimate of 51.0 bcf raw gas to the Östergötland onshore licences. Gripen Oil & Gas has identified three 36-hole development areas on the Ekeby permit. Development Area One (2C resource: 1.70 bcf of 100% CH₄) will be tested by extended well tests in three wells before development proceeds. Gripen Oil & Gas has also been granted the Sandön licence, in Lake Vättern, where the Alum Shale is thought to be deepest and thickest. Water depths range from 30' – 100'. Drilling has already taken place in the lake for mining exploration purposes and it is expected that a first shale gas exploration well will be drilled in Q4-2013 or early 2014. Gripen Oil & Gas also has five (5) concessions in the Baltic Depression on the island of Öland.

Siljan Ring Depression

AB Igrene. Further north, AB Igrene has 18 concessions with Lower Paleozoic shale potential in the Siljan Ring, where Lower Paleozoic rocks have been preserved around the margin of a depression formed by a major Late Devonian meteor impact. The concessions have been renewed until June 15th 2015. To date five percussion holes have been drilled followed by five core holes of about 1,600' each, three of them in the Mora area on the west of the ring, which is now the focus of exploration, with the last two core holes having been drilled there in Q2 2013. Produced gas is dry, exceeding 90% methane with the remainder dominantly nitrogen. Gas occurs at depths below 1,180' in Mora-001 and below 1,000' in Solberga-1. Identified units with shale gas potential include the Tøyen Formation (Lower Ordovician), Fjäckå Shale (Upper Ordovician) and a Llandovery (Lower Silurian) shale (Kallholn Formation?). [Note: In the late 1980s, the Gravberg-1 well was drilled through a fractured granite within the impact crater to a TD of 22,000' to test Thomas Gold's theory of the abiogenic origin of petroleum.]

Poland: Further to the southeast, in Poland, the most widespread Lower Paleozoic target has been Lower Silurian-age graptolitic shale, with the Upper Cambrian to Lower Ordovician and Upper Ordovician being secondary targets. The Silurian in particular thickens towards the southwest in the area of the Gdansk Depression (Baltic Depression) and the Danish-Polish Marginal Trough which defines the southwest margin of the Baltic Depression. In parts of the Trough, such as the Warsaw Trough and Lublin Trough, more than 10,000' of Silurian section may be present. Burial depths to base Silurian range from 3,000' in the east and on the East European Platform Margin to 15,000 in the west, being deepest in the Warsaw Trough. Depths in the Lublin Trough are variable because of the presence of a number of separate fault blocks, but maximum depth to base Silurian is about 10,000'.

To date, this play has been the most sought after in Europe. Some 39 concessions have been awarded in the Baltic Depression, of which 10, largely operated by LOTOS Petrobaltic, are offshore in the Baltic Sea and 29 lie onshore in the Gdansk Depression. Six of the most easterly concessions, such as the four held by Wisent Oil & Gas, were considered to be more prospective for shale liquids than for shale gas. Four concessions have subsequently been relinquished by BNK Petroleum, Eni and PGNiG. Another 40 concessions have been awarded in the Danish-Polish Marginal Trough and 14 on the East European Platform Margin, northeast of the Marginal Trough. 17 of these awards (12 – Marginal Trough; 5 - Platform Margin) have since been relinquished by Cuadrilla, Dart Energy, DPV Service, ExxonMobil and Marathon.

Baltic Depression.

Thirteen different companies are active in the onshore Gdansk Depression including ConocoPhillips and the Polish state company, PGNiG, plus a number of small niche players.

3Legs Resources / ConocoPhillips. The first tests of the Polish Lower Paleozoic commenced in the Gdansk Depression. Between June and October 2010, Lane Energy (a subsidiary of 3Legs Resources) drilled two vertical wells, Lebień LE-1 on its western Lębork concession and Legowo LE-1 (tested with a DFIT) on the eastern Cedry Wielkie concession. In January 2011 Netherland, Sewell & Associates estimated gross gas in place in the Silurian / Ordovician section of Lane's six licences at 170 Tcf. Following a decision to prioritise Lane's three western Baltic Basin concessions, Legowo LE-1 was plugged and abandoned.

A 3,300' horizontal leg drilled within the Upper Ordovician Sasino Formation in a second Lebień well (LE-2H) in May 2011 was the first horizontal shale gas well drilled in Poland. After a 13-stage slickwater frac the well flowed an unstabilised 2.2 MMscf/d on 8th September 2011 using coiled tubing and N₂ lift. It was recompleted with a tubing string on 17th September and flowed from 380 up to 520 Mscf/d on N₂ lift, plus frac fluid. 15% of the total frac fluid had been recovered by the end of the test. A second flow test in early November 2012 using a 3 ½" string flowed at rates of up to 780 Mscf/d, averaging 550 Mscf/d. A third phase of testing commenced on 8th July 2013 using a 2 3/8" tubing string. Downhole pressure gauges were installed and pressurized samples collected. Flowing commenced on 21st July at an initial rate of 470 Mscf/d and had declined to 230 Mscf/d by 11th September, by which time 44% of the frac fluid had been recovered. The productive intervals in all three wells were in the Lower Silurian and Upper Ordovician.

In July 2011 Lane spudded Warblino LE-1H, in a third concession (Damnica). A vertical pilot was drilled to 10,570'. This was followed by a horizontal leg of 4,088' within the top 16' of a presumed new Cambrian prospective interval which was then redrilled with a 1,650' horizontal leg (12,610' MD) because of hole stability issues. Subsequent analysis has revealed that the horizontal leg was actually drilled within the Lower Ordovician Sluchowo Formation instead of the intended Cambrian Alum Shale (also known as the Piasnica Formation). A 7-stage gel frac test was suspended after 5 days during which flow declined from 60-90 Mscf/d to 18 Mscf/d. On retest in summer 2012 the well produced at a rate of 90 Mscf/d after 20 days of flow. Log analysis confirms that the Alum Shale (Piasnica Formation) is prospective in this area re-entering the well to drill and test a lateral within the Cambrian section is under consideration.

Lane's initial seismic and drilling programme on its six Gdansk Depression concessions was funded by ConocoPhillips (see *4.3 Ownership Transactions: Farm-ins*) after which ConocoPhillips opted to retain an interest (and operatorship) in only the three western concessions. The companies spudded the Strzeszewo LE-1 vertical well on the Lębork concession on 4th October 2012 and drilled to a TD of 10,040'. A DFIT was carried out in the Cambrian interval in January 2013 followed by a single stage hydraulic frac in May. Clean-up using nitrogen lift commenced on 4th August. The well was shut in on 7th September 2013 after recovering 22.5% of the frac fluid and flowing gas intermittently. A second DFIT, single-stage hydraulic frac and flow test took place in the primary target, the Upper Ordovician Sasino Formation, in December 2013, flowing gas at modest rates and recovering 63% of frac fluid.

Lublewo LEP-1 was spudded in the Lębork concession in September and drilled to a TD of 9,593'. The rig then spudded Slawoszyno LEP-1 in February 2014 on the Kawia concession, drilling to a TD of 9,250'. The wells confirmed the thickness and prospectivity of the Upper Ordovician Sasino Formation and Upper Cambrian Piasnica Formation. Based on these results and recently acquired 2D seismic, the rig was then mobilised to drill a 5,250' horizontal sidetrack in the Sasino formation in Lublewo LEP-1. A stimulation programme (cross-linked gel) of at least 20 frac stages is planned for this horizontal leg in Q3 2014.

BNK Petroleum – Saponis Investments. The drilling contractor, NAFTA Pila, which drilled the first two Lane wells spudded Wytowno S-1 (Slawno concession) in December 2010 on behalf of Saponis (BNK; RAG; Sorigenia; LNG Energy). The US\$ 6 million well reached TD at 11,745' in

mid-February 2011. The well encountered gas shows in a shallower 130' Lower Silurian section and over a deeper 300' Lower Silurian hot shale section. The well appears to have been drilled on a localised paleo-topographic high which accounts for the absence of a Cambro-Ordovician section. The strongest shows were recorded in the deeper Lower Silurian interval (124 scf/ton), while the shallower interval averaged 77 scf/ton. Wytowno S-1 was followed by a 11,780' well, Lebork S-1, on the Slupsk concession which encountered gas shows over a 935' interval from Lower Silurian to Cambrian Alum Shale. The Lower Silurian averaged 40 scf/ton while the 155' Cambro-Ordovician interval averaged 268 scf/ton. Total Organic Carbon (TOC) is also significantly higher in the Cambro-Ordovician interval.

In July 2011 Saponis spudded a third well, Starogard S-1 which had reached a TD of 11,560' by early September. The well encountered a similar Lower Silurian to Cambrian section to that of Lebork S-1 with a gross thickness of some 820'. Gas contents (Lower Silurian: 38 scf/ton; Ordovician: 17 scf/ton) were lower than in the first two wells. Completion of the first two wells commenced in mid-September 2011 with fracking of the Cambrian interval in Lebork S-1 commencing on 30th September. The fracturing of the Cambrian and Ordovician intervals did not permit an effective test to take place as insufficient proppant was injected as a result of higher than expected overpressures. The gas that did flow and was flared contained methane, ethane and propane. The shale character in the three Saponis wells is indicated in Table 3 below.

Location	Play	Age	Thickness Range (ft)	SiO ₂ %	Carbonate %	Clay %	Porosity %	Total Organic Carbon %
Saponis Concessions, Baltic Depression	Graptolitic Shale	Lower Silurian	300 - 485	28 - 30	8 - 27	44 - 50	1 - 9.6 (avg 3.8)	0.1 - 4.2
	Graptolitic Shale	Ordovician	75 - 90	32 - 54	8 - 18	33 - 43	1.4 - 6.9 (avg 4.2)	0.05 - 6
	Alum Shale	Upper Cambrian	45	25	30	39	4.1 - 5.2 (avg 4.6)	5.0 - 9.2 (avg 7.2)

Table 3. Shale Character in Saponis Wells, Baltic Depression

In April 2012, gas in place in the Saponis concessions was estimated to lie within the range 45.4 to 66.8 Tcf with a best estimate of 55.5 Tcf. Prospective recoverable resources were estimated in the range 4.5 to 13.2 Tcf with a best estimate of 8.0 Tcf. In December 2013, BNK Petroleum and Esrey Energy (formerly LNG Energy) acquired the Saponis interests of RAG and Sorgenia. It was also announced that Saponis will relinquish the Starogard and Slawno concessions, retaining the Slupsk concession on which Lebork-S1 was drilled.

BNK Petroleum – Indiana Investments. BNK announced that it would commence the drilling of three wells on its wholly-owned blocks to the south of the Saponis Slawno and Slupsk concessions in February 2012 and on 28th February spudded Miszewo T-1 in the Trzebielino concession. The well drilled to a TD of ~ 17,700' but only muted gas shows were recorded. The well appears to have been drilled on the downthrown side of a major fault and to have encountered a different depositional environment from wells further to the northeast.

Gapowo B-1 was then spudded in May 2012 in the Bytow concession. It lies on the upthrown side of the fault and was drilled to a TD of some 14,000'. The well encountered a 400' Lower Silurian interval and 155' Ordovician interval, both overpressured. Core data suggest that prospective shale is 130' to 250' in thickness and has higher porosity (3.9 – 6.1%; 5.1% avg.), permeability and TOC (1.1 – 4.2%; 2.5% avg.) than any of the other BNK-operated wells in the Baltic Depression. The average gas readings from these fractured overpressured shales were over 20 times greater than those encountered in Lebork S-1. Gas in place for the most prospective Lower Silurian / Ordovician interval is estimated at up to 86 Bcf / section with total gas in place for the well estimated at up to 135 Bcf. Permission to drill and fracture stimulate a horizontal leg was obtained and a 5,900' horizontal

section was drilled and cased in January / February 2014. A fracture stimulation over 30% of the hole length is planned for Q4 2014.

San Leon. San Leon / Talisman commenced a two vertical well Gdansk Depression drilling programme with the spudding of the Lewino-1G2 well in the Gdansk-W concession in late September 2011. Strong gas shows were encountered over an interval in excess of 3,300' ranging from Middle Silurian to Upper Cambrian. After reaching a TD of 11,810' the rig moved to the Rogity-1 location on the Braniewo concession. This well drilled to 9,147', encountering shows of rich gas over a 1,600' interval from Lower Silurian to Middle Cambrian. Oil shows were also recorded in Lower Silurian shale, Ordovician limestone and shale and Middle Cambrian sandstone. Following Talisman's announcement of its withdrawal from its Polish Operations, on 8th May 2013 San Leon reported that it had assumed 100% ownership of the Gdansk West and Braniewo concessions through its acquisition of the shares of Talisman Energy Polska. San Leon has announced a proposed pilot development programme for the Gdansk West concession. The concession appears to fall within the gas/condensate window and the pilot area of 183 km² (70 square miles) is estimated to contain 1.3 Tcf and 40 million bbl of condensate recoverable. The entire Gdansk West concession has an estimated 12 – 18 Tcf shale gas in place.

On 2nd July 2013, United Oilfield Services (UOS) performed a hydraulic fracture through the 5 ½" liner of Lewino-1G2, pumping over 11,000 barrels of fluid and 95 tons of sand at 120 barrels / minute with a maximum pressure of 12,200psi. The frac was conducted between 11,632' and 11,647' in the Upper Ordovician (Caradoc) Sasino Formation. 25% of frac fluid was recovered along with a small but consistent flow of burnable gas. UOS performed 2 further fracs in Q4 2013. The first was a refrac of the initial interval but using ceramic proppant. The second frac was conducted in a higher part of the Sasino Formation using a slickwater design and flowed gas throughout the duration of the clean-up period (one week). In January 2014, after 6 weeks flow, the well was producing 45-60 Mscf/d (cond / gas: 20bbl / MMscf). Flow is believed to have been from the upper fractured interval only (frac 3) with total Upper Ordovician potential for 200-400 Mscf/d. A 5,000' horizontal well is now planned from the same well pad. San Leon / Hutton had planned to drill a vertical well on the South Prabuty concession in 2013 but this has not taken place.

PGNiG (Polskie Górnictwo Naftowe i Gazownictwo – state-controlled). A promising gas flow was also reported by PGNiG from a single-stage frac test of the Silurian / Ordovician at 9,500' on its Lubocino-1 well on the Wejherowo concession, completed in March 2011. Gas quality was good with heavier hydrocarbons reported, no H₂S and low N₂. A second test was subsequently conducted at 9,200'. A horizontal well (Lubocino-2H) was spudded in August 2012. After hydraulic fracturing, testing was continuing in Q2 2013. The company drilled Lubocino-3H between August and December 2013. PGNiG has also drilled a vertical well, Opalino-2, in the Wejherowo concession. The well, which was spudded in September 2012, with a targeted depth of 10,000', was reported to be production testing in July 2013. Gas flows were reported from the Cambrian at around 10,000'. Wells Opalino-3 and 4 were drilled between November 2013 and March 2014 and PGNiG has indicated that it may start production from the Opalino area in 2015. In conjunction with a consortium of Polish companies (KGHM; PGE; Tauron Polska Energia; Enea), PGNiG also drilled Kochanowo-1 on the Wejherowo concession between April and July 2013. Between March and May the company drilled Wysin-1, its first well on the Stara Kiszewa concession, some 20 miles southeast of Gdansk. Borcz-1 was drilled on the Kartuzy-Szemud concession in the period July – September 2013.

Eni. Eni completed an initial 3 vertical well programme on its Malbork (Kamionka-1) and Elblag (Bagart-1; Stare Miasto-1) concessions. A horizontal leg was drilled on one of the wells and frac testing commenced in the second half of 2012. Eni is reported to be withdrawing from Polish

shale gas exploration and did not renew two of its three licences when they expired in December 2013 and January 2014. The third licence is valid until June 2018.

Danish-Polish Marginal Trough & East European Platform Margin.

There are 37 currently valid (1 March 2014) concessions covering the Platform Margin and Marginal Trough, the most prominent participants being Chevron, Marathon, Polish state company PGNiG, and PKN Orlen, another Polish company. Marathon has announced that it intends to dispose of its Polish assets as part of its global portfolio management programme.

ExxonMobil. The first wells in the Podlasie Depression of the East European Platform Margin (Siennica-1) and Lublin Trough of the Danish-Polish Marginal Trough (Krupe-1), were drilled by ExxonMobil in Q4-2010 and Q1-2011. The wells were fraced in September / October 2011 but the wells failed to flow commercial volumes of gas. In June 2012 it was reported in the Polish press that ExxonMobil will discontinue its Polish shale gas exploration operations. The company had the option to relinquish or transfer its six concessions. Total SA, partner in two of them, announced in October 2012 that it will become operator of one of the concessions and drill a further well, while relinquishing the other. Of the other four concessions, two were relinquished and two transferred to PKN Orlen.

PKN Orlen. On 24th October 2011 PKN Orlen commenced its drilling programme in the Lublin Trough of the Danish-Polish Marginal Trough spudding its first well, Syczyn-OU1 in the Wierzbica concession. Based on the results of this vertical well Syczyn-OU2K was spudded in September 2012, with a planned horizontal leg of some 3,600'. A 12-stage fracture operation and four-week production test was conducted in Q2 2013 but did not yield commercial flow rates. Two other wells were completed in the Wierzbica concession in April (Stręczyn-OU1) and September 2013 (Dobryniów-OU1). In mid-December 2011, PKN Orlen spudded Berejow-OU1 in the Lubartów concession, followed later that month by the Berejow-OU2K horizontal well. Both wells have now been completed and the horizontal well was frac tested in November / December 2013 using 19,000 cubic metres (5 million U.S. gallons) of water & 160 tons sand. Seven frac stages were conducted over a horizontal length of 2,300' at a depth of 8,200'. Between May and July 2013, Uscimów-OU1 was also drilled in the Lubartów concession. In July 2012, Orlen spudded Goździk-OU1 in the Garwolin concession, drilling to a TD of 13,830'.

Location	Play	Age	Thickness (ft)	SiO ₂ %	Carbonate %	Clay %	Effective Porosity %	Total Organic Carbon %
PKN Orlen, Lublin Trough	Lublin Shale	Lower Silurian	200	16 - 33	10 - 30	40 - 56	4.7 max	0.8 - 3.5

Table 4. Silurian Shale Character in Lublin Trough Wells

On the East European Platform Margin PKN Orlen drilled the Stoczek-OU1 vertical well to a depth of 10,300' on the Wodynie-Lukow concession between November 2013 and January 2014. This was immediately followed by the Stoczek-OU1K horizontal well with a measured depth of 14,130', drilled at a depth of 9,500' in the Silurian. The planned length of the horizontal leg was 3,600'.

Chevron. Chevron also commenced its Lublin Trough programme in Q4-2011 with a well in the Grabowiec concession at Lesniowice, spudded on 31st October 2011. A second well at Andrzejow on the Frampol concession was spudded in March 2012. A third well was spudded on the Zwierzyniec concession in December 2012. Krasnik-1 was then drilled on the Krasnik concession between May and August 2013. The company has now drilled a Lower Silurian test on each of its

four Lublin Trough concessions. Zwierzyniec is apparently the most promising as the first well was fraced and a second well is planned. Further development work on the Grabowiec concession, where Chevron conducted a DFIT in Grabowiec-6, has been delayed by protests by local villagers at Żurawłów.

Marathon / Nexen / Mitsui. In Q4-2011 and Q1-2012 Marathon drilled Cycow-1 (Orzechow concession) and Domanice-1 (Siedlce concession) on the East European Platform Margin. The latter well was plugged and abandoned. Drilling activity then moved to the Danish-Polish Marginal Trough where Lutocin-1 (Rypin concession) and Prabuty-1 (Kwidzyn concession) were drilled in the Pommeranian Trough, followed by Lubawskie-1 (Brodnica concession), spudded in September 2012. The final well in the initial 6-well programme, SOK-Grębków-1 in the Sokolow Podlaski concession in the Podlasie Depression, East European Platform Margin, was plugged and abandoned in January 2013. Diagnostic fracture injection tests (DFITs) were conducted in the four non-abandoned wells. Three wells were hydraulically fractured using hybrid slickwater/gel fracs, with one well flowing gas for a week. Marathon has announced that it intends to dispose of its Polish assets as part of its global portfolio management and relinquished 7 of its 11 concessions in October / November 2013. Nexen (40%) and Mitsui (9%) have an interest in the remaining 4 concessions.

San Leon. San Leon / Talisman spudded Szymkowo-1, the final well in their 3-well drilling program, on the Szczawno concession, Danish-Polish Marginal Trough (Pomeranian Trough), in early March 2012. The well drilled to a depth of 14,930' and recorded wet gas shows over some 2,000' of Lower Paleozoic shale. The strongest shows were encountered in the Lower Silurian and Ordovician over a combined thickness of some 350'. San Leon has reported that a 1,650' horizontal leg was drilled in this well. Following Talisman's withdrawal from Poland, San Leon is now operator and now owns 50% of the concession, the other 50% being held by Greenpark Energy.

PGNiG. PGNiG spudded the Lubycza Królewska-1 well on the Tomaszów Lubelski concession, Lublin Trough on 26th March 2012. The well was completed in August 2012 and may be frac tested. Also in the Lublin Trough, Kościaszyn-1 (Wiszniow-Tarnoszy concession) and Wojcieszków-1 (Kock-Tarkawica concession) were drilled between September 2013 and January 2014.

Dart Energy. Dart Energy has published a "best estimate" of 9.485 Tcf shale gas in place in its Milejow concession, where a seismic programme was carried out in Q3-2011. Dart considered its Polish assets to be non-core and relinquished the concession in October 2013.

Poland General. An interesting feature revealed by sampling and gas shows from the three Lane Energy, three Saponis and two San Leon / Talisman well locations in the Gdansk Depression is that thermal maturity appears to decrease in an east to northeast direction leading to an increase in the content of NGLs. The Starogard well produced hydrocarbons up to pentane and Rogity-1 produced C1 – nC8 while the western wells in general produced only methane, ethane and propane. This does suggest that there is the potential for significant liquids production from some concessions. Rogity-1 also discovered a 30' oil column in tight Middle Cambrian sandstone, confirming the decrease in thermal maturity towards the northeast of the Gdansk Depression. The earliest deposition of organic-rich shales is diachronous from northwest to southeast. Only to the northwest of Gdansk (Łeba High) are the Upper Cambrian Alum Shale (Piasnica Formation) and Lower Ordovician Sluchowo Formation organic rich. Organic-rich shales also occur in the Łeba High region from Middle Ordovician (Llandeilian) through to Lower Silurian (Llandovery). Elsewhere, organic-rich Upper Ordovician shale occurs only to the southeast of the Łeba High in the central part of the Gdansk Depression. Organic-rich Silurian shale occurs throughout the region though once again this is diachronous, with only the Llandovery tending to be organic rich in the northwest while further to the south and east in the eastern part of the Gdansk Depression, the Podlasie Depression and the Lublin Trough, both the Llandovery and Wenlock contain organic-rich shales. The Polish Treasury Ministry is said to be targeting commercial production from at least one pad by late 2014 or early 2015. It is assumed that the initial production of 20 – 30 million cf/d will come from the Lower Paleozoic play.

Lithuania: The Cambrian to Lower Silurian succession is also thought to have potential in south-west Lithuania. The Lithuanian Geological Survey has estimated in-place shale gas resources at up to 20 Tcf, with 10-15% recoverable.

Chevron. Chevron plans 2D and 3D seismic and multiple wells primarily for shale gas / oil exploration (see 4.3 *Farm-ins: Lithuania*) on the Rietavas onshore licence. On 25th June 2012 the Lithuanian Geological Survey opened two areas to tender for exploration with a submission deadline of 31st October 2012. In January 2013 it was announced that Chevron was the only applicant. Award of the application was delayed until Parliament amended laws to strengthen environmental regulations and on 16th September Chevron was announced winner of the tender but on 8th October Chevron announced that it was withdrawing from the tender. It is understood that this was because changes in the legal and financial environment covering hydrocarbon exploration had been and will continue to be made since the date Chevron was granted the award. On 29th October 2013, the Environment Ministry announced that a repeat tender will be announced, possibly in Q1 2014 if all legal and tax changes have been determined. Terms will be eased, especially in the area of experience which was extremely stringent in the initial tender. Chevron continues to hold a 50% interest in LL Investicijos, holder of the Rietavas licence.

Romania:

Chevron. Chevron has acquired a concession (Block EV-2 Barlad) on the platform margin in northeast Romania where the Silurian foredeep shales that are prospective in Poland and Ukraine are also believed to occur at depths between 10,000 and 13,000'. Chevron has committed to 400 km of 2D seismic and 3 wells. Prior to the introduction of a shale gas drilling moratorium, the first well in the multi-well drilling programme had been planned for late 2012. Following the expiry of the moratorium, Chevron moved ahead with seismic exploration and the permitting required for drilling. Having obtained all the required permits, in early October 2013 Chevron commenced preparatory work at the drill site near the village of Silistea in Vaslui County but halted operations after five days of protests by villagers. On 19th October 1,700 locals and environmental activists held protests. The government, while accepting the right to peaceful protest, has warned against violence. President Traian Basescu has appeared on TV to stress that failure to source indigenous gas resources plays into the hands of Russia's Gazprom while Prime Minister Victor Ponta has stated that the government's desire and political decision is to have energy independence for Romania by exploiting all of the resources that the country has. Chevron currently plans the first well on the Barlad concession in Q2 2014. A second Lower Paleozoic play occurs on the composite Saxothuringian-Barrandian-Moldanubian terranes (Bohemia) that probably detached from Gondwana at around the time of the Ordovician-Silurian boundary.

Czech Republic:

Hutton Energy. BasGas (now Hutton Energy) has applied for acreage in the Prague and Intra-Sudetic basins of the composite Bohemian terranes. The Silurian pelagic shale is reported to be the target in both basins. The Trutnov application in the Intra-Sudetic Basin was approved on 21st December 2011 but the Trutnov award was cancelled in April 2012 and sent back to the Ministry of Environment regional department to be decided again. In September 2012 the Minister of Environment announced a moratorium on shale gas exploration in the Czech Republic until 30th June 2014.

Spain: Silurian black shale has also been identified as a potential play in Spain's Ebro Basin (by San Leon) and in central Spain.

2.1.2 Carboniferous

The second major play is a Carboniferous basinal marine shale play that extends eastwards from western Ireland and includes the East Irish Sea / Cheshire Basin in northwest England, the Anglo-Dutch Basin, the Northwest German Basin, the Fore-Sudetic Monocline (Northeast German-Polish Basin) in southwest Poland, and the Culm Basin in eastern Czech Republic. The age of the most prospective shales appears to young westwards from the Visean (Middle Mississippian) Kulm facies of Poland, the Czech Republic and northeast Germany to the Namurian (Upper Mississippian to Lower Pennsylvanian) of northwest Germany, the Epen Formation of the Netherlands, the Bowland Shale in northwest England, the Black Metals Marine Band of the Midland Valley Scotland, and the Clare Shale in western Ireland. Visean (Middle Mississippian) shale may also be prospective in Scotland and northwest Ireland. Tests of the Namurian Black Metals Marine Band in the Midland Valley of Scotland by three wells drilled in 2005 and 2007 were the earliest investigations of shale gas potential in Europe. The Carboniferous play has since been drilled in England, Wales and Poland.

Czech Republic:

Cuadrilla Resources. Cuadrilla Resources has received preliminary notification of the award of the Mezerici licence in which the target is considered to be deep marine sediments present in the Lower Carboniferous of the Culm Basin, where the Variscan foreland basin reaches its most easterly extent on the eastern flank of the Bohemian Massif. In September 2012 the Minister of Environment announced a moratorium on shale gas exploration in the Czech Republic until 30th June 2014.

Germany: The nature of German E&P reporting is such that it can be difficult to establish the activity taking place on long-held licences. It is assumed that ExxonMobil, both directly and indirectly through the BEB ExxonMobil / Shell joint venture, will be examining the potential of Visean (Middle Mississippian) shale in eastern Germany and Namurian (Upper Mississippian to Lower Pennsylvanian) shale in the west. Some of BNK Petroleum's initial eight concessions were also targeting Carboniferous shale gas, as are Wintershall's Rhineland and Ruhr concessions and Dart Energy's Saxon I West and Saxon II concessions. Dart reports combined shale gas in-place estimates for the two concessions in the range 0.25 – 2.95 Tcf with a best estimate of 0.97 Tcf. As part of its restructuring, Dart is looking to joint-venture, farm out or sell its German assets. BNK has announced that it intends to relinquish five of its eight German concessions, retaining the three concessions (Adler; Falke; Falke South) in North Rhine – Westphalia's Munsterland Basin, which appear to have primarily Carboniferous potential.

Ireland (Republic of Ireland & Northern Ireland).

Enegi Oil. In February 2011 Enegi Oil was awarded Licensing Option ON11/1 to evaluate the shale gas potential of the Namurian (Upper Mississippian – Lower Pennsylvanian) Clare Shale in western Ireland. The Clare Shale is known to have high TOC (3-8%) but also high levels of thermal maturity. The main issues are whether it is over-mature for gas and gas leakage during Late Carboniferous uplift. In September 2012 Enegi stated that vitrinite reflectance analysis indicates that the shale is of lower maturity than recorded in the literature and that it had engaged Fugro to undertake further testing of the prospectivity. The report submitted to the Irish Petroleum Affairs Division (PAD) in November 2012 indicated that within the area of seismic coverage and assuming a porosity of 7%, gas in place is estimated at 3.62 Tcf. The in-place estimate for the entire option area is 13.05 Tcf and for the high-grade area it is 1.23 Tcf. Having completed the work programme, Enegi Oil announced on 21st February 2013 that it had applied to the PAD for an Exploration Licence. The final award decision is subject to further research being conducted by the Environmental Protection Agency.

Tamboran Resources. In the Northwest Ireland Carboniferous Basin (Lough Allen Basin), which straddles the border between the Irish Republic and Northern Ireland, Tamboran Resources and the Lough Allen Natural Gas Co. have taken out licences on both sides of the border to evaluate the potential of the Visean (Middle Mississippian) Bundoran and Benbulbin shales, both of which yielded strong gas shows in wells drilled in the mid-1980s. TOCs are lower than in Clare (<2%).

Netherlands:

Cuadrilla Resources. Cuadrilla Resources has been awarded a licence (Noord Brabant) on the margin of the London-Brabant High and West Netherlands Sub-basin of the Anglo-Dutch Basin. It is assumed that the Namurian (Upper Mississippian to Lower Pennsylvanian) Geverik Member of the Epen Formation shale is one of the targets in this location. Two wells, at Boxtel and Haaren, are planned. It is also possible that one of these wells may be targeting shale oil in the Lower Jurassic Aalburg and Posidonia formations in the Roer Valley Graben while another also targets tight gas in the Triassic. Cuadrilla's other Netherlands licence (Noordoostpolder) in the Northwest German Basin is a Namurian gas shale play. Drilling of the first well (Boxtel) is unlikely to take place before 2015 as a result of permitting delays and the need to await the outcome of studies commissioned by the Dutch Ministry of Economic Affairs, Innovation and Agriculture on the risks associated with unconventional gas drilling and production. The first study, which was delivered on 27th August 2013, concluded that risks remained very small and is being followed by a 12-18 month study to identify preferred locations for shale gas exploration.

Poland: A total of 21 concessions considered to have shale gas potential have been awarded in the Fore-Sudetic Monocline in southwest Poland but four (4) have subsequently been relinquished (Lane Energy – 3; San Leon – 1). Lane Energy withdrew from the area to focus on its Baltic Basin concessions. San Leon remains the largest concession holder with 9 concessions covering this play. Other operators include Petrolinvest S.A. (through Silurian Sp. and ECO Energy), PGNiG, PKN Orlen and Canadian International Oil Corp. Although all 17 remaining Fore-Sudetic Monocline concessions are considered to have some shale gas prospectivity, some are also being investigated for their conventional oil and gas prospects.

PGNiG. On behalf of the Polish state company, PGNiG, Halliburton frac tested Upper Carboniferous shale in Markowola-1 in the Lublin Trough in July 2010 but the flow rates are said to have been lower than expected.

San Leon. The next test of the Carboniferous, Siciny-2, was spudded on 10th November 2011 by San Leon in the Gora concession, Fore-Sudetic Monocline. This well was located close to Siciny 1G-1, drilled in the 1970s, which had encountered a 3,266' Carboniferous section and was still in Carboniferous at TD. Siciny-2 was drilled to a depth of 11,550', encountering some 3,300' of Carboniferous. Continuous gas shows were encountered across three prospective shale intervals and two tight sandstone intervals encountered below 9,400'. In the first instance, testing will focus on the deeper of the tight sandstone intervals. The three highly-fractured shale intervals in Siciny-2 lie between 6,775' and 8,560' with a gross thickness of 1,400'. TOC values range from 1.2 - 3.25% and vitrinite maturity between 1.2 and 1.5%. Porosities are in the range 1.4 – 8.5% and average permeability is between 80 – 100 nD. Silica content is about 45%. Further prospective shale intervals are expected beneath the deeper of the two tight sandstones in which drilling terminated. Shale gas in place is estimated at up to 70 Bcf/ section. San Leon's estimate 61 Tcf of net risked recoverable tight gas and shale gas across its 13 concessions in the Fore-Sudetic Monocline. In March 2013 San Leon signed a Memorandum of Understanding with Halliburton to jointly explore and develop the Carboniferous and deeper in three of these concessions (Wschowa; Gora; Rawicz). Halliburton perform 3 DFITs on the tight gas sand in Siciny-2 between May and August 2013. These will be followed by a hydraulic fracture treatment. Subject to the execution of a further binding agreement, completion of the DFIT and hydraulic fracturing phase shall give Halliburton the option to earn up to

a 25% working interest in the Carboniferous and deeper sections within the Concessions by fully funding two vertical exploration wells, including full technical evaluation with core, DFIT, and vertical hydraulic fracturing if technically warranted.

United Kingdom:

England: In central England Viséan-Lower Namurian (Middle to Upper Mississippian) organic-rich deep-water marine shales of the Craven Group were deposited in a complex set of tectonically active grabens and half-grabens (“troughs”) which developed as a result of N-S tension during the onset of subduction in the Variscan Foreland Belt to the south. Laterally, on horsts and tilt-block highs, the shales grade into shelf limestones and deltaic sandstones but in the depocentres hemipelagic marine shales and interbedded mass flow deposits may be as much as 16,000’ thick.

Rifting ceased in the late Viséan but subsidence continued in the Namurian. A number of phases of Late Carboniferous uplift associated with the Variscan orogeny brought about basin inversion, and a complex set of hydrocarbon maturity conditions. The primary target has been informally named the Bowland-Hodder unit by the British Geological Survey, and comprises the Bowland Shale, Hodder Mudstone, Edale Shales, Holywell Shales and other local unit names. The unit has been subdivided into a thick lower syn-rift unit (Lower Bowland Shale; Hodder Mudstone) and thinner upper post-rift basin infill unit (Upper Bowland Shale). The lower unit is known to reach thicknesses of up to 11,500’ in depocentres and may be thicker. The upper unit transgressed across the highs and platforms but is considerably thicker and more organic rich within the basins. It is typically about 500’ thick but reaches up to 2,900’. Depths to the top of the Bowland-Hodder unit range from zero to 16,000’. Depth to gas maturity ($R_o > 1.1\%$) is estimated at about 9,500’ but will be less where there has been subsequent basin inversion and uplift. TOC ranges from 0.2 – 8% but normally falls within the range 1-3%. For reasons of sample availability, most of these values come from the upper unit. Present-day kerogen is dominated by mixed type II-III and type III but may have been modified by maturation. The most prospective areas are considered to be the Bowland Basin, Edale Gulf, Gainsborough Trough and Cleveland Basin.

Cuadrilla Resources. Cuadrilla Resources, through its Bowland Resources subsidiary, has interests in the onshore portion (Bowland Basin) of the East Irish Sea Basin in PEDL 165 in Lancashire, northwest England. Spudded on 16th August 2010, the company’s Preese Hall-1 well targeted a Viséan-Namurian (Middle to Upper Mississippian) interval with the Bowland Shale the primary target. Drilled to a depth of 9,098’, the vertical well encountered over 4,000’ of shale between 4,400’ and 9,004’. The shales contained both vertical and horizontal fractures and produced “substantial gas flows”. The well encountered three prospective shale formations with a net thickness of 2,411’: Sabden Shale of Arnsbergian (Late Mississippian) age (approximately 170’); Bowland Shale of Brigantian (Middle to Late Mississippian) age (1,685’); Hodder Mudstone of Viséan (Middle Mississippian) age (554’). The well was due to have a 12 frac-stage completion over an interval from 5,260’ to 9,000’ but after 5 fracs, fracking was suspended due to two small earthquakes in the vicinity of the well (2.3 and 1.5 Richter Local Magnitude). The company commissioned a study to determine the relationship, if any, between the fluid injection and seismicity (see 5. *Above-ground issues: United Kingdom*). The first three fracs (perforated intervals from 8,420’ – 8,949’ in the Hodder Mudstone) were tested on comingled flow and produced satisfactory amounts of gas and frac flow-back water. Fracs 4 and 5 (7,810’ – 8,259’ in the base of the Lower Bowland Shale) were being flowed in mid August 2011. In December 2013, Cuadrilla announced that no further exploration work will take place on the Preese Hall site. Between January and August 2011 the rig drilled a second well 3 km NE of Preese Hall-1 at Grange Hill-1, where top Lower Bowland Shale was forecast at ~ 6,500’, slightly shallower than in Preese Hall-1. Preliminary core analyses suggest similar gas contents to Preese Hall-1 but over a thicker series of possible pay zones, as indicated by the final TD of 10,775’ compared with the forecast TD of 9,500’. In July 2013, Cuadrilla announced that it intended to apply

for planning permission to hydraulically fracture and test the well but subsequently announced that it does not intend to frac the well at this time but rather to use it as an observation well for seismic monitoring of two new sites. Becconsall-1, 15 km south of Preese Hall-1, spudded on 16th August 2011 and represented a substantial step-out from the locations of the first two wells.. Top Lower Bowland Shale was forecast at ~ 8,000', significantly deeper than in the previous two wells. On 13th October a vertical sidetrack, 1Z, was spudded and the well was completed on 21st December 2011. No results have been announced other than the TD of 10,500'. Cuadrilla plans a DFIT on this well.

On 6th October 2012, drilling commenced on a fourth well (Anna's Road-1), some 5 km southwest of the Preese Hall-1 location. Top Bowland Shale was estimated at 9,000' and TD at 11,500'. On 16th November, however, it was reported that the well had been abandoned at 2,000' because of a stuck packer. Plans to respud the well in January 2013 were subsequently altered to allow the company to modify its planning application to include the vertical well, a 3,000' horizontal leg, hydraulic fracturing and flow testing. Cuadrilla subsequently decided to abandon the Anna's Road well and restore the site to its previous condition. On 4th February 2014, Cuadrilla announced that the company intends to apply for planning permission to drill, hydraulically fracture and flow test up to four exploration wells on each of two sites, one at Roseacre Wood, Roseacre, and the other at Preston New Road, Little Plumpton. Separate applications will also be made to install two seismic arrays that will be used to monitor the hydraulic fracturing process.

Because of the substantial thickness of the Bowland Shale in PEDL 165, shale character shows significant variation. The shale is thought to have undergone an early period of oil generation prior to Variscan (Late Carboniferous) uplift. The subsequent deposition of the Manchester Marl and anhydrite (Upper Permian) formed a regional seal. Peak maturity occurred during the Jurassic – Cretaceous and was followed by Alpine uplift. Total Organic Carbon (TOC) ranges from 1 – 6%, averaging 2 – 4%. Thermal maturity ranges from wet gas (C1 – C5) at the top of the shale to dry gas, with Ro range of 0.8 – 2.0% and Btu in the range 990 – 1,450. Porosity can range from 1 – 6% but gas-filled porosity is typically 4-5%. Silica / carbonate content is high with less than 50% clay, though the younger Sabden Shale, which is generally within the oil window, has higher clay content.

Based on gas desorption and geochemical studies undertaken at the Preese Hall well and a net shale thickness of 2,411' in that well, original gas in place at the Preese Hall location was estimated at 538.6 Bcf / square mile. On 22nd September 2011, Cuadrilla Resources announced a preliminary gas in place estimate of 200 Tcf for its 1,130 km² (436 square miles) PEDL 165 licence in Lancashire. The uncertified estimate was based on the two wells drilled at that time by Cuadrilla plus historical data from three wells drilled between 1987 and 1990 by British Gas. At the ShaleUK 2014 conference on 4th March 2014, Cuadrilla announced an increase in gas in place to 330 Tcf with potential for 100 Tcf recoverable.

IGas Energy. On 4th November 2011, IGas Energy spudded a joint coal seam gas / shale gas exploration well in the Carboniferous Rossendale Basin (beneath the Permo-Triassic Cheshire Basin) on PEDL 190 south of the River Mersey opposite Liverpool. The Ince Marshes-1 well was completed on 21st January 2012 having encountered about 1,000' of Bowland Shale in which gas indications were observed throughout. The well was still in shale at TD with total thickness estimates at ~ 1,650'. TOC generally fell in the range 1.2 – 3.7%, averaging 2.73%. Previous independent analysis suggested 4.6 Tcf gas in place in this area but on the basis of the well results IGas said that its potential in-place resource could be doubled to 9.2 Tcf. On 3rd June 2013, IGas reported that its in-house estimate of shale gas initially in place in its northwest England licences was 15.1 to 172.3 Tcf with a most likely in-place resource of 102 Tcf. In June 2012 IGas announced the beginning of a formal process to find a farm-in partner for its Cheshire shale gas prospect. On 15th January 2013, IGas announced a successful share placing, part of which is intended to fund a two-well shale gas appraisal programme intended to "augment value ahead of any farm-out". ExxonMobil was one of the companies rumoured to have been in discussions with IGas. On 10th January 2014 IGas spudded a second Rossendale Basin joint coal seam gas / shale gas exploration well at Irlam, west of

Manchester. Irlam-1 has a planned TD of 10,100' and is forecast to penetrate a 3,175' Bowland Shale sequence (with a further possible 300' cut out by faulting).

Dart Energy. Dart Energy has 11 licences in the Cheshire and Stafford basins. Netherlands Sewell & Associates (NSAI) has a best estimate of 30.5 Tcf original gas in place over six of these licences. The Bowland Shale may also be prospective east of the Pennine High in the East Midlands, Humber and Cleveland basins, where it is a known source rock for oil and gas. Since 2010 a complex set of acquisitions, farm-ins and ownership exchanges has taken place on licences PEDL 139 and 140 in the Gainsborough Trough, East Midlands Basin, reflecting the potential of this acreage. Of the original licencees, only Egdon Resources remains, with eCorp International, IGas, Dart Energy and, most recently, French major Total all acquiring interests. Total (40%) is the largest interest holder and IGas is the operator. Total will fund a work programme including the drilling of a vertical exploration well. Total has also taken an option to farm into the adjacent PEDL 209 operated by Egdon. Dart Energy bought into the Gainsborough Trough acreage through its acquisition of Greenpark Energy's unconventional gas assets (see 4.2 *Licence Acquisitions: United Kingdom*). Dart's (NSAI) best estimate of Original Gas in Place for 7 of its 13 licences east of the Pennines is 32.4 Tcf net to Dart (47.6 Tcf gross). The above estimates of net gas in place predate the GDF SUEZ farm in. A number of wells which have been drilled in Yorkshire to explore for conventional Permian and Carboniferous carbonate and sandstone reservoirs have also drilled through and sampled the Bowland Shale.

Rathlin Energy (UK). Between April and September 2013, Rathlin Energy (UK), a wholly owned subsidiary of Canada's Connaught Oil & Gas, drilled Crawberry Hill-1 and West Newton-1 in the Humber Basin, north of Hull, East Riding of Yorkshire. The wells were conventional exploration wells designed also to appraise the Bowland Shale. Planning permission for testing the two wells has been applied for. The applications are for flow tests of the Permian carbonate and Carboniferous (Lower Namurian) sandstone plus mini fall-off tests (DFITs) in the Upper Visean / Lower Namurian (presumed Bowland Shale) at 8,783' in Crawberry Hill-1 and 10,023' in West Newton-1.

Viking UK Gas. Between June and October 2013, Viking UK Gas, a wholly owned subsidiary of Third Energy, which in turn is 97% owned by a private equity arm of Barclays Bank, drilled Kirby Misperton-8 as a deep Bowland Shale appraisal well on the Kirby Misperton conventional field in the Cleveland Basin, North Yorkshire. The neighbouring Kirby Misperton-1 had encountered ~ 2,500' of Bowland Shale when drilled in 1985. Planning permission has also been obtained to investigate Carboniferous shale potential in southern England.

Coastal Oil & Gas. On PEDL 252 on the southern margin of the Wales – Brabant High near Woodnesborough in Kent (north of the Kent Coalfield), Coastal Oil & Gas has received planning permission for a well to take core samples of some 8 Westphalian (Middle Pennsylvanian) coal seams and the Lower Limestone Shales of the Tournasian (Lower Mississippian) Avon Group. It is not known when this well will be drilled.

Wales.

IGas Energy. IGas Energy has identified 1.14 Tcf of 2P contingent resources of gas in place in the Bowland Shale equivalent on its acreage in North Wales.

Coastal Oil & Gas. In South Wales Coastal Oil & Gas applied for permission to drill the Llandow gas shale exploration well to a depth of 2,130' to log and core the Namurian Millstone Grit Shale Group, the Dinantian Upper Limestone Series and Lower Limestone Series, and possible gas shale in the Ordovician, in addition to Devonian tight gas. Despite this well being drilled on the same basis as previous coal seam gas exploration wells drilled in the area by Coastal in 2007/8, the

company was obliged to withdraw the application in the face of local opposition to the drilling. When resubmitted the application was rejected by Vale of Glamorgan Council but has since been approved on appeal (see 5. *Above-ground issues: United Kingdom*). Although the principal shale gas target in the Llandow well appears to have been the Lower Limestone Shales of the Courceyan (Lower Mississippian) Avon Group, Coastal's partner, Eden Energy has identified the Namurian as the principal target over its acreage. The most prospective unit is presumed to be the Pendleian (basal Namurian or Upper Mississippian) Aberkenfig Formation. Eden has reported a gross unrisks P90 estimate of 34.2 Tcf shale-gas-in-place in the Namurian of its seven South Wales licences (17.1 Tcf net to Eden).

U.K. Methane. In August / September 2011, U.K. Methane (a company with similar management to Coastal Oil & Gas) spudded St Johns-1 and Banwen-1, targeting Namurian shale. The target depths are believed to be relatively shallow, about 2,000' in the case of St Johns-1.

Scotland.

Dart Energy. The basal Namurian (Upper Mississippian) Black Metals Marine Band in licence PEDL 133 in the Midland Valley of Scotland was cored by Composite Energy in Airth-6 (2005) and Longannet-1 and Bandeath-1 (2007). These were the earliest shale gas investigations in Europe. The Black Metals Member (Limestone Coal Formation) of the Kincardine Basin occurs at depths of 1,000' to 4,000'. The Black Metals was 120' thick in Airth-6 and the core analysis results are assumed to have been promising, as BG Group subsequently farmed into the licence. In June 2011, Australia's Dart Energy (formerly Composite Energy) announced the results of an independent assessment by NSAI of shale resources in PEDL 133, in the Midland Valley of Scotland. This indicates an estimated gas-in-place of 0.8 Tcf in the Black Metals Member, and a potential resource of 0.1 Tcf. The deeper Visean (Middle Mississippian) shales of the Lawmuir and Lower Limestone formations are estimated to contain 3.6 Tcf gas in place with a gross resource of 0.5 Tcf. Dart Energy owns 100% of the Namurian prospect but BG retains a 51% interest in the Visean prospect. Shale gas exploration of PEDL 133 is still at an early stage while the company focuses on the start-up of coal seam gas production from the licence.

2.1.3 Liassic (Lower Jurassic)

The third major regional play comprises Lower Jurassic bituminous shales that are being targeted in the Weald Basin (southern England), Paris Basin, the Netherlands, northern Germany and Switzerland's Molasse Basin. In continental Europe, the principal target is the Lower Toarcian Posidonia Shale. In eastern Germany and Poland the Lower Toarcian grades into a terrestrial facies and loses its source potential. In southern England the principal bituminous shales (Blue Lias; Black Ven Marls; Green Ammonite Beds) are older and occur in the Lower Lias. These bituminous shales are clearly oil-prone. The principal limitation regarding their shale gas potential therefore lies in finding locations in which they have been sufficiently deeply buried to have entered the gas window. Locations where this may have occurred include the flexural foreland basin of the Swiss Molasse and the Mesozoic depocentres of the Lower Saxony Sub-basin (Northwest German Basin) and the offshore Broad Fourteens Basin and Central Graben of the Netherlands.

A number of companies are thought to be investigating Lower Jurassic shale gas potential. These include Cuadrilla Resources in *England's* Weald Basin and Schuepbach Energy in *Switzerland's* Molasse Basin. Whether the Liassic shales will be within the gas window in the Weald Basin remains to be seen though it is possible that they may have generated biogenic gas at shallow depths. To date, the only known exploratory tests of the Lower Jurassic shale gas play have taken place in Germany where ExxonMobil drilled wells between 2008 and 2011.

France: Schuepbach Energy was awarded two permits in the Languedoc-Provence Basin where Total was awarded the Montélimar permit. The Lower Jurassic (Toarcian) Schistes Carton is considered to have potential in the area covered by all three permits. Both the Schuepbach and Total permits have since been cancelled (see 5. *Above-ground issues: France*) and Schuepbach is reported to have asked the French government for 1 billion Euros by way of compensation. A number of other companies have also applied for permits in Languedoc-Provence, many of them overlapping.

Germany:

ExxonMobil. The ExxonMobil / Shell co-venture (BEB) commenced shale gas exploratory drilling in 2008 in the Lower Saxony Basin, drilling Damme-2/2A in the Munsterland concession and Oppenwehe-1 in Minden. Schlahe-1 was drilled in 2009 in the Scholen concession. Posidonia Shale is known to have been at least one of the targets for these wells. ExxonMobil is believed to have spudded Lünne-1 (Bramschen concession, Emsland) around 17th January 2011 and reached the Posidonia Shale at about 4,720'. In March 2011, the Lünne-1A horizontal sidetrack was drilled in the Posidonia Shale to a total length of 760'. (The well was planned to have a 1,600' horizontal leg.) A frac test is planned but has not yet been applied for. The thickness of the Posidonia Shale ranged from 80' (Lünne-1) to 115' (Oppenwehe-1; Schlahe-1). ExxonMobil has also announced plans to drill and frac test a 3,300' horizontal leg (Z14b) at a depth of 3,380' within the Posidonia Shale from well Z14 in the Bahrenborstel Upper Permian Zechstein carbonate sour gas field. The Bahrenborstel Z14b sidetrack is one of a number of future horizontal shale gas exploratory wells planned by ExxonMobil in Lower Saxony, also including: Leese-Ost-1 and Ortland 26. No dates for drilling any of these wells are available at this time

BNK Petroleum. BNK Petroleum has announced that it intends to relinquish five of its eight German concessions, retaining only the three concessions (Adler; Falke; Falke South) in North Rhine – Westphalia's Munsterland Basin where the Posidonia Shale is a possible target.

San Leon. Realm Energy, a wholly-owned subsidiary of San Leon has a single concession (Aschen) in the Lower Saxony Basin where the Posidonia Shale is believed to be within the gas window.

2.1.4 Other plays with shale gas potential

Austria:

OMV. OMV has investigated the potential of the Upper Jurassic Mikulov Formation in the Deep Vienna Basin. The company estimates that the formation contains 200 – 300 Tcf of gas in place of which 15 Tcf may be recoverable. The target occurs at depths greater than 14,700' and a temperature of 160° C. Two initial wells had been planned near Herrnbaumgarten and Poysdorf in the Mistelbach District of Lower Austria at a combined cost of EUR 130 million. But subsequent proposed changes to Austrian environmental legislation mean that the project is no longer economically viable.

Bulgaria: The Lower to Middle Jurassic of the Moesian Platform, especially the basal Stefanetz Member of the Middle Jurassic Etropole Formation, is a target in northern Bulgaria, where Direct Petroleum (TransAtlantic Petroleum) has a licence and Chevron successfully applied for a licence which was subsequently revoked. Chevron has indicated that the Silurian was also a target in its Novi Pazar licence.

Transatlantic Petroleum / LNG Energy. Direct Petroleum / LNG Energy spudded the 10,500' Goljamo Peshtene R-11 well in the A-Lovech exploration licence in late September 2011. The well (TD 10,465') encountered 375' of net pay in the Etropole Formation with numerous gas shows in the C1 – C3 range. TransAtlantic has estimated the gross unrisks prospective undiscovered recoverable resource at 11 Tcf (best estimate). Operations in Bulgaria are constrained by the decision of the Bulgarian Parliament in January 2012 to ban hydraulic fracturing. Permission from the Bulgarian Government has not yet been received to resume completion and testing operations on the Peshtene R-11 well.

Croatia: Hungary's MOL and its part-owned subsidiary INA have indicated that the Miocene of the Mura and Drava sub-basins (Pannonian Basin) of eastern Croatia has shale gas potential.

France: Permo-Carboniferous basins in the Languedoc such as the Stephanian-Autunian (Upper Pennsylvanian – Lower Permian) Lodève Basin may have some potential in bituminous Autunian (Lower Permian) shale. Schuepbach Energy was awarded two permits in the Languedoc-Provence Basin, one of which also incorporated part of the Lodève Basin. The Schuepbach permits have since been cancelled (see 5. *Above-ground issues: France*) and Schuepbach is reported to have asked the French government for 1 billion Euros by way of compensation. Realm (San Leon) has identified Stephanian-Autunian potential in the Bresse-Valence Basin, where it has submitted an application. Elixir Petroleum is exploring for shale gas (and tight gas) in the Permo-Carboniferous of the Moselle concession in the eastern Paris Basin, where in the past at least two wells have produced gas to the surface from the target interval (probably Carboniferous). In the main Paris Basin many conflicting applications have been filed. While the main focus of these is probably Liassic shale oil, a number are presumably also targeting shale gas potential in underlying Permo-Carboniferous half-grabens.

Germany: The Upper Devonian Kellwasser shale has been touted as having potential in northern Germany, as have Wealden paper shales of Berriasian age in the Lower Saxony Sub-basin.

ExxonMobil. The ExxonMobil / Shell co-venture (BEB) commenced shale gas exploratory drilling in 2008 in the Lower Saxony Basin, drilling Damme-2 and 3 in the Munsterland concession and Oppenwehe-1 in Minden. Schlahe-1 was drilled in 2009 and Niedernwöhren-1 was spudded in the Schaumburg permit in October 2009. ExxonMobil is believed to have spudded Lünne-1 (Bramschen concession, Emsland) around 17th January 2011. The Wealden is known to have been at least one of the targets in all of these wells and Damme-3 and Niedernwöhren-1 targeted the Wealden exclusively. Damme-3 is known to have been frac tested (3 fracs). Wealden thickness ranges from 800' (Schlahe-1) to 2,300' in the Damme wells. Realm Energy (San Leon) also sees the Wealden as a potential target on its Aschen concession.

3Legs Resources. In the Bodensee Trough, north of the Swiss-German border, Parkyn Energy, another 3Legs Resources subsidiary, took out two licences in 2009 in which the principal prospect appears to be lacustrine shale of Permian age. The company acquired two-year extensions to these licences in December 2013 and then transferred its interest to Rose Petroleum in order to maximise its focus on its Baltic Basin concessions in Poland.

Hungary: The shale gas exploration situation in Hungary is unclear.

Falcon Oil & Gas. In September / October 2009, Falcon Oil & Gas / ExxonMobil / MOL tested an Upper Miocene basin-centred gas prospect in the Makó Trough (Pannonian Basin) with only limited success, after which ExxonMobil and MOL exited the project. But Falcon has suggested that its acreage holds a "potential fractured oil and gas play". Previously, in 2007, Falcon had tested a naturally fractured marl-rich section of the Upper Miocene Endröd Formation in Szekkutas-1. After

fracture treatment at about 11,100' the well flowed at an unstabilised rate of 1.577 million scf/d plus 50 to 100 ppm H₂S. RPS Energy (January 2013) estimated the 2C gas resources of the Lower Endröd at 1.11 Tcf but with the qualification that there is a less than or equal to 25% chance that the contingent resources will be converted to reserves.

MOL/INA. MOL and its part-owned subsidiary INA have indicated that the Miocene of the Mura and Drava sub-basins (Pannonian Basin) of eastern Croatia has shale gas potential and it can be assumed that this extends into western Hungary.

Delcuadra. In September 2009, Austria's RAG (Rohöl-Aufsuchungs Aktiengesellschaft) acquired Toreador Hungary Ltd. Toreador had just drilled the Balotaszallas-E-1 (Ba-E-1) well in the Kiskunhalas Trough of the Pannonian Basin. Ba-E-1 encountered an over-pressured 1,840' gross gas-bearing interval in an interbedded Karpatian (Lower Miocene) sequence of siltstone, shale and sandstone below 10,000'. The two lowest zones were fractured and are believed to have produced gas-condensate. At that time, the tested lithology was reported as tight sandstone (Shaoul et al., 2011). In July 2011, the Delcuadra Kft consortium (Delta Hydrocarbons 53%; RAG 25%; Cuadrilla 22%) recompleted an additional 3 zones of the Lower Miocene reservoir in Ba-E-1. At the Global Shale Gas Plays Forum in September 2011, RAG reported this as a shale gas frac and has subsequently confirmed that the completions were carried out in "a thick heterolithic sequence of shales and (very) fine clastics". Testing produced a gas flow rate of 1 million cf/d plus small amounts of condensate. Both are being sold and a long term production test commenced in August 2011 and full gas-condensate production should commence before end-2011. Cuadrilla has the option to earn a further interest by drilling and completing a second well in the Ba-IX Mining Block. This well, Ba-E-2, was planned for the second half of 2012.

Italy:

Independent Resources. A shale gas / coal seam gas combination play is being investigated by Independent Resources in the Ribolla Basin, Tuscany. Upper Miocene (Messinian) gas shale straddles a coal seam of up to 20' thickness over a distance of tens of kilometers along the basin axis. The play was discovered in the course of evaluating the results of the Fiume Bruna-1 & 2 coal seam gas exploration wells drilled in 2009-2010. Farm-out discussions with companies which have experience of analogous plays were undertaken but have not produced a suitable partner, in part, the company believes, due to the public opposition in Europe to unconventional gas exploration and exploitation. In-place and recoverable 2C contingent resources are estimated at 300 Bcf and 160 Bcf, respectively. New seismic is scheduled for late 2013 and any early development will probably be based on coal seam gas to avoid concerns about hydraulic fracturing.

Netherlands: The Upper Jurassic Kimmeridge Clay is sufficiently deeply buried in the Central Graben in the northern Netherlands offshore to have reached the gas window. In view of the high well cost and drilling density likely to be required, it seems unlikely that offshore shale gas development will be economic in the foreseeable future unless an existing platform and wells happen to be fortuitously located in an optimal location for shale gas development.

Romania: Chevron and Sterling Resources / TransAtlantic Petroleum have acquired a number of licences in the Moesian Platform of the East European margin in the south of the country, along the Bulgarian border. The targets are believed to be shale of Silurian to Lower Devonian age (Tandarei Formation) and Middle Jurassic age (Bals Formation). Sterling Resources / Transatlantic Petroleum are reprocessing existing 2D seismic to identify a drillable location and evaluate re-entering a legacy well on a Silurian prospect in Sud Craiova Block EIII-7.

Romgaz. State-controlled Romgaz says it has made an unconventional discovery, which includes shale gas in the Transylvanian Basin. It has been encountering gas in drilling since the mid 1990s. A moratorium was imposed on shale gas exploration in May 2012 but that has now been lifted. Chevron is proceeding with seismic exploration and acquiring the necessary authorisations for drilling.

Spain: Applications that are presumed to be for shale gas exploration have been submitted in the Basque-Cantabrian Basin (BNK; Realm Energy (San Leon)), Pyrenean Foothills (Cuadrilla Resources), Ebro Basin (Realm Energy (San Leon)) and the Campo de Gibraltar (Schuepbach Energy / Vancast). The focus of interest appears to be the Basque-Cantabrian Basin and the area of the Pyrenean Foothills immediately to the east. Trofagas Hidrocarburos (BNK) has been awarded three concessions in the basin, Realm (now San Leon, operating as Frontera Energy Corp.) has two awards plus two pending awards, Leni Oil & Gas has interests in four and while SHESA (owned by the Basque Energy Board, the regional government of the Basque Country) has interests in a substantial number of permits it seems to be focussing on the Enara permit. There does, however, appear to be a divergence of opinion regarding the most prospective targets. BNK, Leni and San Leon believe that the Jurassic is most prospective (especially the Lias) while SHESA is targeting Albian – Cenomanian shales. San Leon sees the Middle Albian – Lower Cenomanian Valmaseda Formation and Carboniferous shale as objectives in its Geminis licence on the Basque Country coast.

SHESA. SHESA and its partners, HEYCO Energy and True Oil, plan to drill two vertical wells, Enara 1 and 2, to evaluate the Albian – Cenomanian Valmaseda Formation where it estimates there are 200 Tcf in place.

BNK Petroleum. BNK has submitted five Environmental Impact Assessments on its Sedano and Urraca concessions as part of the exploratory drilling permitting process and plans to drill in Q1 2014, pending permitting.

San Leon. In the Ebro Basin, San Leon's six pending awards are primarily targeting organic-rich Paleozoic shales (Ordovician; Silurian; Carboniferous) but Eocene shale is also a target.

Switzerland:

Schuepbach. In addition to the Lower Jurassic Posidonia Shale, Schuepbach has also targeted the Aalenian (Middle Jurassic) Opalinuston in the Molasse Basin. It is understood, however, that the cantonal authorities in Fribourg would not renew the Fribourg licence when it expired at end-2011, over environmental concerns. Schuepbach still hopes to explore for shale gas in Canton Vaud, to the south of Fribourg.

United Kingdom: The Upper Jurassic Kimmeridge Clay has been proposed as a possible target in the Weald Basin, *England*, but there is considerable doubt that it will be mature for significant gas generation in this basin, although biogenic shale gas may be a possibility. Cuadrilla's interest in the Kimmeridge Clay is for shale oil rather than shale gas. If there is shale gas potential in the basin it seems more likely that it will come from older shales (Rhaetic or older). For example, Esso's 1963 Bolney 1 well is reported to have found a marine Middle Devonian interval within the gas window.

2.2 Some general gas resource play issues

Most plays are “statistical” in nature. Every coal unit and shale unit is “different” and also generally displays inhomogeneity. Statistical distributions can be obtained for parameters such as estimated ultimate recovery (EUR) and peak production from analogous wells. With a large enough sample size (number of wells) the geology of the play and the best drilling and completion strategies

can be understood sufficiently well to make performance of a play and its recoverable resources predictable. European exploration is still some considerable way from achieving these levels of understanding. To convert recoverable resources into reserves requires good technology: smart wells; fracture and stimulation; real-time micro-seismic mapping.

2. Shale liquids in Europe

The principal shale liquids (tight oil) target in Europe is the Liassic (Lower Jurassic) which is considered by many to be an analogue to the Bakken Formation of the Williston Basin. It is being investigated in France, Germany, The Netherlands and Portugal. The Upper Jurassic is understood to be a target in the south of the United Kingdom and central Poland, while a liquids-rich area has also been identified in the Polish Lower Paleozoic play.

France: There are four Liassic (Lower Jurassic) targets in the Paris Basin: Schistes Carton (Toarcian); Banc de Roc (Pliensbachian); Amaltheus Shale (Pliensbachian); Sinemurian-Hettangian Shale. The Liassic section is similar to the Bakken Formation in that the bituminous shales also contain a middle calcareous member (Banc de Roc). TOC ranges from 1 – 12%, averaging 6%, and thickness ranges from 30' to 230'.

Hess. Toreador Resources (now ZaZa Energy Corp.) investigated the fractured shale oil potential of the Liassic interval. Shows had previously been detected in 11 conventional exploration wells drilled from the 1950s onwards and 6 wells have produced oil on test. On 10th May 2010 Toreador signed an investment agreement with Hess Corp. whereby each partner would hold a 50% interest in Paris Basin unconventional oil exploration and production. In July 2012 ZaZa Energy transferred its remaining 50% interest to Hess (see 4.3 *Ownership Transactions: Farm-ins*). Toreador / Hess had planned to drill six wells in 2011, at least two of them horizontal, but as a result of the French government study into the economic, social and environmental impact of shale gas and shale oil drilling and the introduction of the resultant legislation, the programme was suspended. Hess had scheduled a three (3) vertical well drilling program for 2013 but it is unclear whether this will test the Liassic play.

San Leon. Realm Energy (now wholly-owned by San Leon), although focused on shale gas, has shale oil potential on the nine permits for which it has applied in the Paris Basin. San Leon estimates the potential of these licences at greater than 100 million boe. Realm had in the past indicated that the Toarcian Schistes Carton may also have shale oil potential within the area of its Blyes permit application in the Bresse-Valence Basin.

Vermilion Energy. In spring and autumn 2010 Vermilion Energy fracture tested two vertical wells in the Toarcian Schistes Carton, producing 32 - 38° oil from both wells. In February 2011 these wells were believed to be producing about 63 bbl/d. Vermilion had planned to drill another two vertical wells in 2011 to evaluate all four zones and to drill a horizontal well in 2012 based on 2011 results but it is understood that Vermilion has now suspended all Paris Basin shale oil evaluation activity. On 22nd September 2011, Vermillion withdrew three permit applications in the Paris Basin, possibly as a consequence on the ban on hydraulic fracturing introduced on 13th July 2011 (see 5. *Above-Ground Issues: France*).

Germany: Outcrop work by BNK Petroleum has identified samples of the Toarcian-age Posidonia Shale with thermal maturities ranging from below the oil window to within the gas window. It therefore seems probable that over some of BNK's acreage the Posidonia Shale will fall within the oil window and have potential for tight shale oil. BNK has announced that it intends to relinquish five of its eight German concessions, retaining only the three concessions (Adler; Falke; Falke South) in North Rhine – Westphalia's Munsterland Basin, where the Posidonia Shale is a possible target.

Hungary: Falcon Oil & Gas has indicated that the Upper Miocene Endröd Formation in the Makó Trough (Pannonian Basin) has shale oil potential. In 2007, Magyarcsanad-1 flowed 48° API oil and gas from natural fractures in argillaceous marl and siltstone of the Upper Endröd at 13,320'. The initial rate of 387 bo/d and 655 Mscf/d declined to 63 bo/d and 137 Mscf/d after 23 days. The well produced a total of 850 barrels of oil and 2 million cf gas intermittently between November 2009 and July 2012. RPS Energy (January 2013) estimated the 2C oil resources of the Upper Endröd at 76.71 million barrels but with the qualification that there is a less than or equal to 25% chance that the contingent resources will be converted to reserves.

Lithuania:

Minijos Nafta. In Mid-May 2012 local oil producer Minijos Nafta spudded a Cambrian sandstone oil exploration well, Skomantai-1, on its Gargzdai concession which was also intended to test the Ordovician and Silurian shales for unconventional hydrocarbons. Core samples were sent abroad for analysis of natural fractures, induced fracturing potential, porosity, permeability, source rock quality & maturity. In this location the Lower Paleozoic probably has shale liquids potential.

Netherlands: Cuadrilla Resources, in partnership with Dutch state company EBN, is targeting multiple unconventional hydrocarbon prospects on its Noord Brabant concession. The first well to be drilled (Boxtel-1) will evaluate the shale oil potential of the Posidonia Shale (Lower Toarcian) in the Roer Valley Graben at a depth of about 11,500'.

Poland:

Wisent Oil & Gas. Wisent Oil & Gas has four of the most easterly concessions in the Gdansk Depression, along the border with the Russian enclave of Kaliningrad, where Lukoil has been producing conventional oil for some time. As is noted above, these concessions appear to be situated in a more liquids-prone part of the basin (see 2.1.1 Lower Paleozoic: Poland). In addition to tight shale oil, Wisent expects there to be conventional prospects in Cambrian and Ordovician carbonates. Wisent drilled its first well, Rodele-1, on the Kętrzyn concession between February and March 2013 to a depth of 5,075'. The Silurian shale was found at the depth and thickness expected. The well was fraced in September 2013. Wisent spudded Babiak-1 on the Lidzbark Warmiński concession in March. The well drilled to a true measured depth of 9,160', including a 1,865' horizontal leg. The well was fraced in July 2013.

San Leon. Following Talisman's announcement of its withdrawal from its Polish Operations, on 8th May 2013 San Leon reported that it had assumed 100% ownership of the Gdansk West and Braniewo S concessions through its acquisition of the shares of Talisman Energy Polska. On 3rd July San Leon then announced an agreement whereby Wisent Oil & Gas could earn a 45% interest in the Braniewo S concession by conducting a three-stage fracture on the Rogity-1 well followed by drilling and testing a multi-stage horizontal well on the concession. The first Rogity-1 frac was completed in tight oil-bearing Middle Cambrian quartzitic sandstone on 4th August 2013. The fluid produced from the 9,055-9,070 interval indicated that the sandstone is in the vicinity of the oil-water contact in this location. The second (8,860-8,925' in Ordovician shale and marl) and third (8,630-8,710' in Lower Silurian Llandovery shale) frac stages were then tested comingled with the first, oil (39°) flowing to surface. Geochemical analysis indicated that oil different from Cambrian oil was recovered and that mobile oil had therefore been recovered from the shales. Wisent will now drill a vertical well, Rogity-2, either on the crest of the Rogity Cambrian structure or to the south of Rogity-1, where the Silurian shale is forecast to have higher TOC. Wisent will also undertake 3D seismic or additional drilling to compensate for the horizontal multi-fraced well originally envisaged.

Hutton Energy. In 2011, Hutton Energy's Polish subsidiary Strzelecki Energia acquired three concessions in the Mogilno-Łódź Trough of the Northeast German-Polish Basin in central Poland. In addition to conventional traps in Jurassic and Triassic sandstone, the company considers that the concessions have unconventional oil and gas potential in Jurassic shale, most probably of Middle Jurassic (Dogger) and Late Jurassic (Kimmeridgian) age. In February 2013, Hutton engaged Challenge Energy to find a partner to progress exploration activity on the three concessions. The prospectus indicated an upside of 100 million barrels of Jurassic shale oil potential.

Portugal: On 1st March 2012, Porto Energy Corp., holder of five licences on and offshore the Lusitanian Basin, announced that it had entered into a definitive joint venture agreement with Sorgenia International of the Netherlands and Austria's Rohöl-Aufsuchungs Aktiengesellschaft (RAG) to evaluate the unconventional resource potential of the Lower Jurassic (Liasic) basal Brenha Formation within Porto's concessions. The organic-rich Lias is the source of oil seeps along the coast and has historically been surface mined for bitumen. In September 2012 the company announced that it has received approval from the Portuguese oil and gas authority for its development and production plan for the Company's concessions onshore Portugal. The plan covers a period of five years during which Porto will execute a work programme focused on commercialising the Lias resource play in one or more areas within its concessions. In October 2012 Porto announced the conclusion of a 23-well stratigraphic drilling programme (Phase 1) to evaluate the unconventional resource potential of the Lower Jurassic (Lias) stratigraphic interval. The preliminary results demonstrated thicknesses and presence of organic-rich intervals consistent with pre-drill estimates and cores taken within the Lias interval showed higher than expected Total Organic Carbon. The farm-in partners had until December 31, 2012 to elect to proceed to Phase 2 activities as contemplated under the joint venture but on 5th April 2013 Porto announced that the partners had elected not to do so. Porto therefore expects to commence a farm-out process for its unconventional onshore Lias acreage.

United Kingdom: The Bowland Shale is an oil source rock in the East Midlands area of England and can be expected to lie within the oil mature zone at a number of locations. In the younger Namurian (Upper Mississippian – Lower Pennsylvanian) Millstone Grit Group in Lancashire, basal shales such as the 2,000' "Sabden Shale" (Samlesbury Fm) and the 230' "Caton Shale" (Silsden Fm) are believed to lie within the oil window in some locations. In southern England, the Upper Jurassic Kimmeridge Clay (thickness > 1,600'; TOC > 20%) and Lower Oxford Clay (thickness 300' maximum TOC 12%) and Blue Lias, Black Ven Marls and Green Ammonite Beds of the Lower Jurassic Lower Lias (thickness > 1,600'; maximum TOC 12%) have shale liquids potential.

Cuadrilla Resources. Cuadrilla Resources is investigating the shale oil potential of the Upper Jurassic Kimmeridge Clay in its Bolney project on PEDL 244 in the Weald Basin, southern England, where Esso found gas shows at shallow depth in Bolney-1 (1963). In April 2010 Cuadrilla received planning permission to drill the Lower Stumble test of the Kimmeridge Clay using the well pad of Balcombe-1, drilled by Conoco in 1986 on the Bolney (Lower Stumble) anticline. Top Kimmeridge Clay is estimated to occur at a depth of around 1,830' at this location and to lie within the relatively small sweet spot where the Kimmeridge Clay has reached oil maturity. Cuadrilla spudded Balcombe-2 on 2nd August 2013, drilling to a TD of 2,700' on 5th September, despite interruptions caused by protesters. The 1,700' Balcombe-2Z horizontal leg was then drilled within the Mid-Kimmeridge "T" Micrite at 2,500' and the well completed on 22nd September 2013. The well encountered hydrocarbons and has been suspended while Cuadrilla applies for planning permission for testing. The planning application excludes hydraulic fracturing and is being treated as a conventional well producing from natural fractures. In May 2011, AJ Lucas reported that Cuadrilla had fraced the Cowden 2 gas discovery well in the Weald Basin. The well was drilled by Independent Energy in August 1999 on a separate licence, EXL 189. The results were said to be inconclusive. It is not

known if this was a test of the well's shale oil or shale gas potential since an oil discovery, Lingfield-1, was also made within the EXL 189 licence area in 1999. AJ Lucas indicated that a further well would be drilled later but it is unclear whether this refers to the Lower Stumble shale oil test on PEDL 244 or a well on EXL 189.

Celtique Energie. Celtique has applied to drill the Fernhurst-1 well on PEDL 231 in the Weald Basin as a test of a conventional Kimmeridge Limestone and a Great Oolite stratigraphic trap play but also to establish the shale liquids potential of the Kimmeridge Clay and Middle and Lower Lias.

3. Ownership transactions

There have been a substantial number of business deals in Europe as late entrants tried to gain a foothold in promising acreage and smaller companies sought additional financing. Full company M&A activity has also occurred though most transactions have taken the form of licence purchases or farm-ins.

4.1 Company mergers, acquisitions and restructuring

On 28th February 2011, Dart Energy Ltd. of Australia announced that it would acquire with immediate effect the 90% of the shares in the UK's Composite Energy Ltd. that it did not already own. Although primarily a coal seam gas explorer, Composite Energy had acreage with shale gas potential in both Scotland and Poland. On takeover, Composite Energy became Dart Europe Ltd. On 10th August 2011, Treador Resources Corp. announced a merger with ZaZa Energy LLC of Houston, TX, combining ZaZa's Eagle Ford and Eagle Ford/Woodbine ("Eaglebine") interests with Treador's Paris Basin interests. The new company will be called ZaZa Energy Corp. On 26th August 2011, the UK's San Leon Energy plc and Canadian company Realm Energy International Corp. announced an agreement whereby San Leon would acquire all of the shares of Realm, resulting in Realm becoming an indirect subsidiary of San Leon. The acquisition was completed on 10th November 2011. On completion of the deal, San Leon acquired 3 licences in Poland, 1 in Germany and 2 in Spain. In addition Realm had 10 outstanding licence applications in France and 8 applications in Spain. With the exception of 9 applications in the Paris Basin focused on shale oil, the primary target of the Realm licences and applications was shale gas. On 16th January 2012, Dart Energy announced the formation of Dart Energy International Shale. This wholly-owned subsidiary will manage and develop the company's growing portfolio of shale gas interests. With the exception of one asset in China, these are held in Europe. On 24th January 2013, San Leon Energy plc completed the acquisition of Aurelian Oil & Gas plc. Aurelian owned unconventional gas assets and acreage with unconventional gas potential in Poland plus other largely conventional assets in several European countries. On 2nd April 2013, Dart Energy announced the cancellation of the planned IPO of Dart Energy International (Dart Energy's non-Australian operations).

On 17th September 2013, Eden Energy announced that it had entered into a conditional agreement to sell all of its U.K. coal seam methane and shale gas portfolio to Shale Energy plc. The assets comprise Eden's 50% interest in 17 licences in England and South Wales and a 100% interest in one licence in South Wales. Seven licences in South Wales have an estimated P90 shale-gas-in-place of 17.1 Tcf net to Eden (6.35 Tcf recoverable). On condition that Shale Energy raised the capital to make the acquisition by November 2013, Eden Energy would hold a 29.9% direct interest in Shale Energy. Although Shale Energy failed to complete by the deadline, Eden has continued to extend the conditional agreement with Shale Energy Plc for the sale of its entire UK coal seam methane and shale gas portfolio for £11.5million (approximately A\$19.3million), and at the date of this report, that contract, conditional upon Shale Energy raising £7 million, remains in existence. On

13th November 2013, Poland's PKN Orlen completed the acquisition of Canadian company TriOil Resources Ltd., a move designed to buy in experience in horizontal drilling and hydraulic fracturing.

4.2 Licence acquisitions

Germany: On the 23rd December 2011, in the course of acquiring BG's UK coal seam gas interests, Dart Energy obtained an exclusive option to acquire for no additional consideration a 100% interest in two licence areas held by BG in Germany (Saxon I West and Saxon II), which are prospective for both CBM and shale gas. Dart exercised the option in May 2012.

Poland: On 15th November 2010, the UK's San Leon Energy plc announced that it had agreed to acquire Mazovia Energy Resources (a EurEnergy Resources Corp. subsidiary), holder of three concessions in the Fore Sudetic Monocline, southwest Poland. The concessions are thought to have Carboniferous shale gas potential. On 10th December 2010, Eni S.p.A. announced that it had agreed to acquire Minsk Energy Resources (a EurEnergy Resources Corp. subsidiary), holder of three concessions in the Baltic Depression. On 21st January 2013 PKN Orlen announced that it has been assigned two concessions on the East European Platform Margin, previously held by ExxonMobil.

United Kingdom: On 28th December 2011, Dart Energy announced that it had agreed to acquire all of the unconventional gas assets of Greenpark Energy Ltd., comprising 22 onshore licences in the UK. Seven of these licences are considered to have shale gas potential.

4.3 Farm-ins and interest transfers

Bulgaria: On 29th August 2011, LNG Energy Ltd. announced that it had entered into an agreement with TransAtlantic Petroleum Ltd. to earn a 50% interest in the A-Lovech exploration licence in northwest Bulgaria. LNG Energy was to provide up to US\$ 7.5 million to drill, core and test a 10,500' Middle Jurassic shale gas exploration well. Closure of the deal was announced on 22nd September 2011.

France: On 10th May 2010, Toreador Resources Corp. (now ZaZa Energy Corp.) and Hess Corp. announced an agreement, whereby Hess would make a \$15 million upfront payment and invest up to \$120 million in a two-phase work programme on Toreador's awarded and pending shale oil exploration permits in the Paris Basin. Phase 1 was to consist of an evaluation of the acreage and drilling of six wells. Depending on the results of Phase 1, Phase 2 was expected to consist of appraisal and development activities. Following Phase 2, provided contractual obligations had been met, Hess would hold a 50% share of Toreador's working interest in the covered permits. On 26th July 2012, ZaZa Energy announced that it had transferred its remaining 50% interest to Hess Corp., retaining a 5% overriding royalty interest. On 26th September 2013, however, the Minister for Ecology, sustainable Development and Energy refused to authorise the transfer to Hess Corp. on the grounds that (a) Hess's French subsidiary did not have the technical capacities required by the Mining Code and (b) the licences could be exploited only by the use of hydraulic fracturing. On 15th July 2011, Realm Energy International Corp. (now San Leon) announced that it had entered into a farm out agreement with ConocoPhillips covering its nine exploration licence applications in the Paris Basin. The agreement provided Realm with a limited carry on exploration expenditure conditional on actual acreage acquired and required activity commitments. Realm was designated operator for the initial exploration phase with ConocoPhillips having an operatorship option thereafter. The nine licences are considered to be primarily prospective for tight oil. It is assumed that this agreement lapsed with the acquisition of Realm by San Leon.

Germany: Following renewal of its two licences in the Bodensee Trough, north of the Swiss-German border on 20th December 2013, Parkyn Energy, a 3Legs Resources subsidiary, transferred its interests to Rose Petroleum in exchange for a 2% royalty and contribution of €400,000 towards past costs.

Lithuania: In October 2012 it was reported that Chevron had taken a 50% interest in LL Investicijos, holder of the Rietavas oil field licence, with an option to acquire the other 50%. Tethys Oil announced that Chevron had also acquired a further 6% stake in the Rietavas field from Tethys with an option to acquire a further 8.5% within three years. It is understood that Chevron's primary interest in the licence is in shale exploration.

Poland: In August 2009, ConocoPhillips reached an agreement to farm into 3Legs Resources' six Baltic Depression concessions. ConocoPhillips is funding the initial exploration and evaluation programme but 3Legs Resources remains the operator. ConocoPhillips had until 20th March 2012 to determine whether to exercise an option to take a 70% interest in the concessions. If exercised, operatorship would transfer to ConocoPhillips. On 20th March 2012, 3Legs Resources announced that ConocoPhillips would exercise its option in respect of the three western concessions. Completion of the option exercise took place on 14th September 2012, whereupon operatorship of the three western concessions passed to ConocoPhillips. It was also announced that the two companies were considering options for the three eastern Baltic Depression concessions which are situated in a more liquids-prone part of the basin (see *2.1.1 Lower Paleozoic: Poland*). In order to develop an appropriate strategy for the three eastern concessions, they were to be divested into a separate Polish legal entity, which would be a wholly-owned subsidiary of 3Legs Resources. ConocoPhillips has opted not to acquire a 70% interest in the three eastern concessions. On 1st March 2010, Irish company San Leon Energy Ltd. disclosed that it had entered an agreement with Talisman Energy Inc. whereby Talisman would acquire a 60% interest in San Leon's three Baltic Depression concessions in exchange for covering 60% of the cost of a seismic programme and drilling one well on each of the three concessions with an option to follow up with a further three wells. If the second three wells are not drilled, Talisman's interest will reduce to 30%. On 6th March 2013, Talisman announced that it was evaluating its options in Poland and on 8th May San Leon reported that it had reacquired 100% ownership of Talisman's Polish interests. On 3rd July San Leon then announced an agreement whereby Wisent Oil & Gas could earn a 45% interest in the Braniewo concession by conducting a three-stage fracture on the Rogity-1 well followed by drilling and testing a multi-stage horizontal well on the concession. On 26th April 2011, Marathon Oil Corp. announced that Nexen Inc. will take a 40% interest in 10 of Marathon's 11 concessions in the Lower Paleozoic play, eastern Poland. On June 9th 2011, Mitsui & Co. Ltd. reported that it had agreed to acquire a 9% interest in the 10 concessions, reducing Marathon's interest to 51%. Marathon remained operator. The one concession excluded from the farm-outs was Plonsk SE in the Danish-Polish Marginal Trough. On 13th May 2011, Total SA announced an agreement with ExxonMobil to farm in to two concessions in the Lublin Trough, Danish-Polish Marginal Trough. Total acquired a 49% interest while ExxonMobil retained a 51% interest and operatorship. The farm-in was approved in July 2011. On 14th August 2011, Hutton Energy plc (formerly BasGas Pty Ltd.) announced that through its Polish subsidiary Strzelecki Energia it intended to take a 49% interest in four ExxonMobil concessions in the Podlasie Depression of the East European Platform margin. ExxonMobil would retain 51% and operatorship. Although the deal was approved subsequently by the Polish Office of Competition and Consumer Protection, the deal was never closed. On 6th June 2012 San Leon announced that it had taken a 75% interest in three concessions owned by Hutton Energy plc through its Polish subsidiary Strzelecki Energia, one in the Danish-polish Marginal Trough and two with Carboniferous prospectivity in the Fore-Sudetic Monocline. In both cases the farm-in concessions are adjacent to concessions in which San Leon already has an interest. Total SA has indicated that it will become 100% owner and operator of the Chelm concession on the East European Platform Margin. ExxonMobil previously held 51% of the concession and was operator.

United Kingdom: On 13th June 2013 it was announced that Centrica plc has acquired a 25% interest in the Bowland exploration licence PEDL 165 from operator Cuadrilla Resources (56.25%) and AJ Lucas (18.75%). Centrica acquired the interest for GBP 40 million and will pay a further GBP 60 million in exploration and appraisal costs. If Centrica elects to continue into the development phase, it will then pay a further GBP 60 million. On 22nd October 2013 Dart Energy announced that GDF SUEZ will farm into 13 of its U.K. licences in Central England and North Wales. GDF SUEZ will acquire a 25% interest with Dart retaining 75% and operatorship. The funding will support an unconventional exploration and appraisal programme of up to 4 shale gas wells and 10 coal seam gas wells. The farm-in was completed on 28th November 2013. On 13th January 2014 it was announced that French major Total SA would take a 40% interest in PEDLs 139 and 140 in the Gainsborough Trough in Lincolnshire. Total will pay \$1.6 million in back costs to the other partners, Dart Energy (17.5%), Egdon Resources (14.5%), eCorp Oil & Gas (13.5%) and IGas (14.5%) and fund a fully carried work programme of up to \$46.5 million. The programme includes the acquisition of 3D seismic, drilling and resting a vertical exploration well and, conditional on its success, a second horizontal well. The farm-in was completed on 4th February 2014, at which time IGas became operator. On 30th January 2014 Egdon Resources announced that Total SA has signed an opt-in agreement for PEDL 209, adjacent to PEDLS 139 and 140 (above) in the Gainsborough Trough. Total has the option to farm-in until 31st December 2015 and on doing so will earn a 50% interest by paying 100% of an exploration programme up to £13.47 million. Three conventional prospects on the acreage are excluded from the deal.

4.4 Relinquishments

Germany.

BNK Petroleum. BNK Petroleum has announced that it intends to relinquish five of its eight German concessions, retaining the three concessions in North Rhine – Westphalia's Munsterland Basin. Some of the licences to be surrendered contained primarily conventional prospects.

Poland: By 28th February 2014 a total of 24 shale gas and 1 shale liquids concessions had been relinquished, 12 in the Danish-Polish Marginal Trough, 5 on the East European Platform Margin, 4 on the Fore-Sudetic Monocline and 3 in the Baltic Depression.

BNK Petroleum (Indiana Investments). In December 2013 BNK relinquished its Darlowo concession in the Baltic Depression.

Cuadrilla. In February 2014 the company relinquished its Lukow concession on the Danish-Polis Marginal Trough

Dart Energy. In October 2013 Dart Energy relinquished its Milejow concession in the Lublin Trough, to focus on its U.K. operations.

DPV Service. Between April and July 2013, DPV Service relinquished the five concessions with unconventional potential that it held in the Danish-Polish Marginal Trough, retaining only a conventional licence.

Eni. Eni chose not to renew two of its three concessions in the Baltic Depression when they expired in December 2013 and January 2014. The third licence is valid until June 2018.

ExxonMobil. After the transfer of two concessions to PKN Orlen and surrendering its 51% interest in another to its partner, Total SA, ExxonMobil has relinquished its other three Polish concessions, one in the Danish-Polish Marginal Trough and two on the East European Platform Margin.

Lane Energy. Lane Energy (3Legs Resources) has relinquished without drilling the three concessions that it held in the Fore-Sudetic Monocline.

Marathon Oil. In October and November 2013 Marathon relinquished four concessions in the Danish-Polish Marginal Trough and three on the East European Platform Margin.

PGNiG. PGNiG relinquished the Bartozyce shale liquids concession in the Baltic Depression in December 2013.

San Leon. In April 2013, San Leon relinquished one concession in the Fore-Sudetic Monocline which it had held through its Vabush Energy Subsidiary. It retains interests in nine other concessions in that basin.

Saponis (BNK Petroleum; Esrey Energy). In 2013, Saponis announced its intention to relinquish the Starogard and Slawno concessions, retaining the Slupsk concession. The relinquishments had not taken place by 28th February 2014.

4. Above-ground issues

Other than general fiscal, legal and environmental regulation of hydrocarbon exploration and exploitation, there are a number of issues that specifically face most gas and liquid resource play developments. Per-well reserves and productivity can be low and benefit from an established gas compression and distribution infrastructure. To convert resources into reserves also requires large numbers of wells. Some North American resource plays employ 10-acre spacing as opposed to the 640-acre spacing typical of conventional wells. This could pose a problem in densely populated areas of Europe but horizontal wells drilled from a single pad can be used to reduce the well footprint. In British Columbia's Horn River Basin, Apache Corp.'s well design concept should recover gas from two different stratigraphic intervals over an area of 7 km² from a single 28-well pad. Other environmental issues such as water availability and water disposal capacity may also impact on ultimate recovery. Almost inevitably, the concerns that have been raised in the U.S. about potential contamination of groundwater supplies from chemicals used in hydraulic fracturing of shale gas reservoirs are being echoed in Europe. In addition, the potential of fracking to induce local seismicity has also been raised. A major public misconception appears to be that the word "unconventional" implies new, untested, and therefore risky, drilling and completion technology. Public disquiet has manifested itself in a number of countries, most notably Bulgaria, France, Germany, Romania and the United Kingdom. The issues have now entered the political realm, creating a further condition of uncertainty. While vested commercial interests (e.g. the coal, nuclear and renewable energy industries; importers of conventional gas; natural gas storage operators) are almost certainly a factor, populism in advance of elections is undoubtedly playing a part and environmental groups are using the controversy to advance their own agendas. Until there is public recognition that the drilling and fracturing technology that is in use has been applied for decades in hundreds of thousands of wells and that all that is "unconventional" is the mode of subsurface occurrence of the natural gas, there are likely to be deferrals and delays in the evaluation of shale gas potential in a number of countries. It remains a problem of perception. "People overestimate the dangers of what is new and underestimate those of what they're used to" (Rudolf Huber, CEO of NeXtLNG Ltd.).

The commissioning on 8th November 2011 of the first of two 1,224 km (760-mile) Nord Stream gas pipelines across the Baltic Sea from Portovaya Bay in Russia to Lubmin in Germany, effectively created a divergence of interests between the western European countries served by Nord Stream (e.g. Germany; Denmark; U.K.; The Netherlands; Belgium; France; Czech Republic) and those countries still dependent on Russian gas from the overland route transiting through Ukraine (e.g. Poland; Bulgaria; Romania). Gazprom's announcement that it is considering further Nord Stream pipelines and its downbeat remarks about European shale gas exploitation suggest that it sees shale gas development in Europe as a threat to its position as largest gas supplier to the continent and is keen to divert governments away from shale gas and back towards Russia as a guaranteed supplier.

International Energy Agency: Conscious of the impact that negative publicity has on realizing the potential of unconventional gas, on 29th May 2012 the Paris-based International Energy Agency released a World Energy Outlook special report on "Golden Rules" that are needed to support a potential "Golden Age of Gas". The report provides insights into the environmental challenges linked to unconventional gas production and how best to deal with them.

European Union (EU): On 4th February 2011, the European Council announced a number of priority actions in its Conclusions on Energy (PCE 026/11). Priority 7 stated "In order to further enhance its security of supply, Europe's potential for sustainable extraction and use of conventional and unconventional (shale gas and oil shale) fossil fuel resources should be assessed." In September 2011, the EU Energy Commissioner, Guenther Oettinger of Germany, said that he hopes to put forward proposals in spring 2012 to standardise regulations on hydraulic fracturing. This followed a report published in July for the European Parliament by six German authors entitled *Impacts of shale gas and shale oil extraction on the environment and on human health*. Herr Oettinger's announcement produced a strong reaction from the Polish Treasury Minister who stated that exploration for unconventional hydrocarbon resources is already adequately regulated and that the possibility of European Union wide regulation is not provided for in the Lisbon Treaty (Treaty on the Functioning of the European Union or TFEU). (Both the Lisbon Treaty and the Energy Treaty Charter recognise state sovereignty in the use of a country's energy resources.) On 22nd September 2011, Herr Oettinger's spokeswoman, Marlene Holzner, said that the commission is studying whether the current European Union environmental laws would apply to shale gas production, but isn't planning to propose any new legislation. On 13th October 2011 EU Climate Action Commissioner, Connie Hedegaard, said that she was not inclined towards a moratorium on shale gas drilling based on the information that she had heard so far. The European Commission (EC) selected a Brussels law firm, Philippe & Partners, to analyse how the relevant applicable European legal framework, including environmental law, is applied to the licensing, authorisation and operation of shale gas exploration and exploitation, using a sample of four Member States: France; Germany; Poland; Sweden. The 104-page report was published on 8th November 2011. On 27th January 2012 Energy Commissioner Oettinger stated that "the legal study confirms that there is no immediate need for changing our EU legislation." On 7 September 2012 the European Commission published three new studies on unconventional fossil fuels, in particular shale gas. The studies look at the potential effects of these fuels on energy markets, the potential climate impact of shale gas production, and the potential risks shale gas developments and associated hydraulic fracturing may present to human health and the environment.

Unconventional Gas: Potential Energy Market Impacts in the European Union. The study on energy market impacts shows that unconventional gas developments in the US have led to greater Liquefied Natural Gas supplies becoming available at global level, indirectly influencing EU gas prices.

Climate impact of potential shale gas production in the EU. The study on climate impacts shows that shale gas produced in the EU causes more GHG emissions than conventional natural gas produced in the EU, but – if well managed – less than imported gas from outside the EU, be it via pipeline or by LNG due to the impacts on emissions from long-distance gas transport.

Support to the identification of potential risks for the environment and human health arising from hydrocarbons operations involving hydraulic fracturing in Europe. The study on environmental impacts shows that extracting shale gas generally imposes a larger environmental footprint than conventional gas development. Risks of surface and ground water contamination, water resource depletion, air and noise emissions, land take, disturbance to biodiversity and impacts related to traffic are deemed to be high in the case of cumulative projects.

In launching the EU's green paper on energy and climate aims for 2030, Energy Commissioner Günther Oettinger took a favourable position on shale gas, quoting the gas prices in the U.S. compared with European prices. Anne Glover, chief scientific adviser, gave a scientific green light to shale while noting that there are risks involved with all energy production, including wind and coal. But she also noted that in terms of extraction and production there are non-scientific issues to be debated. Connie Hedegaard, Climate Commissioner, was less positive, stating that different geological conditions and environmental rules mean that shale gas exploitation in Europe will bear little comparison with the U.S. Separately from the European Commission, the German chairman of the European Parliament's committee on the Environment, Public Health and Food Safety indicated in July 2011 that he wants a new "energy quality directive" that would introduce stringent regulations to cover fuels with what are deemed to be adverse environmental impacts – tar sands oil and shale gas among them. As might be expected, given the variety of political positions represented, the European Parliament's opinions are more diverse than those of the Commission and in some cases contradictory. These were expressed in two resolutions adopted by committee in mid-September 2012. The emergence of exploration for shale oil and shale gas in some EU countries should be backed up with "robust regulatory regimes" according to separate non-binding resolutions by the Energy Committee (on industrial aspects) and the Environment Committee (on health and environment ones). Member states should be "cautious" pending further analysis of whether EU level regulation is adequate, according to environment MEPs. Each EU country has the right to decide for itself on whether to exploit shale gas, said the Energy Committee. Member states should have robust rules on all shale gas activities, including hydraulic fracturing of rock ("fracking"). MEPs also advised the EU to learn from US experiences, with a view to using environmentally-friendly industrial processes and "best available technologies". The European Commission previously concluded that EU rules adequately cover licensing and early exploration and production of shale gas but "a thorough analysis" of EU regulation on unconventional fossil fuels is needed, given the possible expansion of their exploitation, noted Environment MEPs. In April 2013, the chair of Parliament's science and technology options assessment panel said that Europe is in the "denial phase" on shale gas. On 22nd January 2014 the European Commission adopted and published a non-binding Recommendation and Communication for its Shale Gas Enabling Framework (thereby avoiding legislative proposals). Member states are invited implement it within six months (thereby bypassing the European Parliament elections in May 2014) and the EC will review the Recommendation 18 months after publication.

The Recommendation invites Member States to ensure that:

- There is an integrated approach to the granting of permits;
- Risk assessments are undertaken on potential drilling sites;
- Baseline studies and subsequent monitoring are undertaken on drilling sites;
- Operators apply best practice;
- Use of chemicals in frac fluid is minimised and fluid content used is made publicly available on a per well basis;

- An EIA is carried out where required under EU Directive 2011/92/EU (i.e. when gas production exceeds 17.5 MMscf/d).

Background comment. Individual EU member states have the right to determine exploitation of energy resources and their energy mix (TFEU Article 194). Member states are also free to set more stringent environmental protection measures than required by EU legislation (TFEU Article 193). Most aspects of hydrocarbon exploration and production are covered by existing EU legislation: Hydrocarbon Directive; Water Framework Directive; Groundwater Directive; Environmental Impact Assessment; Registration, Evaluation, Authorisation and Restriction of Chemical substances (REACH); Natura 2000 (protected areas); and other regulations covering waste, noise etc.

Austria: OMV's plans to drill one or two shale gas exploratory wells in the wine quarter of Lower Austria ran into substantial opposition. Despite seeking community support, the company's plans were resisted not only by environmental and community groups but also by politicians, including the Environment Minister and Governor of Lower Austria. On 2nd March 2012 OMV announced that it would suspend drilling plans pending the completion of a comprehensive environmental and social study by the Federal Environmental Agency and TÜV Austria Group, a technical and environmental safety consultancy. In July 2012 the Minister for Environmental and Agricultural Affairs announced plans to reform the environmental impact assessment act to incorporate shale gas exploration. The cost of producing a detailed environmental inspection and assessment for any proposed well effectively makes shale gas drilling uneconomic and OMV currently has no further plans for shale gas exploration in Austria.

Bulgaria: The shale gas debate featured in the October 2011 presidential elections with the two principal opposition candidates both indicating that they opposed shale gas development. The election was won, however, by the candidate of the ruling party (Citizens for European Development of Bulgaria). Environmental organisations and opposition parties wished to impose a temporary moratorium on shale gas exploration and called for a referendum on allowing such activities. Although the Ministry of Economy, Energy and Tourism indicated that it planned a thorough assessment of the risks involved in shale gas development it appeared to be broadly supportive of shale gas exploration. On 19th October 2011, a delegation representing a number of ministries and regional governors visited Poland to learn from the Polish experience. In the face of massive public protests, on 18th January 2012 parliament placed an indefinite ban on the use of hydraulic fracturing. The previous day, prior to final execution of the licence agreement, the government announced the withdrawal of the Novi Pazar permit for shale gas exploration awarded to Chevron in June 2011. Chevron continues in discussions with the government to provide assurances that hydrocarbons can be produced safely from shale. The Minister for Economy and Energy has said that he believes powerful financial interests were behind the mass protests. The pro-Russian Centre Left party played a leading role in opposing shale gas research. (Gazprom provides 98% of Bulgaria's gas.) Since the moratorium was imposed a Movement for Energy Independence has been established and has called for cancellation of the moratorium. But informed opinion suggests that at present the government does not believe that it is politically worthwhile to confront public opinion.

Czech Republic: The Náchod District assembly and some 50 local administrations submitted formal objections to the Ministry of Environment's award of the Trutnov permit to Basgas Energia Czech, a subsidiary of Hutton Energy. In April 2012 the Trutnov award was cancelled and sent back to the Ministry of Environment regional department to be decided again. In September 2012 the Minister of Environment announced a moratorium on shale gas exploration in the Czech Republic until 30th June 2014. Prime Minister Petr Necas has said that suitable legislation that will define the framework for prospecting and exploitation is required, and only after such legislation has been adopted could further steps be discussed.

France: In February 2011, shale gas and shale oil drilling in France was suspended by the authorities pending a progress report on the environmental consequences of shale exploitation. The ultimate outcome of this process was the passing of a law on 13th July 2011 (Law 2011-835) that prohibited the exploration for, and production of, liquid or gaseous hydrocarbons by hydraulic fracturing. Permit holders had two months in which to advise the administrative authorities of the techniques that they use or intend to use in their exploration activities. Failure to respond or an intention to use hydraulic fracturing would result in withdrawal of the permit. A national commission would also be established to evaluate the environmental risks associated with hydraulic fracturing and to set out the conditions under which scientific research under public control can take place. The government is to report annually to parliament on the evolution of exploration and production technology in France, Europe and internationally and also on the results of the scientific research undertaken. In September 2011, major French E&P company Total S.A. announced as part of its report to the authorities that it would continue the evaluation of its Montélimar exploration licence but that the work programme does not envisage the use of hydraulic fracturing. Other companies were expected to adopt a similar approach.

On 3rd October 2011 the ministers of Ecology, Sustainable Development, Transport & Housing and Industry, Energy & the Digital Economy announced in a joint press release that the three permits issued specifically for exploration for shale gas would be cancelled. These are the Total S.A. Montélimar exploration and the Schuepbach Villeneuve-de-Berg and Nant licences. Total expressed surprise as it had undertaken not to use hydraulic fracturing and was awaiting the government's notification to understand the legal basis for the cancellation. The official confirmation of the repeal of the three licences was gazetted on 13th October 2011. On 26th November the CEO of Total S.A. announced that the company would appeal against the revocation of the Montélimar licence and on 12th December the company filed an appeal in the Paris Administrative Court in order to clarify the situation, on the grounds that the company had complied with the Act of July 13th 2011. In October 2012 Christophe de Margerie, Total CEO, stated that the Group was no longer willing to spearhead the shale gas quest in France and that it is up to politicians and government officials to decide on the future of shale gas exploration in the country.

The French Union of Petroleum Industries declared that the cancellation decisions will send a negative signal to international investors and are prejudicial to an economy which imports 99% of its oil and 98% of its gas consumption. The CEO of French company GDF Suez said that while it was appropriate that the government evaluate technology and processes, closing the door forever to shale gas development would be "a major mistake". On 11th October 2011 the National Assembly rejected a bill submitted by the parliamentary opposition which set out to prohibit exploration for, and exploitation of, unconventional hydrocarbons irrespective of the techniques used. The proposed bill was deemed to contain several flaws and to be incompatible with the law of 13th July 2011. On 21st March 2012, a new decree established a National Commission to evaluate shale oil and gas exploration techniques and operations. The commission would be consulted on: conditions for implementation of hydraulic fracturing research projects; managing risk and environmental protection during experimentation on new techniques to exploit shale oil and gas; the government's annual report to parliament set out in the Act of July 13th 2011 (above). At end September 2012, the members of the commission had not yet been appointed. Since the presidential election in May 2012 and the formation of a new government, official statements have sent a variety of messages, some of them contradictory. Most recently, on September 14th, President Hollande stated that, as far as the exploration and exploitation of non-conventional hydrocarbons is concerned, hydraulic fracturing will be banned throughout his five-year term in office and instructed the Environment Minister to reject seven applications for permits to explore for shale gas, citing potential impacts on health and the environment. (It should be noted that he did not order the rejection of a number of pending applications for permits with shale oil potential.) The president's forceful statement seems to have taken industry representatives and even some government sources by surprise, as there are major concerns in France regarding the long-term impact of such a ban on the economy and energy security.

At a parliamentary hearing in April 2013, senators, company representatives, scientists and energy policy analysts broadly supported a resumption of exploration for shale oil and gas so that at the very least France's resource potential could be evaluated. On 11th October 2013, ruling on a challenge submitted by Schuepbach Energy, the French Constitutional Court ruled that the ban on hydraulic fracturing introduced in Law 2011-835 is not disproportionate and that the law conforms to the Constitution. Only Arnaud Montebourg, Minister of Industrial Renewal, has supported development of shale gas, subject to the proviso that the industry finds alternative ways of bringing gas to surface by methods that do not risk the pollution and other dangers for which hydraulic fracturing has been blamed. There is, however, a groundswell of support for lifting the ban from industry. A consequence of the ban on hydraulic fracturing has been an accumulation of unprocessed applications for exploration permits. On 31st January 2014 a total of 110 permit applications were awaiting decision.

Background comment. In 2007, 78% of all French electricity production came from nuclear power. Two new European pressurised water reactors (EPRs) are due to be commissioned by 2017, so it can be assumed that the nuclear industry will not be supporting shale gas development!

Germany: Fracking was first used in conventional wells in 1955 (Schleswig-Holstein) and 1977 (Lower Saxony). Between 1977 and 2010 some 140 frac operations were conducted in Germany. The first fracking of unconventional gas wells (tight gas) occurred in the mid-1990s in the Söhlingen Field, Lower Saxony, and fracking was conducted in at least three other tight gas fields in Lower Saxony in the period 2005-2010. Despite a 55-year history of fracking, there was no public interest in the application of the technology in Germany until 2010. Unlike France, where governance is highly centralised, the German Länder (constituent states of the Federal Republic of Germany) have a high degree of autonomy. The political strength of the Grüne (Green environmental party) is at an all-time high both federally and at state level, and environmental groups have exerted considerable pressure on politicians in areas where shale gas development is proposed. In March 2011 the state Environment minister of North Rhine-Westphalia, a member of the Grüne, introduced a moratorium on shale gas exploration. To date, however, most shale gas exploration has taken place in Lower Saxony, which has not introduced such a moratorium. The Minister for Environmental Protection in the federal government announced on 29th July 2011 that an expert survey on the environmental impact of shale gas production would be ordered and that changes to the geological and mining laws are likely.

On 4th August 2011 the Federal Environment Agency published an opinion entitled *Einschätzung der Schiefergasförderung in Deutschland* (Assessment of shale gas production in Germany). The report is generally negative towards shale gas and appears to selectively quote, for example, sources such as the Tyndall Centre for Climate Change at the University of Manchester and Robert Howarth at Cornell University that are generally considered to exaggerate the impact of natural gas as a source of greenhouse gas emissions. If the planning and legislative requirements proposed in the report are implemented, they will probably have the effect of making shale gas production uneconomic in Germany. In September 2012 the German Federal Ministry for the Environment, Nature Conservation and Nuclear Safety (BMU) produced a report entitled "Environmental impacts of fracking in the exploration and production of natural gas from unconventional deposits". Although the report does not recommend a ban on hydraulic fracturing, some of the proposed conditions are sufficiently prescriptive to cast doubt on the viability of much unconventional E&P activity. In the same month, following a risk study published by the Environment and Economic ministries of the state of North Rhine – Westphalia the state authorities banned hydraulic fracturing operations until more evidence on the risks involved is available. In December 2012, the German parliament voted to put forward a bill permitting hydraulic fracturing to resume, subject to strict controls (e.g. limited to areas where water resources will not be impacted; mandatory EIA; mandatory information on fluid treatment and flowback). In January 2013, the Federal Institute for Geosciences and Natural

Resources (BGR) responded to the September 2012 Environment Ministry (BMU) report, criticising it for its lack of geosciences expertise, its inconsistency and subjectivity and failure to use the available broad knowledge base of existing technology. Though current legislation permits requests for hydraulic fracturing to be filed under existing water rights and mining law, none of the public authorities would grant such a request, so there was effectively a moratorium on hydraulic fracturing until the new bill was introduced. The government failed to introduce the bill prior to the September 2013 federal elections. During the subsequent coalition-building process, in November 2013, it was announced that the partners in government had agreed to place a moratorium on hydraulic fracturing until environmental and health concerns are resolved. In February 2014, spokespersons for the German gas industry pointedly indicated that the decline in German gas production can be attributed to the political reluctance to permit hydraulic fracturing, despite it having been used in German tight sandstone reservoirs for over 50 years (see above).

Background comment. The German unconventional hydrocarbons industry is not well developed and domestic companies lack the necessary technology. These companies are focused on the production, importation and storage of conventional gas. Germany also has a substantial renewable energy industry. All of these interests would be threatened by large volumes of low-cost indigenous natural gas. It is therefore in the interests of German industry not only to make shale gas production as unprofitable as possible in Germany but to use its influence to restrict large-scale gas production elsewhere in Europe (see the direction of the German strategy in the *European Union* above).

Ireland (Republic of Ireland): The principal prospect in Ireland lies in the Northwest Ireland Carboniferous Basin (Lough Allen Basin), which straddles the border between the Irish Republic and Northern Ireland but most of the opposition has come from the Republic side. At a company information meeting in early September 2011, the operator, Tamboran Resources, offered to conduct fracking without chemical additives but this did nothing to soften the opponents of the scheme. The government subsequently asked the Environmental Protection Agency (EPA) to conduct a study on the effects of fracking. The 26-page report prepared by the University of Aberdeen, entitled *Hydraulic Fracturing or 'Fracking': A Short Summary of Current Knowledge and Potential Environmental Impacts*, will be used as the groundwork for a more comprehensive study by the EPA. The major environmental trust, An Taisce, has called for fast track regulation to clarify the currently uncertain regulatory position regarding onshore drilling. In April 2013, Energy Minister Pat Rabbitte reaffirmed that no decision on permitting hydraulic fracturing will be taken until the EPA's study is concluded at the end of 2014.

Background comment. As confirmed by the Minister of State at the Department of Communications, Energy and Natural Resources on 21st March 2012, conventional fracking has already been applied by Dowell Schlumberger in the case of three Irish onshore wells: Dowra-1 Re-entry (1981), Dowra 2 (2002) and Thur Mountain 1 (2002).

Netherlands: Although the provincial authorities in Noord Brabant were opposed to Cuadrilla Resources' plans to drill two wells, in early 2011 the Dutch Minister for Economic Affairs, Agriculture and Innovation granted a licence for drilling to proceed. (The Dutch state, through its wholly-owned company EBN, has a 40% interest in the licence.) On June 29th 2011, however, the ministry indicated that shale gas exploration in the Netherlands would not move ahead until the results of the UK's inquiry into hydraulic fracturing had been assessed. "If it appears that there are unacceptable risks, no drilling for shale gas will occur," the Minister, Maxime Verhagen, said in a letter to parliament. "Concerns regarding shale gas are understandable and I take them very seriously."

In October 2011, Cuadrilla encountered another setback when a court ruled that Boxtel town council was wrong to grant a temporary exemption from zoning for its Boxtel-1 well since that was

based on activities concluding within five years and, if commercial production had been established, it was likely that operations would exceed this time span. Cuadrilla must now return to Bostel council to resolve the situation and their spokesman expected a few months' delay to a well that was due to spud early in 2012. The most recent company estimate is that this well will not now spud until 2013.

The Dutch Ministry of Economic Affairs, Innovation and Agriculture commissioned an independent study of all possible risks and consequences of shale gas exploitation, including methane emissions from drilling, the presence of heavy metals in drilling mud, and the risk of induced seismicity. The study was delivered on 27th August 2013 and concluded that while total risks were slightly greater than the risks associated with conventional exploration due to the large number of wells involved, they remained very small. The government will now undertake a study to identify all likely shale gas exploration sites on Dutch soil to determine where locations with the highest likelihood of success and least environmental risk occur. This study is likely to take 12 – 18 months and in the meantime no shale gas exploration applications will be processed and where permits have already been granted, companies will not proceed until the study is complete. Some 60 out of 400 local authorities had declared their opposition to shale gas production.

Poland: Unlike most other countries the major political debate in Poland has been about maximising the benefit of shale gas exploitation to the state. In advance of the October 2011 parliamentary election, the opposition Law and Justice Party prepared draft legislation covering Polish shale gas. In the election, however, the ruling Civic Platform–Polish People's Party coalition won sufficient seats to continue in government. Draft regulations regarding a hydrocarbon extraction tax on conventional and unconventional hydrocarbon production were published on 16th October 2012 but will not come into effect until 2015. The implied tax burden is 40% of gross profits. More contentious, however, has been the licensing regime and the process of granting shale gas concessions, with six persons, three Ministry of Environment officials and three company employees, detained and released on bail on suspicion of offering or receiving bribes for the allocation of licences. *The Economist* has noted that the existing rules were designed for a system in which a small number of state-controlled companies were operating, and not for the current exploration environment. With most of the prospective shale gas acreage now under licence, however, any changes will be taking place after the horse has bolted.

It was expected that new regulations on shale gas extraction would be announced in November / December 2012 and implemented from 2013. It is thought that a simplification of environmental requirements and general reduction in red tape would form a part of the new regulatory environment. Companies would no longer require to hold a licence before conducting non-drilling energy exploration operations, but energy companies looking to enter the Polish shale market will have to be pre-approved by the Polish government to buy existing licences. A state-owned National Energy Minerals Operator (NOKE) will also be created. NOKE will participate in shale gas projects, where it is intended that it strengthens administrative oversight of licence obligations, and have right of first refusal on secondary trade in exploration licences. NOKE will pay its net profit to the Polish Treasury and to municipal governments, thereby involving local communities in successful shale gas development. NOKE's profits will also go to a planned Hydrocarbon Generations Fund, a form of sovereign wealth fund.

In mid-February 2013 the new hydrocarbon regulations were published in draft form for a one-month public consultation period. They involve a changed Geology and Mining Law and amendments to eight other bills. Some environmental requirements will be loosened. The final draft of the regulations was submitted to the Prime Minister's office in mid-June. Parliament was expected to approve the bill before the end of 2013, after which it will require the signature of the President.

In order to accelerate shale gas development, in March 2014 the Polish government offered six-year tax breaks to shale gas projects, avoiding the introduction of special taxes. According to Prime Minister Donald Tusk, the proposal would go through Parliament's approval as early as early

April. It has also been reported that the government will drop plans to create the proposed National Energy Minerals Operator (NOKE), in a move to cut red tape and reduce regulatory hurdles.

Romania: The protests in Bulgaria (above) have been echoed in Romania. Bulgarian activists demonstrated outside the Romanian embassy in Sofia (capital of Bulgaria) and have been in contact with like-minded groups in Romania. The Barlad municipality, where Chevron planned to drill later in 2012, opposed shale gas exploration and in March 2012 some members of the parliamentary opposition filed a legislative initiative which, if passed, would ban hydraulic fracturing. The parliamentary opposition came to power in April 2012 and in May introduced a moratorium on shale gas exploration, due to run until December 2012. In June, the March proposal to ban shale gas exploration and exploitation by hydraulic fracturing and cancellation of licences in which fracking would be used, was overwhelmingly rejected by the Romanian Senate. Comments by the Environment Minister in August 2012, that shale gas exploitation by hydraulic fracturing will not be approved unless the results of EU studies on its environmental and health implications indicate that it is acceptable, suggested that the moratorium was likely to be extended but when it expired at end-December 2012 it was not renewed.

Spain: In October 2012 the Government of Cantabria in northern Spain published a draft law which, if implemented, would prohibit the use of hydraulic fracturing as long as the doubts and uncertainties surrounding the use of the technique that exist today persist. The Cantabrian regional parliament passed the proposals into law on 8th April 2013. It should be noted that the bulk of the exploration permits in the Basque-Cantabrian basin, especially those in which shale gas exploration is proposed, lie in other regions: Basque Country (where the Autonomous Government is an active participant); Castilla y Leon; La Rioja; Navarra. On 30th October 2013 it is reported that the Spanish Government explicitly legalised hydraulic fracturing by amending a 1998 hydrocarbon exploration law to include hydraulic fracturing under permitted exploration techniques. EIAs will not be required before conducting fracturing operations. A law streamlining environmental requirement for industrial projects, which could accelerate shale gas exploration approvals, was published on 5th December 2013. In January 2014 the Spanish government then announced that it was taking Cantabria's ban on hydraulic fracturing to the Constitutional Court, arguing that it violates national law on hydrocarbon exploitation.

Sweden: In the September 2010 parliamentary election campaign the opposition centre-left alliance comprising the Social Democrats, the Left Party and the Green Party pledged to oppose large-scale fossil fuel production in Sweden, including Shell's planned exploitation of shale gas in southern Sweden. In the event, the ruling centre-right Alliance coalition was re-elected.

Switzerland: In Switzerland, the cantons have a substantial degree of independence and E&P is solely a cantonal responsibility. The Swiss Federation could have an indirect influence on shale gas through its responsibility for environmental legislation but there is no legislation specifically targeted at shale gas at the present time. The federal government's environmental focus is currently on carbon capture and storage (CCS). In April 2011 the cantonal authorities in Fribourg suspended all shale gas prospecting activities and refused the renewal of Schuepbach's exploration licence, due to expire at end-2011. The explanation given was that the environmental impact and pollution risk accompanying drilling had not yet been clearly identified and that the canton preferred to focus on renewable energies. In the canton of Jura, the Green party has questioned the authorities on their policies regarding shale gas. In Neuchatel the Grand Council has decided that in the event of a discovery, in principle an exploitation concession will be awarded to Celtique Energie and that shale gas is not specifically excluded from this decision. The Celtique Energie web site, however, suggests that their only unconventional prospects (shale oil and shale gas) are in the Weald Basin in southern England.

United Kingdom: On 24th November 2010, the House of Commons Energy and Climate Change Committee launched an evidence-based enquiry into the prospects for shale gas in the UK, the risks and hazards associated with shale gas, and the potential carbon footprint of large-scale shale gas extraction. The committee visited Fort Worth and Austin, Texas, Washington, DC, and two Cuadrilla Resources drilling sites near Blackpool, Lancashire.

The voluminous report (223 pages in two volumes) which was published on 23rd May 2011 produced a number of conclusions and 26 recommendations. In its summary, however, the committee stated that “on balance, we feel that there should not be a moratorium on the use of hydraulic fracturing in the exploitation of the UK’s hydrocarbon resources, including unconventional resources such as shale gas” (House of Commons Energy and Climate Change Committee, 2011). Nevertheless, a number of issues have arisen in the United Kingdom and some examples are given below. On 21st October 2011, the Vale of Glamorgan Council (south Wales) rejected a planning application submitted by Coastal Oil & Gas to drill Llandow-1, a shallow (2,600’) conventional and shale gas exploratory well situated on an industrial estate. Despite Environment Agency Wales indicating that it had “no objection to the application as submitted”, the Welsh Government declining to get involved as the issues were “not of more than local importance” and the application itself stating “This application does **not** include fracking”, the local environmental group “The Vale says No” supported by the local member of the UK Parliament put sufficient pressure on the councillors to ensure that all 17 members of the planning committee opposed the application.

Although in debate the councillors spoke of their concerns about pollution if fracking followed a positive exploration outcome, this does not represent a valid reason for rejection. The official reason given was therefore that “the applicant has submitted insufficient information to satisfy the Local Planning Authority that the quantity and quality of groundwater supplies in the vicinity of the site, would be protected”. The council leader indicated subsequently that better guidelines were required from the Welsh Assembly (regional government) for test drilling and fracking.

On 7th July 2012 an appeal against the decision to reject the planning application was upheld by the Welsh Planning Inspectorate who concluded that the main issue was the potential effect on the quantity and quality of groundwater supplies. The inspector concluded that the proposal would not harm groundwater supplies and Llandow-1 can now be drilled. As was indicated above (2.1.2 *Shale gas in Europe: Carboniferous*), fracking operations at Cuadrilla Resources’ Preese Hall drilling site were halted after two small earthquakes (2.3 and 1.5 Richter Local Magnitude) were reported on 1st April and 27th May 2011. The British Geological Survey (BGS) subsequently determined that the earthquakes at depths of 12,000’ and 6,500’ were within a few thousand feet of the drilling site and that the correlation between the earthquakes and their proximity to, and the timing of, hydraulic fracturing operations pointed to the earthquakes being the result of the fracking process.

On 2nd November 2011, Cuadrilla Resources (well operator) presented a geomechanical report (de Payter & Baisch, 2011) on the causes of the seismicity and future mitigation procedures to the Department of Energy and Climate Change (DECC). The report concluded that the repeated seismicity resulted from direct injection of fluid into the same critically-stressed fault zone and that this could be avoided in future by rapid flowback after treatment and reduction in treatment volume, accompanied by real-time seismic monitoring to initiate appropriate action when seismic magnitude exceeds pre-defined thresholds. The DECC sought input from the BGS and other expert sources before taking any decision on the resumption of fracking operations. A BGS spokesman did, however, indicate that earthquakes of the magnitude reported in Lancashire have been occurring for hundreds of years as a result of coal mining and generally go unnoticed. The independent report prepared for DECC agreed “that a suitable traffic light system linked to real-time monitoring of seismic activity is an essential mitigation strategy” allowing adjustments to be made to the injection volume and rate during the fracturing procedure, thereby preventing noticeable seismic activity (Green et al., 2012). On 5th December 2012, in a move widely read as encouraging shale gas exploitation, the government announced the creation of a new Office of Unconventional Gas and Oil,

with the intention of focusing regulatory effort to meet the needs of future production. On 13th December it was announced that hydraulic fracturing can resume, subject to controls to mitigate the risk of seismic activity. In the March 2013 Budget, the UK Chancellor of the Exchequer stated that tax arrangement for companies involved in shale gas exploration would be “generous”. Planning clarity should be available by summer 2013 and proposals would be developed to ensure that local communities benefit from shale gas projects in their area.

On December 6th 2011, the Northern Ireland Assembly passed a motion calling for a moratorium on hydraulic fracking. But no legislation exists to compel a Northern Irish Minister to act upon a moratorium and as the Minister for Enterprise, Trade and Investment has pointed out, no application has been submitted. She will, however, be in a difficult position if one is submitted. It should be noted that hydraulic fracturing has already been used in Fermanagh in 2001, in three tight gas wells.


United Kingdom - General. A more general concern on the part of United Kingdom environmentalists is that development of an extensive low-cost shale gas industry threatens the development of renewable energy within the country, by rendering the latter uneconomic. There is also the argument on the one side that gas provides the most sustainable bridge to a low-carbon future while others see that ready availability of gas will simply result in increasing use of fossil fuel-based energy. As there are divisions even within the British government on these issues we can expect that, in the UK at least, this debate is set to run for some time!

References

- Andrews, I.J., 2013. The Carboniferous Bowland Shale gas study: geology and resource estimation. British Geological Survey for Department of Energy and Climate Change, London, UK.
- Green, C.A., Styles, P. & Baptie, B.J., 2012. Preese Hall shale gas fracturing: review & recommendations for induced seismic mitigation. Department of Energy and Climate Change, April 2012.
- House of Commons Energy and Climate Change Committee, 2011. *Shale Gas*. Fifth Report of Session 2010–12, London, The Stationery Office Limited.
- Lovell, M., Davies, S. & Macquaker, J. 2010. Petrophysics in unconventional gas reservoirs. Presentation at *The Geology of Unconventional Gas Plays*, The Geological Society, London, 5-6 October, 2010.
- Polish Geological Institute – National Research Institute, 2012. Assessment of shale gas and shale oil resources of the Lower Paleozoic Baltic-Podlasie-Lublin Basin in Poland. Warsaw, March 2012.
- Rogner, H-H. 1996. *An assessment of world hydrocarbon resources*, International Institute for Applied Systems Analysis, Working Paper WP-96-056, pp. 44.
- Shaoul, J.R., Spitzer, W. & Dahan, M.W. 2011. Case study of unconventional gas well fracturing in Hungary, SPE Paper 142751.
- Svenska Shell 2011. World Wide Web Address: <http://www.shell.se/home/content/swe/naturgas/>.
- TNO 2009. *Inventory non-conventional gas*. TNO Report TNO-034-UT-2009-00774/B.
- U.S. Energy Information Administration, 2011: *World Shale Gas Resources: An Initial Assessment of 14 Regions Outside the United States*.
- U.S. Energy Information Administration, 2013: *Technically Recoverable Shale Oil and Shale Gas Resources: An Assessment of 137 Shale Formations in 41 Countries Outside the United States*.
- U.S. Geological Survey, 2012. Potential for Technically Recoverable Unconventional Gas and Oil Resources in the Polish-Ukrainian Foredeep, Poland, 2012. Fact Sheet 2012-3102, July 2012.

Appendix 1.

Distribution of known shale gas drilling in Europe. *Base map courtesy of IHS.*



Appendix 2.

Shale gas exploration and appraisal wells drilled in Europe

Geological Province	Sub-Province	Concession	Well Name	No	Operator	Spud	Compl	TD ft	Horiz	Frac	Target Fm	Result - Content
Bulgaria												
Moesian Platform		A-Lovech	Goljamo Peshtene	R-11	LNG Energy	27-Sep-11	End Nov-11 @TD	10,466			Etropole	numerous show s C1 - C3
Moesian Platform		A-Lovech	Deventci	R-2	TransAtlantic Petroleum	27-Oct-11					Etropole	
Germany												
Northw est German Basin	Low er Saxony Basin	Münsterland	Damme	2	ExxonMobil	2008	2008	10,950			Wealden, Posidonia	
Northw est German Basin	Low er Saxony Basin	Münsterland	Damme	2A	ExxonMobil	2008	2008	10,935			Posidonia Shale	
Northw est German Basin	Low er Saxony Basin	Münsterland	Damme	3	ExxonMobil	2008	2008	5,280		3	Wealden	
Northw est German Basin	Low er Saxony Basin	Minden	Oppenw ehe	1	ExxonMobil	Jun-08	2008	8,730			Wealden, Posidonia	
Northw est German Basin	Low er Saxony Basin	Schaumberg	Niedernw öhren	1	ExxonMobil	2009	2009	3,394			Wealden	
Northw est German Basin	Low er Saxony Basin	Scholen-Barenburg II	Schlahe	1	ExxonMobil	2009	2009	4,870			Wealden, Posidonia	
Northw est German Basin	Low er Saxony Basin	Bramschen	Lünne	1	ExxonMobil	17-Jan-11	Mar-11	5,170			Wealden, Posidonia	
Northw est German Basin	Low er Saxony Basin	Bramschen	Lünne	1A	ExxonMobil	Mar-11	2011	5,503	Y		Posidonia Shale	
Poland												
Baltic Depression	Gdansk Depression	Trzebielino	Miszew o	T-1	Indiana Investments (BNK)	28-Feb-12	Sep-12	17,700			Low Paleozoic	Muted gas show s
Baltic Depression	Gdansk Depression	Bytow	Gapow o	B-1	Indiana Investments (BNK)	Mid-late May 12	Jul-12	14,100			Low Paleozoic	Major gas show s
Baltic Depression	Gdansk Depression	Bytow	Gapow o	B-1A	Indiana Investments (BNK)	Mid-Jan 14	23-Feb-14		Y	7 planned	Low Paleozoic	High gas show s
Baltic Depression	Gdansk Depression	Slaw no	Wytow no	S1	Saponis Investments	Dec-10	14-Feb-11	11,750			Low Paleozoic	significant gas show s: C1 - C3
Baltic Depression	Gdansk Depression	Slupsk	Lebork	S1	Saponis Investments	11-Mar-11	25-Apr-11	11,780		Y	Low Paleozoic	significant gas show s: C1 - C3
Baltic Depression	Gdansk Depression	Starogard	Starogard	S1	Saponis Investments	16-Jul-11	Sep-11	11,560			Low Paleozoic	significant gas show s: C1 - C5
Baltic Depression	Gdansk Depression	Lębork	Łebień	LE-1	Lane Energy (3Legs)	Mid Jun-10	28-Jul @ TD	10,120		1; DFIT	Low Paleozoic	gas
Baltic Depression	Gdansk Depression	Lębork	Łebień	LE-2H	Lane Energy (3Legs)	10-May-11	Jun-11		Y	13	Low Paleozoic	gas show s
Baltic Depression	Gdansk Depression	Lębork	Strzeszew o	LE-1	Lane Energy (3Legs)	04-Oct-12	Early Dec-12	10,040		DFIT; 2	Low Paleozoic	
Baltic Depression	Gdansk Depression	Lębork	Lublew o	LEP-1	Lane Energy (3Legs)	13-Dec-13	20-Jan-14	9,593			Low Paleozoic	
Baltic Depression	Gdansk Depression	Lębork	Lublew o	LEP-1ST1H	Lane Energy (3Legs)				Y	20 frac	Sasino Fm	
Baltic Depression	Gdansk Depression	Kaw ia	Slaw oszyno	LEP-1	Lane Energy (3Legs)	15-Feb-14	17-Mar-14	9,250			Low Paleozoic	
Baltic Depression	Gdansk Depression	Cedry Wielkie	Łęgow o	LE-1	Lane Energy (3Legs)	27-Aug-10	Q4-2010	11,270		2 DFITs	Low Paleozoic	gas show s
Baltic Depression	Gdansk Depression	Damnica	Warblino	LE-1H	Lane Energy (3Legs)	17-Jul-11	Sep-11	10,570	Y	7	Low Paleozoic	gas show s
Baltic Depression	Gdansk Depression	Gdansk-W	Lew ino	1G-2	Talisman Energy Polska	26-Sep-11	17-Nov-11	11,800		3	Low Paleozoic	C1+ small C2-C5
Baltic Depression	Gdansk Depression	Elblag	Bagart	1	Eni Polska	01-Dec-11	Mar-12				Low Paleozoic	
Baltic Depression	Gdansk Depression	Elblag	Stare Miasto	1	Eni Polska	Apr-12	Sep-12			Y	Low Paleozoic	
Baltic Depression	Gdansk Depression	Malbork	Kamionka	1	Eni Polska	May-12	Aug-12				Low Paleozoic	
Baltic Depression	Gdansk Depression	Wejherow o	Lubocino	1	PGNIG	Dec-10	Mar-11	11,500		2	Low Paleozoic	promising gas flow . No H2S and low N2. Heavier hydrocarbons
Baltic Depression	Gdansk Depression	Wejherow o	Lubocino	2H	PGNIG	Aug-12	Nov-12		Y	DFIT; frac	Low Paleozoic	
Baltic Depression	Gdansk Depression	Wejherow o	Lubocino	3H	PGNIG	Aug-13	Dec-13		Y		Low Paleozoic	
Baltic Depression	Gdansk Depression	Wejherow o	Opalino	2	PGNIG	Sep-12	Dec-12				Low Paleozoic	flow ed gas
Baltic Depression	Gdansk Depression	Wejherow o	Opalino	3	PGNIG	Nov-13	Jan-14				Low Paleozoic	
Baltic Depression	Gdansk Depression	Wejherow o	Opalino	4	PGNIG	Jan-14					Low Paleozoic	
Baltic Depression	Gdansk Depression	Wejherow o	Tepcz	1	PGNIG	Planned					Low Paleozoic	
Baltic Depression	Gdansk Depression	Stara Kiszew a	Wysin	1	PGNIG	Mar-13	May-13	13,100			Low Paleozoic	
Baltic Depression	Gdansk Depression	Wejherow o	Kochanow o	1	PGNIG	Apr-13	Jul-13	10,650			Low Paleozoic	
Baltic Depression	Gdansk Depression	Kartuzy-Szemud	Borc	1	PGNIG	Jul-13	Sep-13				Low Paleozoic	

Appendix 2 (continued).

Shale gas exploration and appraisal wells drilled in Europe

Geological Province	Sub-Province	Concession	Well Name	No	Operator	Spud	Compl	TD ft	Horiz	Frac	Target Fm	Result - Content
Poland (continued)												
Danish-Polish Marginal Trough	Lublin Trough	Grabowiec	Grabowiec	G6	Chevron Polska	31-Oct-11	Feb-12			DFIT	Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Frampol	Frampol	1	Chevron Polska	Mar-12	Apr-12				Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Zwierzyniec	Zwierzyniec	1	Chevron Polska	Dec-12	Mar-13			DFIT; frac	Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Krasnik	Krasnik	1	Chevron Polska	May-13	Aug-13				Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Chelm	Krupe	1	ExxonMobil E&P Poland	03-Dec-10	Jan-11	12,490		Y	Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Ponki-Kazimierz	Markowola	1	PGNiG	Apr-10	Jun-10			1	Upp Carb	
Danish-Polish Marginal Trough	Lublin Trough	Tomaszów Lubelski	Lubycza Królewska	1	PGNiG	26-Mar-12	Aug-12				Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Wiszniew-Tarnoszyn	Kościaszyn	1	PGNiG	Oct-13	Jan-14				Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Kock-Tarkawica	Wojcieszów	1	PGNiG	Sep-13	Dec-13				Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Wierzbica	Syczyn	OU1	Orlen Upstream	24-Oct-11	Dec-11	9,445			Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Wierzbica	Syczyn	OU2K	Orlen Upstream	24-Sep-12	Early Nov-12	13,450	Y	12	Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Wierzbica	Stręczyn	OU1	Orlen Upstream	22-Feb-13	Apr-13	11,480			Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Wierzbica	Dobryniów	OU1	Orlen Upstream	26-Jun-13	Sep-13				Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Lubartów	Berejów	OU1	Orlen Upstream	Mid Dec-11	Jan-12	8,573			Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Lubartów	Berejów	OU2K	Orlen Upstream	12-Dec-12	Feb-13	12,565	Y	7	Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Lubartów	Uscimów	OU1	Orlen Upstream	May-13	04-Jul-13				Low Paleozoic	
Danish-Polish Marginal Trough	Lublin Trough	Garwolin	Goździk	OU1	Orlen Upstream	16-Jul-12	Oct-12	13,830			Low Paleozoic	
Danish-Polish Marginal Trough	Pomeranian Trough	Rypin	RYP-Lutocin	1	Marathon Oil Poland	Early Apr-12	Jul-12			Y	Low Paleozoic	
Danish-Polish Marginal Trough	Pomeranian Trough	Kwidzyn	KWI-Prabuty	1	Marathon Oil Poland	18-Jul-12	Sep-12			DFIT; frac	Low Paleozoic	
Danish-Polish Marginal Trough	Pomeranian Trough	Brodnica	BRO-NM Lubuskie	1	Marathon Oil Poland	Sep-12	Dec-12			DFIT	Low Paleozoic	
Danish-Polish Marginal Trough	Pomeranian Trough	Szczawno	Szymkowo	1	Talisman Energy Polska	07-Mar-12	Jun-12	14,930	Y		Low Paleozoic	C1 - C3
East European Platform Margin	Podlasie Depression	Minsk Mazowiecki	Siennica	1	ExxonMobil E&P Poland	20-Feb-11	Apr-11			Y	Low Paleozoic	
East European Platform Margin	Podlasie Depression	Siedlce	SIE-Domanice	1	Marathon Oil Poland	Jan-12	Mar-12				Low Paleozoic	
East European Platform Margin	Podlasie Depression	Sokolow Podlaski	SOK - Grębków	1	Marathon Oil Poland	Dec-12	Jan-13				Low Paleozoic	
East European Platform Margin	Podlasie Depression	Wodynie-Lukow	Stoczek	OU1	Orlen Upstream	18-Nov-13	Jan-14	10,300			Low Paleozoic	
East European Platform Margin	Podlasie Depression	Wodynie-Lukow	Stoczek	OU1K	Orlen Upstream	Jan-14	Mid Mar-14	14,130	Y		Silurian	
East European Platform Margin	Volhyno-Podolian Monocline	Orzechow	ORZ-Cycow	1	Marathon Oil Poland	Dec-11	Jan-12			DFIT; frac	Low Paleozoic	
Fore-Sudetic Monocline		Gora	Siciny	2	Gora Energy (San Leon)	10-Nov-11	Mid Feb-12	11,550		DFIT; 2 fracs	Low Carb	C1 - C3

Appendix 2 (continued).

Shale gas exploration and appraisal wells drilled in Europe

Geological Province	Sub-Province	Concession	Well Name	No	Operator	Spudded	Completed	TD ft	Horiz	Fracs	Target Fm	Result - Content
Sweden												
Östergötland Low er Paleozoic		Motala area	5 wells		Aura Energy	Early Oct-11	Q4-2011				Alum Shale	
Östergötland Low er Paleozoic		Ekeby	Brunneby	BY-1	Gripen Energy	Mar-12	Mar-12	282			Alum Shale	w eak flow of flammable gas
Östergötland Low er Paleozoic		Ekeby	Bobergs Häradallmånings	BH-1	Gripen Energy	Mar-12	Mar-12	328			Alum Shale	w eak flow of flammable gas
Östergötland Low er Paleozoic		Ekeby	Rocklunda	RL-1	Gripen Energy	Mar-12	Mar-12	282			Alum Shale	w eak flow of flammable gas
Östergötland Low er Paleozoic		Ekeby	Ekebyborna	GH-2	Gripen Energy	Mar-12	Mar-12	328			Alum Shale	21 Mscfd in 2-hour flow - 97.5% CH4
Östergötland Low er Paleozoic		Ekeby	Ekebyborna	GH-1A	Gripen Energy	Sep-12	Sep-12	300			Alum Shale	strong gas flow
Östergötland Low er Paleozoic		Ekeby	Ekebyborna	GH-2A	Gripen Energy	Sep-12	Sep-12	340			Alum Shale	gas flow
Östergötland Low er Paleozoic		Ekeby	Ekebyborna	GH-3	Gripen Energy	Sep-12	Sep-12	305			Alum Shale	intermittent gas flow
Östergötland Low er Paleozoic		Ekeby	Fossala	FA-2	Gripen Energy	22-Jun-13	28-Jun-13	352			Alum Shale	
Östergötland Low er Paleozoic		Ekeby	Kullen KN-1	GH-5	Gripen Energy	18-Jun-13	24-Jun-13	366			Alum Shale	3.1 Mscfd after 30 minutes
Östergötland Low er Paleozoic		Ekeby	Uddenä	UD-1	Gripen Energy	10-Jun-13	14-Jun-13	355			Alum Shale	no details
Siljan Ring Depression			5 percussion holes		AB Igrene	2009	2009				Low Paleozoic	
Siljan Ring Depression			Mora	001	AB Igrene	2010	2010	-1,650			Low Paleozoic	
Siljan Ring Depression			Solberga	1	AB Igrene	2011	2011	-1,650			Low Paleozoic	
Siljan Ring Depression			Stumshäs	1	AB Igrene	2011	2011	-1,650			Low Paleozoic	
Siljan Ring Depression			Mora	002	AB Igrene	Q2-2013	Q2-2013	1,670			Low Paleozoic	
Siljan Ring Depression			Mora	003	AB Igrene	Q2-2013	Q2-2013	1,450			Low Paleozoic	
Fennoscandian Border Zone	Colonus Shale Trough	Colonussänkan	Lövestad	A3-1	Shell	28-Nov-09		3,134			Alum Shale	
Fennoscandian Border Zone	Colonus Shale Trough	Colonussänkan	Oderup	C4-1	Shell			3,010			Alum Shale	
Fennoscandian Border Zone	Colonus Shale Trough	Colonussänkan	Hedeberga	B2-1	Shell			2,448			Alum Shale	
United Kingdom												
Anglo-Dutch Basin	Cleveland Basin	PL 080	Kirby Misperton	8	Viking UK Gas	06-Jun-13	04-Oct-13	~10,000			Bow land Shale	
Anglo-Dutch Basin	Humber Basin	PEDL 183	Craw berry Hill	1	Rathlin Energy (UK)	15-Apr-14	12-Aug-14	~9,000		DFIT	Bow land Shale	
Anglo-Dutch Basin	Humber Basin	PEDL 183	West New ton	1	Rathlin Energy (UK)	27-Jun-14	06-Sep-14	~10,420		DFIT	Bow land Shale	
Cheshire Basin	Rossendale Basin	PEDL 190	Ince Marshes	1	IGas	04-Nov-11	21-Jan-12	5,174			Bow land Shale	gas indications
Cheshire Basin	Rossendale Basin	PEDL 193	Irlam	1		10-Jan-14					Bow land Shale	
East Irish Sea Basin	West Bow land Basin	PEDL 165	Preese Hall	1	Cuadrilla	16-Aug-10	08-Dec-10	9,098		5	Bow land Shale	substantial gas flow s
East Irish Sea Basin	West Bow land Basin	PEDL 165	Grange Hill	1	Cuadrilla	15-Jan-11	15-Apr-11				Bow land Shale	
East Irish Sea Basin	West Bow land Basin	PEDL 165	Grange Hill	1Z	Cuadrilla	15-Apr-11	Early Aug-11	10,775			Bow land Shale	
East Irish Sea Basin	West Bow land Basin	PEDL 165	Becconsall	1	Cuadrilla	23-Aug-11	13-Oct-11				Bow land Shale	
East Irish Sea Basin	West Bow land Basin	PEDL 165	Becconsall	1Z	Cuadrilla	13-Oct-11	21-Dec-11	10,500			Bow land Shale	
East Irish Sea Basin	West Bow land Basin	PEDL 165	Anna's Road	1	Cuadrilla	06-Oct-12	21-Nov-13	2,000			Bow land Shale	Junked & Abandoned
Midland Valley of Scotland	Kincardine Basin	PEDL 133	Airth	6	Composite Energy	15-Oct-05	05-Dec-05	3,524			Black Metals M.B.	
Midland Valley of Scotland	Kincardine Basin	PEDL 133	Longannet	1	Composite Energy	16-Feb-07	29-Apr-07				Black Metals M.B.	
Midland Valley of Scotland	Kincardine Basin	PEDL 133	Bandeath	1	Composite Energy	15-May-07	18-Jun-07				Black Metals M.B.	
South Wales Carboniferous		PEDL 148	Banw en	1	UK Methane	07-Sep-11	16-Sep-11				Aberkenfig?	
South Wales Carboniferous		PEDL 149	St Johns	1	UK Methane	26-Aug-11	23-Mar-12				Aberkenfig?	

Appendix 3.

Selected companies with potential interest in shale gas exploration in Europe, by country.

Country	Companies
Austria	OMV
Bulgaria	Chevron; Transatlantic Petroleum / Esrey Energy
Croatia	INA-MOL
Czech Republic	Applications: Cuadrilla Resources; Hutton Energy
Denmark	Total / Danish North Sea Fund (Nordsøfonden)
France	No valid permits as a result of moratorium on hydraulic fracturing: at 28 Feb 2014, there were 110 outstanding permit applications (many overlapping) from multiple companies.
Germany	BNK Petroleum; Dart Energy; ExxonMobil / Shell (BEB); Rose Petroleum; San Leon; Wintershall
Ireland	Enegi Oil; Tamboran Resources
Italy	Independent Resources plc
Lithuania	Chevron (through LL Investicijos)
Netherlands	Cuadrilla Resources / EBN; Hutton Energy
Poland	3Legs Resources; BNK Petroleum; CalEnergy Resources; Canadian International Oil Corp; Chevron Corp; ConocoPhillips; Cuadrilla Resources; Eni; Esrey Energy; EurEnergy Resources; Greenpark; Hutton Energy; LOTOS Petrobaltic; Mac Oil; Marathon; Mitsui; Nexen; PETROLINVEST; PGNiG; PKN Orlen; RAG; San Leon; Sorgenia; Total SA
Romania	Chevron; TransAtlantic Petroleum / Sterling Resources
Spain	BNK Petroleum; Leni Gas & Oil; Repsol; San Leon; Schuepbach Energy; Sociedad de Hidrocarburos de Euskadi (SHESA); Vancast Exploración
Sweden	Aura Energy; AB Igrene; Gripen Oil & Gas AB; Tekniska Verken i Linköping AB
Switzerland	Schuepbach Energy
United Kingdom	Centrica; Coastal Oil & Gas; Cuadrilla Resources; Dart Energy; eCORP; Eden Energy; Egdon Resources; GDF Suez; IGas; Tamboran Resources; Total; UK Methane
Certain of the companies listed have indicated their intention to exit shale gas exploration in the country indicated but retained their interest at the time of compilation of the table.	

China Shale Gas and Shale Oil

By Shu Jiang (University of Utah, Energy & Geoscience Institute, Salt Lake City, Utah 84108 USA)

The shales spanning from Pre-Cambrian Sinian (a period right before Cambrian) to Quaternary are widely distributed in China. The Pre-Cambrian to Upper Paleozoic organic rich shales with maturity in gas window and shallow Quaternary shales have shale gas potentials and Mesozoic to Cenozoic organic rich

shales with maturity in oil window have shale gas potentials (Fig.1). In 2010, The Strategic Research Center of Oil and Gas, Ministry of Land and Resources and China University of Geosciences at Beijing used an analog assessment regime to announce that China Shale Gas resource is predicted to be about 30 BCM (1050 TCF). In 2011, the US Energy Information Administration (EIA) assessed that China could have 1275 trillion cubic feet (TCF) technically recoverable shale gas, in March 2012, China Ministry of Land and Resources announced China had 25.08 trillion cubic meters (886 TCF) of recoverable onshore shale gas reserve. Recently, EIA reduced China recoverable shale gas reserve to 1115 TCF in June 2013 and gave a number of 32 Billion Barrel recoverable shale oil for China. Either number indicates China's shale resource is comparable with US's updated 665 TCF recoverable shale gas and 58 billion barrels of shale oil resource. One recent breakthrough is that China is the only country outside of North America that has reported commercially viable production of shale gas based on the latest commercial quantity shale gas production reported from Sichuan Basin by Sinopec and PetroChina, although the volumes contribute less than 1% of the total natural gas production in China. In comparison, the shale gas as a share of total natural gas production in 2012 was 39% in the United States and 15% in Canada (EIA, Oct 2013). The successful development evidence in Sichuan Basin especially in Fuling area recently makes the China's 2015 output target of 6.5 bcm possible, which was thought impossible before last month. This will encourage Beijing government and draw interests of international oil companies.




Fig. 1 The distribution of potential major China shale gas and shale oil plays.

For US producing shales, they were deposited marine depositional setting. But for hydrocarbon related shales in China were formed in diverse paleo-environments. The Pre-Cambrian to Lower Paleozoic shales distributed all over China were deposited in marine setting. The Upper Paleozoic (Carboniferous to Permian) shales mainly in North China and NW China were deposited in transitional (coastal swamp associated with coal) setting. The Meso-Cenozoic sporadically distributed shales were deposited in lacustrine setting (Fig.2). The typical marine shale, transitional shale and lacustrine shale can be represented by Lower Paleozoic Sichuan Basin, Carboniferous to Permian Ordos Basin and Cenozoic Bohai Bay Basin respectively (Fig.3). The Table 1 summarizes the depositional settings and distribution in time and space for the potential gas and oil shales in China.

Table 1 Depositional setting and distribution in time and space of potential China shales

Depositional setting	Age and Formation		Distribution area
Lacustrine	Cenozoic	Neogene	Qaidam Basin
		Paleogene	Bohai Bay Basin, Qaidam Basin
	Mesozoic	Cretaceous	Songliao Basin
		Jurassic	Turpan-Hami, Junggar, Tarim, Qaidam, Sichuan Basin
		Triassic	Ordos Basin, Sichuan Basin
	Paleozoic	Late Permian	Junggar, Turpan-Hami
Transitional (coastal setting associated with coal)	Paleozoic	Late Permian (Longtan Fm)	Yangtze Platform including Sichuan in Upper Yangtze
		Early Permian (Taiyuan, Shanxi Fm)	North China
		Late Carboniferous (Benxi Fm)	North China
Marine	Paleozoic	Early Silurian (Longmaxi Fm)	Yangtze Platform including Sichuan in Upper Yangtze
		Late Ordovician (Wufeng Fm)	Yangtze Platform including Sichuan in Upper Yangtze, Tarim Basin
		Early Cambrian (e.g. Qiongzhusi Fm)	Yangtze Platform, Tarim Basin
	Pre-Cambrian	Sinian (e.g. Doushantuo Fm)	Upper and Middle Yangtze Platform




Fig. 2 the shale exploration activities in China




Fig.3 Three kinds of potential shales (marine, lacustrine and transitional/coastal setting) and their type basins

China has investigated shale gas and shale oil for nearly 6 years. So far, 2013, 2D seismic data covering 9000 km² and 3D seismic data covering 800 km² were acquired, and 150 shale gas wells (including shallow parameter wells behind outcrop) targeting marine, lacustrine and transitional (coastal swamp setting associated with coal) shales were drilled so far by the PetroChina, Sinopec, CNOOC, Yangchang Petroleum, other state or private companies who recently got shale blocks, Ministry of Land and Resources and foreign partners of Chinese state oil companies. The exploration activities have been mainly focused in Sichuan

Basin, Yangtze Platform outside Sichuan Basin, Ordos Basin, Bohai Bay Basin and Nanxiang Basin (Fig.2). Recently, the Junggar basin has also become target basin for shale oil associated with tight dolomite oil play. So far, almost half of drilled shale wells have good shale gas and shale oil show. Among 30 horizontal wells, several wells were reported very successful based on test results rate of over 100,000 cubic meters daily production. The rate from well Yang201-H2 in Luzhu, Sichuan was reported to produce at 430,000 cubic meters per day and recently a well in Fuling area in E Chongqing was reported to produce 547,000 cubic meters/day. Sinopec drilled 30 shale gas wells in Fuling pilot area and 6 wells were reported to have high rate commercial production with average 180,000 cubic meters/well. Sinopec claimed the 2015 output target in Fuling area will be doubled based on recently encouraging results. For lacustrine shales, PetroChina and Sinopec recently speeded up lacustrine shale oil exploration in Junggar and Sichuan Basin, e.g. Sinopec drilled Shiping 2-1H horizontal wells targeting Jurassic lacustrine shale and got 33.79 tons condensate production after 5 stages fracturing in 864 m lateral.

Geological investigation and exploration show that most potential shales in China had and still have high organic content and marine shales have high maturity for gas generation and lacustrine (lake) shales have low maturity for oil generation. Characteristics of high organic matter content, high maturity, high brittle minerals (Fig.4) and high intra-organic nano-porosity (Fig.5) make China marine shales same to US shales and potentially producible. The drilled shale gas wells targeting marine shale in Sichuan Basin show the similar favorable shale properties e.g. high TOC, high brittleness, etc. as US producing marine shales (Fig.6). Generally, China lacustrine shales have high clay content than marine shales (Fig.4), this is why many experts think it is much more difficult to frac the lacustrine shale. Since lacustrine basins contribute 90% oil production in China and they are expected to play a more significant role in shale oil production, we need new technologies to develop the gas or oil trapped in lacustrine shales. Recently, the tight dolomite oil production from Permian source rock interval in Junggar Basin in NW China (Fig.7) and tight sand oil from Ordos Basin (Fig.8) in North China showed the potentials of lacustrine tight oil potential similar to Bakken shale oil which is mainly produced from middle Bakken dolomite equivalent tight reservoirs. But the oil production from lacustrine shale is still in early stage. In the future, the shale gas and shale oil and tight sand and tight carbonate reservoirs within the organic rich shale could consist of hybrid reservoirs (e.g. shale oil and tight sand oil in Triassic source rock interval in Ordos Basin, Fig.8).




Fig.4 Ternary diagram for mineralogy of marine shale (square legend) and lacustrine shale (triangle legend) in China and its comparison with mineralogy of typical US shales.




Fig.5 SEM of ion polished sample showing intra-organic nano-pores of a marine shale Sichuan Basin, China





Fig.6 Typical shale gas well in Sichuan Basin for marine shale gas



Comprehensive well logging evaluation chart of the Lucaogou Formation reservoir in the Jimsar Sag. d_h —hole diameter; instantaneous potential; GR —gamma ray; R_t —resistivity of intrusion zone; R_c —formation resistivity; ρ —density; Δt —interval transit time; ϕ_n —neutron porosity; AI —acoustic impedance.

Fig.7 Tight dolomite oil from Permian source rock interval with shale oil show, Junggar Basin, NW China (L. Kuang, 2012)

What made shale gas or shale oil work is hydraulic fracturing or fracing, but every shale in the world is different, the shale depositional settings and geologic history made each shale with unique mechanical property. Shale gas and shale oil are produced from marine shales, fine-grained chalks and dolomite interbedded in source rock intervals in US basins. These basins have relatively simple tectonic settings than China. Even promising marine shales in China are similar to brittle Barnett shale in US regarding mineralogy, the complex tectonic setting, much more complex diagenetic history and harsh ground conditions make shale gas extracting in China more challenging than that in US. In some areas in China, the shale resources are either located in the subsurface below the rugged mountain or desert, also, the historical multi-stages of strong tectonic compression, extension in China cause shales in China have different stress fields than those in US, e.g. the maximum principal stress is horizontal in some areas in China and the maximum principal stress is vertical in US, this is why the fracing experiences in US may not

work very well in China. We need investigate more about the geology, geomechanics and hydraulic fracturing design for unique China shales.




Fig. 8 Tight oil and potential shale oil of Triassic Yanchang Fm in Ordos Basin (modified from YAO Jingli, 2013)

Since shale gas exploration and production is technically challenging and China basins have complex tectonic activities and different properties for shales, China has been collaborating with international oil firms and service companies to achieve the ambitious shale gas production plan. Chinese state-owned oil, coal and power energy companies and privately-owned junior companies with non energy experience have tied up with foreign oil companies such as Shell, ExxonMobil, Chevron, ConocoPhillips, Eni, BP, Total, Statoil, Schlumberger, etc. to gain hydraulic fracturing technology in shales. Even though the recent 2nd round bidding blocks located at the margin or outside conventional oil and gas producing basins disappointed many companies. With the speeding and recent good exploration result of Paleozoic marine shale gas exploration and Meso-Cenozoic lacustrine shale oil exploration and very exciting test result in Sichuan Basin, Shell’s production-sharing contract with CNPC (parent company of PetroChina) got approved by Chinese government and Hess signed PSC with CNPC in Langma shale oil block in NW China recently, which are inspiring for many companies. Shell will spend \$1 billion developing China’s shale resources in Fushun-Yongchuan block covering 3,500 sq km in Sichuan Basin. PetroChina plans to drill 113 horizontal shale gas development wells in the next 2 years in Sichuan Basin. Sinopec has planned to drill more in SE Chongqing/E Sichuan Basin and NE Sichuan Basin due to recently commercial shale gas from both marine and lacustrine shales in Sichuan Basin. Based on these, the coming third shale gas bid round will be better than the first two.

The complex geologic setting and different geomechanics regime in China basins did challenge many international companies with successful US shale experiences to frack shales in China. The trial-and-error in the in pilot shale gas areas in Changning-Weiyuan in Sichuan, Fuling in Chongqing, Yanchang block in Ordos has helped companies know better and better to frack shales in China. With limited participation from established global service companies such as Baker Hughes and [Schlumberger](#), Sinopec's

Jiangnan oilfield has improved in key areas of fracturing and logging. At one well in Sichuan Basin, Sinopec-Jiangnan did 22-stage fracturing at a depth of 1,500 meters and the test result showed commercial flow of shale gas. So far, the horizontal drilling and hydraulic fracturing of shales have been reported to generate large stimulated reservoir volume (SRV) (Fig.9)




Fig. 9 Horizontal drilling and hydraulic fracturing for both marine and lacustrine shales in China

At the same time, The China National Energy Administration (“NEA”) issued the Shale Gas Industry Policy (“Policy”) in late October, 2013. The Policy recommends certain reforms to encourage more companies besides oil companies to get access to shale gas exploration and development in China. Also, the new policy gives subsidies and tax incentives to shale gas production companies.

In summary, China has huge potential for both shale gas and shale oil potential, even though the geological setting and geomechanics regime are more complex than US producing shales for hydraulic fracturing, with the learning curve for the lacustrine shale gas in Ordos Basin and shale oil in Nanxiang Basin in central China and tight/shale oil in Santanhu and Junngar Basin in Northwest China, and recent commercial shale gas flow from marine in Sichuan Basin by PetroChina and Sinopec, technology advancement and policy support for incentives and reforms from Chinese government, China has commercially produced 200 million cubic meters in 2013 from pilot areas and the China vast shale resources are expected to be produced on a large scale.

Valuable links

Maps

- Active Shale Gas Plays, lower 48 http://www.eia.gov/oil_gas/rpd/shale_gas.pdf
- Various shale gas plays (Barnett, Fayetteville, Haynesville-Bossier, Marcellus, Woodford) and shale oil (Bakken). http://www.eia.gov/pub/oil_gas/natural_gas/analysis_publications/maps/maps.htm

Assessments

- Assessments of undiscovered oil and gas resources, onshore US <http://energy.cr.usgs.gov/oilgas/noga/>
- Assessments of undiscovered oil and gas resources, World <http://certmapper.cr.usgs.gov/rooms/we/index.jsp>
- Assessment of Australian energy resources https://www.ga.gov.au/image_cache/GA17412.pdf
(courtesy of Gesocience Australia)

Consortia

- Core Lab “Reservoir characterization and production properties of gas shales”
(http://www.corelab.com/rm/irs/studies/GasShales_Global.aspx);
- “Haynesville and Bossier Shale Evaluation” (<http://www.corelab.com/rm/irs/studies/Haynesville-Bossier.aspx>);
- “Eagle Ford Shale Study”
(<http://www.corelab.com/rm/irs/studies/EagleFord.aspx>);
- “Montney Shale Regional Study”
(<http://www.corelab.com/rm/irs/studies/MontneyShale.aspx>);
- “Global Gas Shales Study”
(http://www.corelab.com/rm/irs/studies/GasShales_Global.aspx)
- Colorado School of Mines FAST (Fracturing, Acidizing, Stimulation Technology) Consortium Project 9: stimulation of “shale” reservoirs (<http://www.mines.edu/fast/>).
- Humble Geochemical Services (<http://www.humble-inc.com/>)
<http://www.humble-inc.com/PlayTypes/ShaleGas/tabid/102/Default.aspx>
- GeoMark Research
 - Appalachian Basin Shale Gas Study (2005)
(http://www.geomarkresearch.com/studies_northamerica.cfm)
- Baseline Resolution (<http://brilabs.com/>)
 - Geochemistry Studies (http://brilabs.com/contents/basin_studies2.htm)
- GASH (Gas Shales in Europe)
 - ([http://www.gfz-potsdam.de/portal/-;jsessionid=7BA522526C3C6B6F7C57E0E6A3579326?\\$part=binary-content&id=2022464&status=300&language=en](http://www.gfz-potsdam.de/portal/-;jsessionid=7BA522526C3C6B6F7C57E0E6A3579326?$part=binary-content&id=2022464&status=300&language=en))
- GeoEn (Germany) <http://www.geoen.de/index.php/shale-gas.html>

- CSIRO Shale Research Centre (<http://www.csiro.au/science/shaleResearchCentre.html>)
- PTTC Unconventional Tech Center http://www.pttc.org/tech_centers/unconventional_resources.htm)

Additional Sources of Information

- **References** (see gas shale bibliography on Gas Shale Committee web site) (http://emd.aapg.org/members_only/gas_shales/gasshalereferences.pdf)
- **Trade Journals** (articles included in bibliography above)
 - Powell Barnett Shale Newsletter (<http://www.barnettshalenews.com/>)
 - American Oil and Gas Reporter (<http://www.aogr.com/>)
 - Oil and Gas Investor (<http://www.oilandgasinvestor.com/>)
 - Oil and Gas Journal (<http://www.ogj.com/index.html>)
 - Hart's E & P (<http://www.epmag.com/>)
 - AAPG Explorer (<http://www.aapg.org/explorer/>)
- **Subscription Services**
 - Hart Unconventional Natural Gas Report (<http://www.ugcenter.com/>)
 - IHS Energy (<http://energy.ihs.com/>)
 - Warlick International Report (<http://warlickenergy.com/>)
- **Hydraulic Fracturing**
 - <http://www.strongerinc.org/>

Gas Shales and Shale Oil Calendar

2014

April 6-9, 2014: AAPG Annual Convention & Exhibition, Houston, TX.
<http://www.aapg.org/houston2014/>

April 23-24, 2014: Emerging Unconventional Plays Latin America, Cartagena, Colombia. American Business Conferences. <http://emerging-shale-plays-latin-america.com>

May 20-22, 2014: DUG Permian Basin, Fort Worth, TX. Hart Energy. <http://www.dugpermian.com/>

May 28-29, 2014: Emerging Shale Plays USA 2014, Houston, TX. American Business Conferences. <http://www.emerging-shale-plays-usa-2014.com/>

May 28-29, 2014: Bakken & Three Forks Completions & Well Spacing 2014. Denver, CO. American Business Conferences. <http://www.bakken-completions-2014.com/>

May 29, 2014: Woodford Shale Forum, Oklahoma City, OK. AAPG Forum.
<http://www.aapg.org/career/training/in-person/forums>

June 3-5, 2014: DUG East, Pittsburgh, PA. <http://www.dugeast.com/>

June 24-25, 2014: Woodford SCOOP Development and Exploration Summit, Oklahoma City, OK.
(South Central Oklahoma Oil Province) Infocast.

June 24-26, 2014: Marcellus and Utica Point Pleasant Geosciences Technology Workshop, Pittsburgh, PA. AAPG. <http://www.aapg.org/career/training/in-person/workshops>

August 25-27, 2014: Unconventional Resources Technology Conference, SPE, AAPG, SEG. Denver, CO. <http://www.urtec.org/>

August 26-28, 2014: DUG Australia, Brisbane, QLD, Australia. <http://www.dugaustralia.com/>

September 15-17, 2014: DUG Eagle Ford, San Antonio, TX. <http://www.dugeagleford.com/>

September 21-24, 2014: Second EAGE/SPE/AAPG Shale Gas Workshop in the Middle East, Dubai, United Arab Emirates. <http://eage.org/events/index.php?evp=12848&ActiveMenu=2>